

64 Well Files - EPU 80-D

East Poplar Oil Field  
Enforcement Case

Release in  
Full

Region 8



13678



PRODUCTION DEPT  
FILE COPY

EAST POPLAR UNIT WELL NO. 80

ROOSEVELT COUNTY, MONTANA

MURPHY CORPORATION--OPERATOR

EPA SWD #3  
WU #80

EPA ID# MTS21PE -0026  
MTS2026-0026



EAST POPLAR UNIT WELL NO. 80

ROOSEVELT COUNTY, MONTANA

MURPHY CORPORATION--OPERATOR

HISTORY-----	Page 1
COMPLETION DATA-----	Page 2
ELECTRO LOG DATA-----	Page 3
DRILL STEM TEST RECORD-----	Page 4
CORE ANALYSIS REPORT-----	Page 5
CORE DESCRIPTION-----	Page 6
MUD PROGRAM SUMMARY-----	Page 7
DRILLING BIT & TOTCO RECORDS & DIAMOND CORE BIT RECORDS-----	Page 8
SAMPLE DESCRIPTION-----	Page 9

=====

W E L L H I S T O R Y

=====

WELL NO.: East Poplar Unit No. 80

LOCATION: SW NW Section 3, Township 28 North, Range 51 East

ELEVATION: 2059' Gr. - 2069' K.B.

DRLG. CONTRACTOR: Zach Brooks Drilling Co.

STARTED: 5:00 P.M., July 2, 1956. Rig released 6:30 P.M., July 26, 1956

COMP. CONTRACTOR: Western Oil Well Service Co.

COMPLETED: July 29, 1956

TOTAL DEPTH: 5823' Driller equals 5832' Schlumberger

CASING: 13 3/8" @ 161.39 with 175 sacks cement  
9 5/8" @ 980.68 with 400 sacks cement  
5 1/2" @ 5831.00 with 300 sacks cement

TUBING: 2 3/8" @ 5483.85'

PERFORATIONS: "A-1" Zone from 5456'-5474'

PACKER: None

ACID TREATMENT: "A-1" Zone - 500 gallons etching acid

INITIAL POTENTIAL: Pumping on 6-hour test through treater. 173 BFPD, 28% water (125 BOPD, 48 BFPD).

TYPE COMPLETION: Single Producer in the "A-1" Zone

OK  
Mick

EAST POPLAR UNIT NO. 80-D

WELL HISTORY SUPPLEMENT

5-3-68 Moved in and rigged up pulling unit.

5-4-68 Laid down 3-1/2", 9.20#, J-55, internally coated tubing. Found 1 hole approximately 1" in diameter in 6th joint from top. The top 10 jts. had threads eaten and washed out. Packer was in set position and appeared to be in good condition. Ran 2-7/8" fiberglass tubing as follows:

1 3-1/2" O.D. 9.20#, J-55, Steel Non-EUE 10rd. thd. top X 8rd. thd. btm. internally plastic coated nipple.	10.70
1 3-1/2" 8rd. Non-EUE Steel Collar - Internally coated with plastic and doped internally with Epoxy	.35
1 3-1/2" 8rd. Non-EUE X 2-7/8" 8rd. EUE Fiberglass Change-Over nipple with I.D. of 1.90"	.30
107 jts. 2-7/8" Rock Island Fiberglass Tubing, 1.375/ft., 8rd. EUE, medium heavy service, 1200# W.P.	3192.56
	<u>3203.91</u>
Below RKB	6.50
Landed At	3210.41

Injection pressure with 3-1/2" O.D. Steel tubing was 235 PSI. Injection pressure with 2-7/8" Fiberglass tubing (through 1.90" I.D. Change-over nipple) is 400 PSI.

Started injection-through 2-7/8" fiberglass tubing 5-4-68.

SUPPLEMENT TO WELL HISTORY

EAST POPLAR UNIT NO. 80-D

JUSTIFICATION FOR WORKOVER:

Injection pressure increased too 600 PSI. Pump operating 24 hrs. per day to dispose of produced salt water. Acidized Dakota Sand perforations at 3218-3250', 3462-3512', and 3284-3410' to break any possible block in the perforations on the formation.

8-24-71 Acidized disposal well with 1500 gallons Dowell 15% HCL acid (15 XF) with 9 gallons A-160 inhibitor, and 8 gallons F-40, surface tension lowering agent. Injected acid into tubing at the rate of 2 BPM - 375 PSI and flushed with 2 bbls. salt water to clear pump and lines. Hooked up flowline and started injection pump. Pumped acid away and left station in operation.

Injection Pressure Before Acid Job	600 PSI
Injection Pressure After Acid Job	420 PSI

Pump operating approximately 18 hrs. per day.

EAST POPLAR UNIT NO. 80-D

SUPPLEMENT TO WELL HISTORY

10-2-71 This well was acidized with 2000 gallons of 28% HCL with inhibitor added, as follows:

Fifty bbls. of fresh water was injected ahead of 2000 gallons of acid and followed with 10 bbls. of fresh water. Injections rate was 2 BPM at 400 PSI. ISI was 0 PSI. Injection pump was then started to displace the acid into the formation.

Pressure Prior To Job	=	580 PSI
Pressure After Job	=	440 PSI

Injection pump went down 1 time more than usual on low water level over the past 24 hours.

EAST POPLAR UNIT NO. 80-D

SUPPLEMENT NO. 8

- 8-2-84      Move in rug up pulling unit.
- 8-3-84      Kill well with 10.1# water. Pump 35 barrels down tubing and 60 barrels down casing. Strip out of hole fiberglass tubing, couldn't unscrew tubing. Hack sawed tubing off in 60 joints. Pick up 6 joints tubing and  $2\frac{1}{2} \times 5\frac{1}{2}$  arrow set packer. Run 95 joints tubing coated internally with tube coat T-K 77. Circulate packer fluid down casing. Set packer, put well into production.

EAST POPLAR UNIT NO 80-D

SUPPLEMENT TO WELL HISTORY

September 10, 1998

Wait on truck to kill well. Rig up workover rig. Larkin nut on well head tight, get off, release packer, pull and tally tubing. Cap well off for night.

September 11, 1998

Hydrotest tubing into hole. Set packer and flange up well head. Found hole at 2883' and replaced 2 joints of 2-7/8" tubing. 95 joints tubing in the hole.

Perform Mechanical Integrity Test on well. Held pressure for 45 minutes. Well passed test.

EAST POPLAR UNIT NO. 80-D

- 5-4-99      *Unset packer and pull tubing out of the hole.*
- 5-5-99      *Hydrotest tubing, leaks at 31', 62', 93', 124', 155', and 217', set packer (Arrow Set with 10,000# set down). Fill backside, pressure up to 500 psi, held pressure OK. Also changed 1 collar*





Rec. Prod.

APR 3 1986

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

ONE DENVER PLACE — 999 18TH STREET — SUITE 1300

DENVER, COLORADO 80202-2413

MAR 27 1986

REF: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Al Simpson  
Murphy Oil Corp.  
200 Peach Street  
El Dorado, Arkansas 71730

RE: UIC Final Permit  
EPA # MTS21PE-0026  
Well # EPU 80-D

Dear Mr. Simpson:

Enclosed is the Final Underground Injection Control Permit for the EPU 80-D well defined in your application referenced above. This well is located in the East Poplar Field, Roosevelt County, Montana.

The public comment period closed on February 21, 1986. The only comments received on the draft action were from Murphy Oil. All comments have been addressed and responses to specific comments may be found in the enclosed Responsiveness Summary. Please be aware that this permit becomes effective thirty days after the date of issuance and will remain effective for the life of the well, unless terminated. EPA will review this permit at least every five years.

If you have any questions please refer them to Angus M. Campbell at (303) 293-1420 or write to him at the above address.

Sincerely,

*Max H. Dodson*  
Max H. Dodson, Director  
Water Management Division

Enclosures

EPU SWD #80

Flow Analyzer Model MC-II

Analyzer Serial #129641

Flow Meter Serial #15ST-34027

1 1/2"



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

FEB 6 1989

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

Re: UNDERGROUND INJECTION CONTROL (UIC)  
EPA Permit #MTS2026-0026  
Murphy East Poplar Unit No. 80-D ✓  
SWNW Section 3-T28N-R51E  
Roosevelt County, Montana

Dear Mr. Reede:

Your December 27, 1988 request for reducing the frequency of injected fluid analyses submissions for the referenced salt water disposal well is denied. This decision is based on Murphy Oil's failure to provide this office with four (4) consecutive quarterly chemical analyses of injected fluids for the East Poplar Unit No. 80-D.

We are currently in receipt of a chemical analysis dated November 29, 1988 for the East Poplar Unit No. 80-D. We will accept this November 29, 1988 chemical analysis as the first of four (4) consecutive quarterly fluid analyses as required by EPA Permit #MTS2026-0026. You may re-apply for the reduction of frequency in October 1989.

If you have any questions relative to this decision, please contact Emmett Schmitz at (303) 293-1717.

Sincerely

Max H. Dodson  
Director  
Water Management Division

**MURPHY**  
OIL CORPORATION

INTER-OFFICE CORRESPONDENCE

FROM: W. G. Brown

LOC.: Poplar-P&E

DATE: June 19, 1972

TO: A. W. Simpson

LOC.: El Dorado-P&E

CARBONS TO: File

SUBJECT: Wells Temporarily Abandoned

C  
O  
P  
Y

Enclosed you will find a list of wells in the East Poplar Unit that have been temporarily abandoned. Two, East Poplar Unit No. 8 and 89, of these wells should remain in the T.A. state in order to facilitate a salt water disposal system in the future if needed. The other wells will have to be plugged and cleaned up at some future date so this should be done while the company has an income in this area.

An A.F.E. is in to convert number 8 into a disposal well to take care of four South end batteries (D, R, K & H). East Poplar Unit No. 80-D would take care of the water from A, C, F, and G as it does now. In the event a high fluid withdrawal system is installed at East Poplar Unit No. 88 a disposal well may be needed at EPU "Q" battery, this would mean East Poplar Unit No. 89 would have to be made into a disposal well. Batteries B, E, I, J, L, M, N and P are being handled by East Poplar Unit No. 1-D. Number 2 salt water station could be reactivated if need be as the lines and wells are still intact.

From the above I don't believe any additional wells would be required for salt water disposal facilities other than the two mentioned. Unless your office or the engineering department has some use for these wells I believe they should be P&A'd and the locations cleaned up.

To the best of our knowledge the enclosed list is correct. Please advise as to your feelings on getting this work taken care of and I will proceed accordingly.

  
W. G. Brown

WGB/sb  
enclosure



## United States Department of the Interior

GEOLOGICAL SURVEY  
Conservation Division  
P.O. Box 2550  
Billings, Montana 59103

March 29, 1977

Murphy Oil Corporation  
P.O. Box 547  
Poplar, Montana 59255

Re: NTL-2B Approval for Salt Water Disposal Wells in the Northeast Benrud Field, East Benrud Field, Volt Field and East Poplar Field, Roosevelt County, Montana

Gentlemen:

We have reviewed your applications concerning approval of the numerous disposal wells. Your applications meet the regulations required under NTL-2B, and approval is hereby given for the following disposal wells:

Mule Creek Allotted No.1-D, Fort Peck (Allotted) 35-009, SW SE, Sec. 20-31N-48E, 928' FSL and 2078' FEL, Northeast Benrud Field;

Wetsit No.1-D, Fort Peck (Allotted) 35-072, SW, Sec. 36-31N-47E, 1740' FSL and 1740' FWL, East Benrud Field;

Courchene No.1-D, Fort Peck (Allotted) 35-035, SE SW, Sec. 4-30N-46E, 801' FSL and 2034' FWL, Volt Field;

East Poplar Unit No.1-D, (Klies) #6104, SE SE SE, Sec. 30-29N-51E, East Poplar Field;

East Poplar Unit No.80-D, I-37-IND-12914, SW NW, Sec. 3-28N-51E, 1982' FNL and 761' FWL, East Poplar Field;

East Poplar Unit No.8-D, Fort Peck (Allotted) ---Patented, C NW SE, Sec. 10-28N-51E, 1980' FSL and 1980' FEL, East Poplar Field;

East Poplar Unit No.5-D, I-37-IND-12856, SE SE, Sec. 19-29N-51E, 1205' FSL and 660' FEL, East Poplar Field.

However, approval of the emergency pits that you are requesting cannot be given at this time. Each pit will be inspected individually by a staff member of this office. At the time of this inspection, each pit will be checked to see if it meets the criteria as stated under the section of NTL-2B that deals with emergency pits. We would like to remind you that all emergency pits are to be emptied of all fluids within 48 hours following their use. Each emergency use of the pits is to be reported to this office and approval is needed for the method of disposing of the fluid. Inspection of these pits will take place within 30 days. Also an emergency pit cannot be used as a trash pit.

Sincerely yours,

Virgil L. Pauli  
District Engineer



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

December 15, 1989

Mr. Max H. Dodson  
Director, Water Management Division  
United States Environmental Protection Agency  
Region VIII  
999 18th Street - Suite 500  
Denver, Colorado 80202-2405

RE: UIC Permit #MTS2026-0026  
East Poplar Unit No. 80-D

Dear Mr. Dodson:

Enclosed are four (4) consecutive quarterly water analyses for the East Poplar Unit 80-D, SW NW Section 3, T28N, R51E, Roosevelt County, Montana.

At this time we request a minor permit modification to reduce the frequency of water analysis to once per year to be submitted in the fourth quarter.

Sincerely,

  
Raymond Reede  
District Manager

RR/jh

cc: A.W. Simpson  
C.J. Boyter, Montana Operations  
well file





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

JAN 25 1990

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
Post Office Box 547  
Poplar, Montana 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
Monitoring of Injection Fluids  
Salt Water Disposal Wells  
Roosevelt County, Montana


Dear Mr. Reede:

In response to your recent requests to reduce the frequency of injection fluid analyses for the wells listed below, approval is hereby granted to submit fluid analyses annually, instead of on a quarterly basis. The only exception to this requirement is when there is a change in the source of injection fluids, in which case a water analysis is to be submitted to the Director within thirty (30) days.

<u>WELL</u>	<u>EPA PERMIT NO.</u>
Goings Government 1-D	MTS2008-0008
✓ East Poplar Unit 80-D	MTS2026-0026
East Poplar Unit 8-D	MTS2023-0023
East Poplar Unit 1-D	MTS2022-0022
East Poplar Unit 5-D	MTS2021-0021
Lillian 1-D	MTS2035-0046

If you have any questions concerning this letter, you may contact John Carson at (303) 293-1435. Also, please direct all correspondence to the attention of John Carson at Mail Code 8WM-DW.

Sincerely,

  
Max H. Dodson  
Director  
Water Management Division

cc: Jim Boyter  
Montana Office



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

December 31, 1990

Max H. Dodson, Director  
Water Management Division  
United States Environmental Agency  
Region VIII - Suite 500  
999 18th Street  
Denver, CO 80202-2405

RE: Water Analyses for SWD

Dear Mr. Dodson:

Enclosed are the water analyses on the following salt water disposal wells:

East Poplar Unit 1-D	MTS2022-0022
East Poplar Unit 5-D	MTS2021-0021
East Poplar Unit 8-D	MTS2023-0023
East Poplar Unit 80-D	MTS2026-0026
Sletvold B-1	MTS2036-0047
-D	MTS2035-0046
D	MTS2302-0612
2-D	MTS2398-1768

*Injector profile  
on Tower 1000 ft*

*2902  
701-842-2902*

Sincerely,

*Raymond D. Reede*  
Raymond Reede  
District Manager





RECEIVED

A Halliburton Company

91 MAR 28 PM 12:24

U.S. EPA REGION VIII  
DRINKING WATER BRANCH

March 25, 1991

Murphy Oil Corporation  
P.O. Box 547  
Poplar, MT 59255

Attn: Ray Reede

RE: Radioactive Tracer Evaluation, EPU #80D

Dear Ray:

Radioactive Tracer Logs were run on the EPU #80D well; East Poplar Field, Roosevelt County, Montana; to determine water injection profiles. The results of these logs are as follows:

Perforations below 3,320' were covered with fill and accepting no fluid. From the bottom of the tailpipe at 3,295' fluid is being injected to a depth of 3,306'. From this point to bottom logged interval there is little or no fluid movement. Stationary checks were performed to verify no injected fluid was being placed in perforations at 3,218' to 3,250' and no fluid is channeling up behind the packer.

These interpretations are from log results dated 3/21/91 and will not apply to future well conditions.

Sincerely,

Robert S. Blackford  
Sr. Sales Engineer

APPROVED  
Date 5/24/91





POST OFFICE BOX 547  
POPLAR, MONTANA 59255

March 26, 1991

Max H. Dodson, Director  
Water Management Division  
United States Environmental Protection Agency  
Region VIII - Suite 500  
999 18th Street  
Denver, CO 80202-2405

RE: East Poplar Unit 80-D  
EPA No. MTS2026-0026

Dear Mr. Dodson:

Our permit on East Poplar Unit 80-D states a tracer survey must be run on this well every 5 years. A tracer survey was run by Halliburton Logging Services on March 21, 1991. The copies of the Temperature Log and the Radioactive Tracer Log are enclosed, along with Halliburton's interpretations of the log.

Sincerely,

  
Raymond Reede  
District Manager

RR/jh  
enclosures

cc: Jim Boyter  
Debi Madison  
Paul Ramsey  
Sidney Campbell  
Well file





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

JUN 7 1991

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
EPA Permit No. MT2026-00026  
(Formerly Permit No. MT2026-0026)  
East Poplar Unit No. 80-D  
Roosevelt County, Montana

Dear Mr. Reede:

The Environmental Protection Agency's (EPA) Implementation Section has reviewed the March 21, 1991, Halliburton Radioactive Tracer Survey (RATS) and Differential Temperature Log (DTL). The conclusions of the EPA review group are that the logs, as submitted, do not satisfy Permit Condition Part II, Section C. 2. (a). (Page 6), which requires "... a radioactive tracer survey and a temperature differential log shall be run from a distance of at least 250 feet above the injection zone." Both logs stop considerably short of the required distance above the top perforation and, therefore, the LOGS MUST BE REPEATED.


It is also observed that the Differential Temperature Log does not have a temperature curve while the well is injecting. The required curve must be run at the normal operating pressure. Please include the surface temperature of the injected fluid.

The RAT survey shows fluid moving above the perforations at 3286 feet. On the new RATS log, have all passes overlay on the same base line, and include the depths up to 250 feet above the perforations on all runs.

Mr. Raymond Reede  
EPA Permit No. MT2026-00026  
Page Two

Murphy Oil USA, Inc. must conduct a new RAT survey and run a new DTL log within ninety (90) days of receipt of this letter. If you have any questions in regard to this action, please contact Emmett Schmitz at (303) 293-1436. Please send all reports and correspondence to the ATTENTION: EMMETT SCHMITZ, citing MAIL CODE: 8WM-DW very prominently.

Sincerely,

A handwritten signature in cursive script, appearing to read "Rick Cloggett for".

Max H. Dodson, Director  
Water Management Division

cc: Jim Boyter, MO

Debi Madison  
Fort Peck Assiniboine & Sioux Tribes  
Office of Environmental Protection  
Box 1027  
Poplar, MT 59255

CONCURRENCE COPY

OCT 31 1991

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
EPA Permit No. MT2026-00026  
East Poplar Unit (EPU) No. 80-D  
Roosevelt County, Montana

Dear Mr. Reede:

Staff members of the Environmental Protection Agency's (EPA), UIC Implementation Section, reviewed the August 8, 1991, Halliburton Differential Temperature Log and Halliburton Fluid Travel Log for the EPU No. 80-D. They concluded that the Temperature Log shows characteristics which indicate there may be flow behind the longstring above the perforations, and that this flow may extend as high as 3100 feet kelly bushing (KB). The absence of a shut-in Temperature Log makes it difficult to conclusively evaluate conditions behind the pipe. We suggest that a Temperature Log be run after a minimum shut-in time of six (6) hours. We also suggest that the log run commence farther up the hole, i.e., at 150 feet KB, which is the top of the only underground source of drinking water (USDW) identified in the EPU No. 80-D. We also require that an explanation of the cause for the "tool log spike" shown on the Temperature Log be included in the logging report.

The Radioactive Tracer Log continues to be inconclusive. Murphy Oil USA did not utilize the procedural tracer survey guidelines approved by the EPA for detection of flow behind pipe (copy enclosed). The approved method calls for logging the well during injection to monitor the change and movement of the radioactive slug with time. The determination of fluid flow behind the casing would involve the following action:

- a) Place radioactive slug at least 20 feet above injection perforations during injections at a constant rate with a surface pressure close to the normal operating pressure;
- b) Make overlapping logs of the slug as it moves into the perforations;

8WM-DW  
IS  
10/16/91

8WM-DW  
Indy  
10/21/91

Pche  
8WM-DW  
10/24/91

8WM-DW  
Cathy  
10/27/91

h5

Mr. Raymond Reede  
EPU No. 80-D  
Page Two

- c) After the slug has moved into the perforations, make several logs up the hole to a point above the disposal zone confining interval; and
- d) Logging should continue until the slug has completely disappeared.

It is observed that neither Halliburton nor Murphy Oil supplied key information on the logs which are necessary for the logs interpretation. Information which must be supplied includes:

- a) The actual injection rate and pressure;
- b) The approximate down hole velocity used to estimate approximate flow time of the slug into the formation; and
- c) A narrative of how the log was run and what the results mean.

Murphy Oil USA, Inc. must conduct a new Radioactive Tracer Survey and Differential Temperature Survey within ninety (90) days of receipt of this letter. If you have any questions in regard to this action or with test procedures, please contact Emmett Schmitz at (303) 293-1436. Please send all communication to the ATTENTION: EMMETT SCHMITZ citing MAIL CODE: 8WM-DW very prominently.

Sincerely,

Original Signed By  
ROGER FRENETTE

Max H. Dodson, Director  
Water Management Division

Enclosure: Accepted Radioactive Tracer Survey Guideline and Procedure.

cc: Jim Boyter, MO

Debi Madison  
Fort Peck Assiniboine & Sioux Tribes  
Office of Environmental Protection  
Box 1027  
Poplar, MT 59255

CONCURRENCE COPY

FEB 7 1992

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
East Polar Unit (EPU) No. 80-D  
EPA Permit No. MT2026-00026  
Roosevelt County, Montana

Dear Mr. Reede:

In response to your telephone inquiry of January 6, 1991, to Emmett Schmitz, of this office, concerning running a radioactive tracer survey (RATS) at high surface injection pressures, the Environmental Protection Agency (EPA) concurs with your opinion that under those circumstances a definitive RAT survey is not possible. The EPA will require that Murphy Oil run a Differential Temperature log in lieu of the RAT survey.

The EPA did review the August 8, 1991, Halliburton Differential Temperature Log for the EPU No. 80-D. We have concluded that the Temperature Log does not permit a definitive interpretation of fluid conditions behind pipe. Therefore, the EPA will require you to run another Temperature Log (1) immediately prior to shut-in; (2) a log after a minimum shut-in time of six (6) hours; and (3) a log after twelve (12) hours of shut-in. The EPA also requires that Murphy Oil commence the log run farther up the hole, i.e., at 150 feet KB, which is the top of the only underground source of drinking water (USDW) identified in the EPU No. 80-D. You are also requested to explain the cause for the "tool log spike" shown on the August 8, 1991, Temperature Log survey.

8WM-DW  
A  
1/23/92

8WM-DW  
Rend  
1/27/92

8WM-DW  
Ple  
2/4/92

8WM-DW  
Cuthy  
2/5/92

he

Differential Temperature Log  
EPU No. 80-D  
MT00026  
Page Two

As soon as the winter climate moderates, but within ninety (90) days of receipt of this letter, Murphy Oil USA, Inc. shall run a Differential Temperature Log according to the guidelines described in the preceding paragraph. If you have any questions in regard to the above action, please contact Emmett Schmitz at (303) 293-1436. All correspondence should be sent to the ATTENTION: EMMETT SCHMITZ, citing MAIL CODE: 8WM-DW very prominently.

Sincerely,

Original Signed By  
ROGER FRENETTE

Max H. Dodson, Director  
Water Management Division

cc: Jim Boyter, MO

Debi Madison  
Fort Peck Assiniboine & Sioux Tribes  
Office of Environmental Protection  
Box 1027  
Poplar, MT 59255

FCD:January 15, 1992:ers\disk15\a:\mrfy0026\templog.ltr

Bob Blackford



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

FEB 7 1992

*received  
2-11-92*

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
East Polar Unit (EPU) No. 80-D  
EPA Permit No. MT2026-00026  
Roosevelt County, Montana

Dear Mr. Reede:

In response to your telephone inquiry of January 6, 1991, to Emmett Schmitz, of this office, concerning running a radioactive tracer survey (RATS) at high surface injection pressures, the Environmental Protection Agency (EPA) concurs with your opinion that under those circumstances a definitive RAT survey is not possible. The EPA will require that Murphy Oil run a Differential Temperature log in lieu of the RAT survey.


The EPA did review the August 8, 1991, Halliburton Differential Temperature Log for the EPU No. 80-D. We have concluded that the Temperature Log does not permit a definitive interpretation of fluid conditions behind pipe. Therefore, the EPA will require you to run another Temperature Log (1) immediately prior to shut-in; (2) a log after a minimum shut-in time of six (6) hours; and (3) a log after twelve (12) hours of shut-in. The EPA also requires that Murphy Oil commence the log run farther up the hole, i.e., at 150 feet KB, which is the top of the only underground source of drinking water (USDW) identified in the EPU No. 80-D. You are also requested to explain the cause for the "tool log spike" shown on the August 8, 1991, Temperature Log survey.



Differential Temperature Log  
EPU No. 80-D  
MT00026  
Page Two

As soon as the winter climate moderates, but within ninety (90) days of receipt of this letter, Murphy Oil USA, Inc. shall run a Differential Temperature Log according to the guidelines described in the preceding paragraph. If you have any questions in regard to the above action, please contact Emmett Schmitz at (303) 293-1436. All correspondence should be sent to the ATTENTION: EMMETT SCHMITZ, citing MAIL CODE: 8WM-DW very prominently.

Sincerely,

  
Max H. Dodson, Director  
Water Management Division

cc: Jim Boyter, MO

Debi Madison  
Fort Peck Assiniboine & Sioux Tribes  
Office of Environmental Protection  
Box 1027  
Poplar, MT 59255



POST OFFICE BOX 547  
POPLAR, MONTANA 59235

May 7, 1992

Mr. Emmett Schmitz  
United States Environmental Protection  
Agency Region VIII  
One Denver Place - Suite 1300  
999 18th Street  
Denver, Co 80202-2413

Dear Mr. Schmitz:

Re: 8WM-DW  
Temperature Log, EPU  
80-D

Enclosed you will find a copy of Halliburton Logging Services  
Differential Temperature Log that was run May 5, 1992. Also  
enclosed is a copy of Halliburton's interpretation of the temper-  
ature survey. I hope these are satisfactory.

Yours very truly,

  
Raymond F. Reede  
District Manager

RR/sb  
cc: Sidney Campbell, Murphy E&P, New Orleans, La  
enclosures



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

January 4, 1993

Max H. Dodson, Director  
Water Management Division  
US Environmental Protection Agency  
Region VIII - Suite 500  
999 18th Street  
Denver CO 80202-2405

Dear Mr. Dodson:

Enclosed are the water analysis reports on the following  
salt water disposal wells:

East Poplar Unit 1-D	MTS2022-0022
East Poplar Unit 5-D	MTS2021-0021
East Poplar Unit 8-D	MTS2023-0023
East Poplar Unit 80-D	MTS2026-0026
Sletvold 2-D	MT2619-03705
Lillian 1-D	MTS2035-0046
Wetsit 1-D	MTS2303-0612
Courchene 2-D	MTS2398-1768

Sincerely,

---

Raymond Reede  
District Manager

RR/jh  
enclosures

cc: Jim Boyter EPA Helena



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

January 13, 1995


Max H. Dodson, Director  
Water Management Division  
US Environmental Protection Agency  
Region VIII - Suite 500  
999 18th Street  
Denver CO 80202-2405

Dear Mr. Dodson:

Enclosed are the water analysis reports on the following  
salt water disposal wells:

East Poplar Unit 1-D	MTS2022-0022
East Poplar Unit 5-D	MTS2021-0021
East Poplar Unit 8-D	MTS2023-0023
East Poplar Unit 80-D	MTS2026-0026
Sletvold 2-D	MT2619-03705
Lillian 1-D	MTS2035-0046
Wetsit 1-D	MTS2303-0612
Courchene 2-D	MTS2398-1768

Sincerely,

  
Raymond Reede  
District Manager

RR/jh  
enclosures

cc: Jim Boyter EPA Helena





POST OFFICE BOX 547  
POPLAR, MONTANA 59255

February 8, 1999

Steven Sasaki  
Board Of Oil and Gas Conservation  
2535 St. John's Avenue  
Billings, MT 59102

Re: Renewal of Pit Permits

Dear Mr. Sasaki

As the pit permits have now expired or are going to expire shortly we would like to request an extension of these permits until the lease is plugged and restoration work takes place. The following is a list of the pits we would like to have the permits extended on.

EPU No. 1-D	SE SE Section 30, T29N, R51E	Federal
EPU No. 5-D	SE SE Section 19, T29N, R51E	Federal
EPU No. 8-D	NW SE Section 10, T29N, R51E	Federal
EPU No. 80-D	SW NW Section 3, T28N, R51E	Federal
War Club No. 1	NW SE Section 11, T 29N, R50E	Federal

If you have any questions concerning these pits, please contact the Poplar Office for any addition information you might require.

Yours truly,

A handwritten signature in cursive script that reads "Raymond Reede".

Raymond Reede  
District Manager

sb

cc: Sidney Campbell, New Orleans, LA.  
file





# United States Department of the Interior

BUREAU OF LAND MANAGEMENT  
MILES CITY DISTRICT OFFICE

P.O. Box 940  
Miles City, Montana 59301

IN REPLY REFER TO:

3160  
NTL-2B

DEC 27 1985

Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, Montana 59255

RE: NTL-2B Approval for the East Poplar Unit

Gentlemen:

We have received your NTL-2B application dated 12/2/85, for the federal wells within the East Poplar Unit boundaries. BLM regulation requires NTL-2B approval for all wells within a federal unit. We will not require additional NTL-2B application for nonfederal wells within the unit, rather this letter will serve as NTL-2B approval for all existing wells in the East Poplar Unit. Produced water from the unit is approved for disposal into the following wells:

EPU SWD No. 1    EPA ID No. MTS21PE-0022,  
EPU SWD No. 80    EPA ID No. MTS21PE-0026,  
EPU SWD No. 8    EPA ID No. MTS21PE-0023,  
EPU SWD No. 5    EPA ID No. MTS21PE-0021, and  
EPU SWD No. 29    EPA ID No. MTS21PE-0024.

The following conditions apply to this NTL-2B approval for the disposal of produced water from the referenced unit:

Receipt of this approval does not constitute EPA approval for subsurface injection.

Upon receipt of EPA approval, a copy of the EPA permit must be submitted to this office.

All unauthorized discharges or spills must be reported to this office in accordance with CFR Title 40, Parts 124, 144, 146, and 147.


For future wells, complete NTL-2B applications will not be required. Instead, a Well Completion Report (Form 3160-4) should be used with a statement referring to NTL-2B approval and an explanation of the water source and disposal facilities (see example attached).

Wells outside the unit boundaries will require separate NTL-2B approval.

Any changes to these approved procedures must be submitted via Sundry Notice (Form 3160-5) prior to the commencement of operations.

If you have any questions, please contact Jamie Connell at (406) 232-4331.

Sincerely yours,

A handwritten signature in black ink, appearing to read "James K. Mula". The signature is fluid and cursive, with a large initial "J" and a long horizontal stroke at the end.

Asst. District Manager  
Division of Mineral Resources



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

February 8, 1999

Steven Sasaki  
Board Of Oil and Gas Conservation  
2535 St. John's Avenue  
Billings, MT 59102

Re: Renewal of Pit Permits

Dear Mr. Sasaki

As the pit permits have now expired or are going to expire shortly we would like to request an extension of these permits until the lease is plugged and restoration work takes place. The following is a list of the pits we would like to have the permits extended on.

EPU No. 1-D	SE SE Section 30, T29N, R51E	Federal
EPU No. 5-D	SE SE Section 19, T29N, R51E	Federal
EPU No. 8-D	NW SE Section 10, T29N, R51E	Federal
EPU No. 80-D	SW NW Section 3, T28N, R51E	Federal
War Club No. 1	NW SE Section 11, T 29N, R50E	Federal

If you have any questions concerning these pits, please contact the Poplar Office for any addition information you might require.

Yours truly,

A handwritten signature in cursive script that reads "Raymond Reede".

Raymond Reede  
District Manager

sb

cc: Sidney Campbell, New Orleans, LA.  
file







*"A Commitment to Excellence"*

505 North 24th Street  
Billings, Montana 59101  
Tel 406-248-7170 • 800-448-7170  
Fax 406-248-7304

May 30, 1999

Murphy Oil Corporation  
PO Box 547  
Poplar Montana  
59255

Attn. Mr. Ray Reede

Re: Cathodic Protection System installation, activation and repair

Dear Sir:

We have completed the installation of the new cathodic protection system for the Huber 5-10 disposal well. The cathodic protection system consists of 8 each, 3"x60", linseed oil treated, graphite anodes back-filled with 500 pounds of calcined petroleum cokebreeze per anode. Anode lead wires are #8 AWG with HMW-PE insulation. The anodes are installed horizontally at a depth of 8 feet. Anode spacing is 15 feet. The positive cable is #6 AWG with black HMW-PE insulation. The negative cable is #6 AWG with white HD-PE insulation. The groundbed is powered by an RTS model CSAYSD 24-16 AZ rectifier that is pole-mounted. An "as-built" drawing of the cathodic protection system has been included with this letter.

Testing and repairs were also completed on the rectifier at the <sup>80</sup>AD disposal well. A new transformer and rectifier stack assembly was installed and the rectifier was placed back into service. Both rectifiers were adjusted to target current outputs of 10.0 amps to the well casings. Potential levels noted on the well casings indicated high protection levels at both sites. The flowline at the <sup>80</sup>AD disposal well was found to be shorted to the casing. An insulating union should be installed to separate the well casing from the surface facilities. No other problems were noted at this time.


It has been a pleasure being of service in your corrosion mitigation program, if you have any questions or require additional service please contact us.

Respectfully Submitted,

*Brent Cathey*

Brent Cathey  
Corrpro Companies Inc.

8 anode grounded w/500# of cokebreeze per anode. 8' deep x 120' long trench. Anodes on 15' centers.



△ Soil Resistivity(ohm/cm)

# LEGEND

- ☑ RECTIFIER
- ☑ THERMOELECTRIC GENERATOR
- ☑ SOLAR UNIT
- ☑ ANODE JUNCTION BOX
- ☑ CURRENT CONTROL BOX
- ☑ RTU

- ANODE (HORIZONTAL)
- ANODE (VERTICAL)
- DEEP 4/8 (VERT.)
- △ SOIL RESISTIVITY (ohm/cm) (10m/10m/10m DEPTH)
- PLUMBING UNIT
- ☉ WELL HEAD



- DE-HY DR SEPARATOR
- PROpane TANK
- POSITIVE CABLE
- NEGATIVE CABLE
- FLOWLINE
- POWER CABLE



•Billings, Montana•

CUSTOMER	Murphy Oil Co. Poplar, MT.		ENG. BY
			D.L.
	LOCATION		DESGN. BY
	East Poplar Field Huber 5-D WDW AS BUILT CATHODIC PROTECTION SYSTEM		D.L.
SCALE	NITS	DATE 11/1/88	DRG. BY
			B.C.

Murphy Oil Corp  
East Poplar Field  
Activation Data

Disposal Well 4D

Rectifier Data

Universal  
MWC-3  
220/480 VAC  
28 VDC  
18 ADC

	As Found	As Left
Date		5/24/99
Tap Setting	OFF	C1-F1
DC Volts		5.5
DC Amps		10.0
Circuit Res.		0.55

Potential Data

	Static	ON	
Casing	550	1046	
Flowline	550	1046	No isolation Kit

Disposal Well Huber 5-D

Rectifier Data

RTS  
CAYSAD 24-16  
480 VAC  
24 VDC  
16 ADC  
Ser # C983706

	As Found	As Left
Date	New Site	5/22/99
Tap Setting		A-4
DC Volts		4.25
DC Amps		10.00
Circuit Res.		0.43

Potential Data

	Static	ON	
Casing	610	1070	
Flowline	Fiberglass		



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8  
999 18<sup>TH</sup> STREET - SUITE 500  
DENVER, CO 80202-2466

JUN 22 1999

Ref: 8ENF-T

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede, District Manager  
Murphy Exploration & Production Company  
P.O. Box 547  
Poplar, MT 59255

Re: UNDERGROUND INJECTION CONTROL (UIC)  
Notice of Noncompliance  
Annual Monitoring Reports  
Roosevelt County, MT

Dear Mr. Reede:

Enclosed are Annual Disposal/Injection Well Monitoring Report forms (EPA Form 7520-11) for the wells listed below for the year 1998. These forms should have been submitted by February 15 of this year. Pursuant to permit condition Part II, Section D you are required to submit Annual Monitoring Report forms. Each well requires a separate form, whether the well is active or temporarily abandoned. Please submit the forms within thirty (30) days of receipt of this letter.

<u>Well Name</u>	<u>Permit Number</u>
Mule Creek Allotted #1	MT2791-04292
Well #5-D	MT2021-00021
Well #80-D ✓	MT2026-00026
Well EPU #1-D ✓	MT2022-00022
Well EPU #8-D ✓	MT2023-00023
Well Huber #5 ✓	MT2779-04278

Any person who violates any requirement of the Underground Injection Control (UIC) program is subject to enforcement action under Section 1423 of the Safe drinking Water Act. [42 U.S.C. Section 300h-2], et seq. Enforcement may include civil penalties of up to \$27,500 for each day for each violation and require compliance with all provisions of the Safe Drinking Water Act. If the violation is willful, criminal penalties may be prosecuted in accordance with Title 18 of the United States Code.



Printed on Recycled Paper

If you have any questions concerning this letter, you may contact John Carson at (303) 312-6203. Also, please direct all correspondence to the attention of John Carson at Mail Code 8ENF-T.

Sincerely,

*Connally E. Mears*

Connally E. Mears, Director  
Technical Enforcement Program

Enclosures: EPA Form 7520-11

cc: Deb Madison  
Environmental Program Manager  
Assiniboine & Sioux Tribes  
P.O. Box 1027  
Poplar, MT 59255

Spike Bighorn, Chairman  
Fort Peck Tribal Executive Board  
Assiniboine & Sioux Tribes  
P.O. Box 1027  
Poplar, MT 59255

Sandra Brooks, Field Manager  
Billings Field Office  
Bureau of Land Management  
810 East Main Street  
Billings, MT 59105-3395



POST OFFICE BOX 647  
POPLAR, MONTANA 59256

June 28, 1999

John Carson  
United States Environmental Protection Agency  
Region 8  
999 18<sup>th</sup> Street - Suite 500  
Denver, Co 80202-2466


Dear Mr. Carson

As per our phone conversation you will find copies of the Underground Injection Control Annual Monitoring Reports which we originally submitted sometime in late January of this year. The reports submitted cover the following wells:

EPU No. 5-D	MT2021-00021
EPU No. 80-D	MT2026-00026
EPU No. 1-D	MT2022-00022
EPU No. 8-D	MT2023-00023
Huber No. 5-D	MT2779-04278

No report was submitted on the Mule Creek Allotted No. 1 MT2791-04292 as the application for permit was cancelled in July of 1997.

Sincerely,

  
Sharon Bravard



AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
SW NW Section 3-T28N-R51E, Roosevelt County, Montana

WELL DRILLING & CONSTRUCTION EXPENSE:	TO CSG. PT.	COMP. & EQUIP.	TOTAL COST
Drilling - Footage - 5800' @ \$5.25/ft.	\$ 30,450	\$	\$ 30,450
Daywork - 1 day @ \$850/day & 2 days @ \$775/day	850	\$ 1,550	1,550
Loc. survey, permit & prep.	350		350
Roads, fences, cattleguard, etc.	800		800
Mud mat. & chem., incl. oil & gas	6,000		6,000
Cementing casing	2,200	950	3,150
Testing services incl. swabbing		350	350
Other logs, surveys & analysis	1,850	800	2,650
Perforating services		1,200	1,200
Hydrafrac, acidize, etc. incl. oil		1,400	1,400
Float equip., centralizers, etc.	250	650	900
Trucking, welding & other labor	250	250	500
Supervision & miscellaneous	250	250	500
Total Est. Well Drilg. & Const. Exp.	\$ 43,250	\$ 7,400	\$ 50,650

WELL EQUIPMENT COSTS:			
Casing: 150' of 13-3/8" O.D.	\$ 800		\$ 800
Casing: 1000' of 9-5/8" O.D.	3,775		3,775
Casing: 5800' of 5-1/2" O.D.		\$ 9,700	9,700
Tubing: 5800' of 2-7/8" O.D.		4,800	4,800
Casing head & connections	300		300
Xmas tree & connections		800	800
Total Est. Well Equip. Costs	\$ 4,875	\$ 15,300	\$ 20,175
Total Est. Cost of Well	\$ 48,125	\$ 22,700	\$ 70,825

LEASE EQUIPMENT:			
Flow lines		\$ 2,500	\$ 2,500
Other line pipe, valves & fittings		500	500
Trucking, welding & other labor		500	500
Total Est. Cost of Lease Equip.		\$ 3,500	\$ 3,500
TOTAL EST. COST OF WELL & LEASE EQUIP.	\$ 48,125	\$ 26,200	\$ 74,325

APPORTIONMENT OF TOTAL ESTIMATED COSTS

Murphy Corporation -	%			
Unit Operator	31.448570	\$ 15,135	\$ 8,239	\$ 23,374
Munoco Company	2.096565	1,009	549	1,558
Placid Oil Company	33.545035	16,144	8,789	24,932
The Carter Oil Company	16.335860	7,862	4,280	12,142
Phillips Petroleum Company	16.335860	7,862	4,280	12,142
C. F. Lundgren	.238210	115	62	177

APPROVAL OF EXPENDITURE

Requested by:

Hansen Mica 5/31/56  
Division Production Supt. Date

Recommend Approval:

J. P. Langford 5/31/56  
Division Manager Date

Approved:

\_\_\_\_\_  
By Date

Recommend Approval:

\_\_\_\_\_  
Staff Production Man Date

Recommend Approval:

\_\_\_\_\_  
Budget Supervisor Date

Approved:

\_\_\_\_\_  
Vice President-Operations Date

AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
SW NW Section 3-T28N-R51E, Roosevelt County, Montana  
(Installation of Pumping Unit)

Pumping unit complete with engine	\$5,650
Labor and materials setting unit	750
Trucking, small fittings, and incidentals	150
Rods, pump, and well head equipment	<u>3,000</u>
<b>TOTAL ESTIMATED COST</b>	<b>\$9,550</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

	%	
Murphy Corporation	31.448470	\$3,003
Manoco Company	2.096565	200
Placid Oil Company	33.545035	3,203
The Carter Oil Company	16.335880	1,560
Phillips Petroleum Company	16.335860	1,560
C. F. Lundgren	.238210	23

APPROVAL OF EXPENDITURE

Requested by:

Recommend Approval:

*Harold Miller* JUL 10 1956  
 Division Production Supt. Date

\_\_\_\_\_  
 Staff Production Man Date

Recommend Approval:

Recommend Approval:

*C. F. Lundgren* JUL 10 1956  
 Division Manager Date

\_\_\_\_\_  
 Budget Supervisor Date

Approved:

Approved:

\_\_\_\_\_  
 By Date

\_\_\_\_\_  
 Vice President-Operations Date

56 4/6  
 27 7/6  
 53  
 56 3/6  
 13 1/6  
 9/6  
 97 1/6  
 6 2/6  
 5500



AUTHORITY FOR EXPENDITURE  
 MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
 SW NW Section 3, T28N, R51E, Roosevelt County, Montana  
 (Workover #1)

1,000 Gallons Acid and Service	\$650
Miscellaneous Labor and trucking	<u>150</u>
Total Estimated Cost	\$800

Present Status: Pumping from the "A-1" Zone. Tested May 3, 1958, 68 BFPD, 71% water (48 BFPD, 20 BOPD).

History: Completed July 29, 1956 in the "A-1" Zone from 5456'-5474' (18'), acidized with 500 gallons acid, break down pressure 2500 psi. Injected 4 BPM at 2000 psi. Final injection pressure 1750 psi. Total accumulated production April, 1958 - 63,795 BF, 36,479 BO, 27,316 BW. Well test has declined from 31 BOPD December 2, 1957 to 20 BOPD May 3, 1958.

Proposed Workover: To increase production, re-acidize through casing annulus with 1000 gallons Howco retarded acid, pump test.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.1448470%	\$252
Munoco Company	2.096565%	16
Placid Oil Company	33.545035%	268
Carter Oil Company	16.335860%	131
Phillips Petroleum Company	16.335860%	131
C. F. Lundgren	.238210%	2

APPROVAL OF EXPENDITURE

Requested by: MMH 5-27-58 Date

Recommend Approval:

L. L. Linneman 6-6-58  
Staff Production Man Date

Harold M. ... MAY 29 1958  
Division Production Supt. Date

Recommend Approval:

Harold Robins 6-6-58  
Budget Supervisor Date

Gordon Kirby MAY 29 1958  
Division Manager Date

Approved:

Paul C. McDonald 6-6-58  
Vice President Operations Date

AUTHORITY FOR EXPENDITURE  
 MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
 SW NE Section 3, T28N, R51E, Roosevelt County, Montana  
 (Workover #2)

3000 Gallons HOWCO HV Acid and Pump Truck	\$1,500
Miscellaneous trucking and labor	<u>500</u>
Total Estimated Cost	<u>\$2,000</u>

Present Status: Pumping 14 BOPD, 45 BWPD, 77% water from the "A-1" Zone.

History: Completed July 29, 1956, from the "A-1" Zone perforations 5456' to 5474'. Cumulative production through December, 1958 was 42,254 BO and 40,665 BW.

Justification for Workover: to increase production.

Proposed Workover: Re-acidize the "A-1" Zone with 3000 gallons Howco HV acid (Workover #1 -- 1000 gallons). Acidize down casing annulus to eliminate the cost of pulling rods. Pump test.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.448470%	\$ 629
Munoco Company	2.096565%	42
Placid Oil Company	33.545035%	671
Carter Oil Company	16.335860%	327
Phillips Petroleum Company	16.335860%	327
C. F. Lundgren	.238210%	4

APPROVAL OF EXPENDITURE

Requested by: *MM* 2-19-59 Date Recommend Approval:

*Harold D. ...* 2-23-59 Date Staff Production Man Date

Recommend Approval:

Recommend Approval:

*R. L. ...* 2/23/59 Date Division Manager Date Budget Supervisor Date

Approved:

Vice President-Operations Date

*Received approval from  
 El Dorado 3-16-59*

AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
SW NE Section 3, T28N, R51E, Roosevelt County, Montana  
(Workover #3)

Pulling Unit 3 (8 Hr) days @ \$224 per day  
 Perforate (2 holes) with abrasive jet and  
 500 gallon acid job  
 Retrievable packer and service  
 Miscellaneous trucking and labor  
 Total Estimated Cost

475 \$ 675 \$1148 - 473  
 475 975 \$1456 - 481  
 500 \$ 270 + 204  
 150 \$ 150  
\$2,300 (3024)

Present Status: Pumping from "A-1 & 2" Zone perforations, 5456-74'. Pumping  
 4 BOPD, 34 BWPD (uneconomical).

History: Well No. 80 was completed on July 29, 1956, in the "A-1 & 2" Zone  
 through perforations, 5456'-5474', with an initial potential of 125 BOPD,  
 48 BWPD. Production declined to 11 BOPD, 57 BWPD on June 17, 1958, and  
 was acidized with 1,000 gallons (W.O. #1). Workover Potential was  
 26 BOPD, 80 BWPD. Production declined to 14 BOPD, 47 BWPD by March  
 3, 1959, and was reacidized with 3,000 gallons (W.O. #2). Workover  
 Potential was 28 BOPD, 80 BWPD. Accumulated production from "A-1 & 2"  
 Zone - 47,764 Net BO, 56,391 BW.

Proposed Workover: Perforate the A-3 Zone at 5494' with Dowell abrasive jet  
 2 holes, 180° apart, acidize with 500 gallons, acidize through retrieva-  
 ble packer to isolate perforation 5456-74'. Test the A-3 Zone and  
 produce comingled with the A-1 and 2 Zones.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.448470%	\$ 723	274
Manoco Company	2.096565%	49	20
Placid Oil Company	33.545035%	771	314
Carter Oil Company	16.335860%	376	155
Phillips Petroleum Company	16.335860%	375	155
C. F. Lundgren	.238210%	6	2

APPROVAL OF EXPENDITURE

Requested by: M. H. Lundgren 3-2-60  
 Field/Production Supt. Date

Recommend Approval:

Recommend Approval:

Division Production Supt.

Date

Staff Production Man

Date

Recommend Approval:

Recommend Approval:

Division Manager

Date

Budget Supervisor

Date

Approved:

Received approval from  
 El Parado 3-17-60.

No approval needed from  
 partners as estimated cost is  
 MTJ:im 1000 + 1000 = \$5000

Vice President - Operations Date

AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
SW NE Section 3, T28N, R51E, Roosevelt County, Montana  
(Workover #3)

(Supplement No. 1)

Pulling Unit - Two (8 hour) days @ \$224 per day	\$ 475
Additional Services	<u>475</u>
Total Estimated Cost	\$ 950

Justification for Expenditure: Increase in pulling unit time and service charge due to packer failure and additional material for cutting 3" slots.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.448470%	\$ 299
Munoco Company	2.096565%	20
Flacid Oil Company	33.545035%	319
Carter Oil Company	16.335860%	155
Phillips Petroleum Co.	16.335860%	155
C. F. Lundgren	.238210%	2

APPROVAL OF EXPENDITURE

Requested by: MMH Bailey 4-18-60  
 Field Production Supt. Date

Recommend Approval: \_\_\_\_\_ Recommend Approval: \_\_\_\_\_

Division Production Supt. \_\_\_\_\_ Date \_\_\_\_\_ Staff Production Man \_\_\_\_\_ Date \_\_\_\_\_

Recommend Approval: \_\_\_\_\_ Recommend Approval: \_\_\_\_\_

Division Manager \_\_\_\_\_ Date \_\_\_\_\_ Budget Supervisor \_\_\_\_\_ Date \_\_\_\_\_

Approved: \_\_\_\_\_

Vice-President - Operations \_\_\_\_\_ Date \_\_\_\_\_

*Approved Col. Dames 6-3-60.*

MTJ:m  
4-18-60

*No other approval necessary.*

A.M.M. No. 2-2521

47 AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 30  
SW 1/4 Section 3, T28N, R51E, Roosevelt County, Montana

(PREP. FOR SALT WATER DISPOSAL INTO DAKOTA SAND)

Pulling unit 7 (10 hr.) days @ \$290 per day.	\$ 2,025
Bridge plug, cmt. retainer, and service.	\$ 725
2 block sqz perf., set bridge plugs on WL & selectively perf 32' 126', and 56' (208') 4 holes per ft.	\$ 2,400
Block sqz below and above Dakota sand 2 stages .75 sks each.	\$ 1,400
Pump truck to water frac Dakota sand.	\$ 200
x 3250' of 3 1/2" OD 2.203 H-40 reg tbg internally coated @ \$1.02 per ft.	\$ 5,825
Miscellaneous trucking, labor, and material.	\$ 500
<b>TOTAL ESTIMATED COST</b>	<b>\$ 13,675</b>

(SALT WATER DISPOSAL FACILITIES)

x 2400' of 8" class 100 cement-asbestos w/fluid tie coupling @ \$2.25 per ft.	\$ 5,400
Laying, ditching, and back fill 2400' of 8" cement-asbestos S.W. Gath. Line @ \$0.85 per ft.	\$ 2,050
Connections for tie-ends and line scraper traps.	\$ 1,100
x 1 1/2 HP electric motor (less controls).	\$ 2,100
Miscellaneous trucking, labor, electrician, and Material.	\$ 2,500

**TOTAL ESTIMATED COST (FACILITIES) \$ 13,150**

**TOTAL ESTIMATED COST DISPOSAL WELL AND FACILITIES \$ 26,825**

JUSTIFICATION FOR EXPENDITURE

The 7" and 4 1/2" internally coated steel discharge line to EPU #59-D has had 6 leaks within the last 40 days, (repair cost \$1000). Leak frequency will increase and the line will have to be replaced, lined, or abandoned. Est. cost to replace or install plastic liner - \$31,500.

The disposal capacity of #1-D is not sufficient to handle the unit salt wtr volume of 17,300 EPD. Additional disposal capacity is required to comply with Montana Oil & Gas Commission order of sub-surface disposal of all produced Salt Water.

EPU #30 depleted and watered out in the A zone and temporarily abandoned. 3 workovers failed to increase production. B and C zones structurally low.

Proposed Workover - Set bridge plug w/1 sk cmt above A zone perf. Block sqz btm & top of Dakota sd. Selectively perf and wtr frac 208' of Dakota sd in 3 sections.

Facilities - Station semi-portable. 1 oil well triplex pump, 100 bbls internally plastic coated steel tk skid mounted and electric motor controls surplus material.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.448470%	\$ 8,437
Munoco Company	2.096565%	\$ 562
Placid Oil Company	33.545035%	\$ 6,998
Humble Oil & Refining Company	16.335860%	\$ 4,382
Phillips Petroleum Company	16.335860%	\$ 4,382
C. F. Lundgren	.230210%	\$ 64

APPROVAL OF EXPENDITURE

Requested by: M. H. Lundgren 10-18-62  
 Field Production Superintendent Date

RECOMMEND APPROVAL:

\_\_\_\_\_  
 Production Superintendent Date

APPROVED:

\_\_\_\_\_  
 Production Manager Date

AUTHORITY FOR EXPENDITURE  
MURPHY CORPORATION - EAST POPLAR UNIT NO. 80  
SW NW Section 3, T28N, R51E, Roosevelt County, Montana

(PREP. FOR SALT WATER DISPOSAL INTO DAKOTA SAND)

Pulling unit 7 (10 hour) days @ \$300 per day	\$ 2,100
Bridge plug, cement retainer, and service	\$ 725
2 block sqz perf., set bridge plugs on WL & selectively	
perf. 32', 126', and 50' (208') 4 holes per foot	\$ 3,400
Block sqz below and above Dakota Sand 2 stages .75 sks each	\$ 1,400
Pump truck to water frac Dakota Sand	\$ 800
3250' of 3½" OD 9.20# H-40 reg tbg internally coated @ \$1.82 per ft.	\$ 5,825
Miscellaneous trucking, labor, and material	\$ 500
<b>TOTAL ESTIMATED COST</b>	<b>\$14,750</b>

(SALT WATER DISPOSAL FACILITIES)

2400' of 8" class 100 cement-asbestos with fluid tite coupling @ \$2.25 per foot.	\$ 5,400
Laying, ditching, and back fill 2400' of 8" cement-asbestos S.W. Gath. Line @ \$0.85 per foot.	\$ 2,050
Connections for tie-ends and line scraper traps.	\$ 1,100
1 - 125 HP electric motor (less controls)	<del>\$ 2,100</del>
Miscellaneous trucking, labor, electrician, and material	\$ 2,500
<b>TOTAL ESTIMATED COST (FACILITIES)</b>	<b>\$13,150</b>

**TOTAL ESTIMATED COST DISPOSAL WELL AND FACILITIES \$27,900**

JUSTIFICATION FOR EXPENDITURE

The repair cost on the steel injection lines to EPU #59-D, Dakota Sand disposal well, Smith #1, Rehder #7, and Owen-Simons #1 pressure maintenance wells, is averaging \$300 per month and the leak frequency is increasing. (The leaks have damaged and will continue to damage farm land until abandoned or replaced). The estimated cost to replace the high pressure steel lines. \$58,000

The disposal capacity of #1-D is not sufficient to handle the unit salt water volume of 16,000 BPD. Additional disposal capacity is required to comply with Montana Oil & Gas Commission order of sub-surface disposal of all produced Salt Water.

EPU #80 depleted and watered out in the A-Zone and temporarily abandoned. Three workovers failed to increase production. B and C Zones structurally low.

PROPOSED WORKOVER: Set bridge plug w/1 sk cmt above A-Zone perf. Block sqz btm & top of Dakota sd. Selectively perf and wtr frac 208' of Dakota sd in 3 sections.

FACILITIES: Station semi-portable. 1 oil well triplex pump, 100 bbls internally plastic coated steel tk skid mounted and electric controls surplus material.

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Corporation	31.448470%	\$ 8,774
Munoco Company	2.096565%	\$ 585
Placid Oil Company	33.545035%	\$ 9,359
Humble Oil & Refining Company	16.335860%	\$ 4,558
Phillips Petroleum Company	16.335860%	\$ 4,558
C. F. Lundgren	.238210%	\$ 66

APPROVAL OF EXPENDITURE

Requested By: W. T. James 7-20-63 Recommend Approval: \_\_\_\_\_  
Date

\_\_\_\_\_  
L. L. Duncan Date W. J. Thornton Date

APPROVED:

\_\_\_\_\_  
Manager - P. & E.

\_\_\_\_\_  
Date

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION - EAST POPLAR UNIT NO. 80  
SW NW Section 3, T28N, R51E, Roosevelt County, Montana

(TO PREP. EPU #80-D FOR SALT WATER DISPOSAL AND FACILITIES)

JUSTIFICATION:

EPU #80-D Disposal Well, Supplement #1 to A.F.E. #3-1519 is to cover the additional expense due to cementing 5-1/2" casing and requiring extra squeeze job.

EPU #80-D Facilities, Supplement #1 to A.F.E. #3-1519 was overspent because it was anticipated that the work would be done in warmer weather instead of sub zero weather.

TOTAL OVERSPENT 80-D AND FACILITIES \$2,900

APPORTIONMENT OF TOTAL ADDITIONAL EXPENSE

Murphy Corporation	31.448470%	\$ 912
Munoco Company	2.096565%	\$ 60
Placid Oil Company	33.545035%	\$ 973
Humble Oil & Refining Company	16.335860%	\$ 474
Phillips Petroleum Company	16.335860%	\$ 474
C. F. Landgren	.238210%	\$ 7

APPROVAL OF EXPENDITURE

Requested By: <u>MTJ James</u>	<u>1-31-64</u> Date	Recommend Approval:
M. T. James		
<u>L. L. Duncan</u>	<u>1-28-64</u> Date	<u>W. J. Thornton</u> <u>1-28-64</u> W. J. Thornton Date

APPROVED:

MTJ  
 Manager - P. & E. Date

AUTHORITY FOR EXPENDITURE

MURPHY OIL CORPORATION - EAST FORLAR UNIT NO. 20-D  
SW 1/4 Section 3, T28N, R51E, Roosevelt County, Montana  
(Change Tubing String)

**HISTORY:** Converted to a salt water disposal well in the Dakota Sand December, 1963 with 3-1/2" O.D. steel tubing internally coated with Tube-Note TK-2 coating. Indicated tubing leak developed February, 1968 (6 years service). Cumulative salt water disposal through January, 1968 5,701,241 bbls. water.

**PRESENT STATUS:** January, 1968 disposal 100,500 bbls. water at an average injection pressure of 220 PSIG. No tubing survey was run after the results of EPU No. 1-D survey.

**PROPOSAL:** Replace the 3-1/2" O.D. steel tubing with 2.82" O.D. medium heavy service (1200 PSI WP) fiber glass tubing. Run tubing open ended (no packer). Displace casing annulus with 40° gravity crude.

ESTIMATED COST

Drilling Unit, 10 hrs. at \$33.50 per hr.	\$ 350.00
1275' of 2.82" O.D. 1.37# Grd. EVE Fiber Glass Tubing (1200 PSI WP)	
at \$1.90 ft. plus Freight	\$ 6,300.00
Misc. Labor, Trucking, and Material	\$ 500.00
<b>TOTAL ESTIMATED COST</b>	<b>\$ 7,150.00</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 2,249.00
Unoco Company	2.096565%	\$ 150.00
Lacid Oil Company	33.545035%	\$ 2,400.00
Unale Oil and Refining Company	16.335860%	\$ 1,167.00
Drilling Specialties	16.225860%	\$ 1,167.00
J. F. Lundgren	.239210%	\$ 17.00

APPROVAL OF EXPENDITURE

Requested by:

Approved:

W. J. Thornton  
 W. J. Thornton

3-6-68 / 51 W. J. Thornton  
 Date

3-8-68  
 Date

*John R. [unclear]*  
*and [unclear]*  
*Tracy [unclear] 3-27-68*



*M. T. James*

A.F.E. No. 0-1501 -10

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION - EAST POPLAR UNIT NO. 80-D  
SW NW Section 3, T28N, R51E, Roosevelt County, Montana  
(Replace Accumulator Vessel)

HISTORY: Converted East Poplar Unit No. 80 to a salt water disposal well in December, 1963. A 107 bbl. internally plastic coated tank was used as the accumulator vessel. The vessel has required complete recoating and patching once and partial recoating and patching a second time. Leaks are reoccurring, showing a need for replacement of the vessel.

PRESENT STATUS: An average of 104,000 BWPM is being disposed of at this well.

PROPOSEL: Replace the present accumulator vessel with a used L-500 redwood tank.

ESTIMATED COST

Wood Tank L-500 - Erected	\$ 3,500.
20' X 6" Cement Pad	\$ 150
Labor to remove old vessel and hookup new tank	\$ 600
Misc. Labor, Material and Trucking	\$ 250
TOTAL ESTIMATED COST	\$ 4,500

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 1,415
Placid Oil Company	33.545035%	\$ 1,510
Humble Oil and Refining Company	16.335860%	\$ 735
Phillips Petroleum Company	16.335860%	\$ 735
Munoco Company	2.096565%	\$ 94
C. F. Lundgren	.238210%	\$ 11

APPROVAL OF EXPENDITURE

Requested by:

APPROVED:

*M. T. James*  
M. T. James

*1-20-70*  
Date

*W. J. Thornton*  
W. J. Thornton

*1-26-70*  
Date

MEJ/sb  
January 20, 1970

File E.R.U. #80-D

A.F.E. No. 1-1516-10

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION  
EAST POPLAR UNIT NO. 1-D  
SE SE Section 30, T29N, R51E, Roosevelt County, Montana  
EAST POPLAR UNIT NO. 80-D  
SW NW Section 3, T28N, R51E, Roosevelt County, Montana

JUSTIFICATION: The injection pressures have increased and disposal pumps are running 98-100% each day, with only one standby pump.

Well	Date	Pressure	Date	Pressure	Increase
East Poplar Unit No. 1-D	7-70	440 PSI	7-71	480 PSI	40 PSI
East Poplar Unit No. 80-D	7-70	430 PSI	7-71	560 PSI	130 PSI

PROPOSAL: Acidize each well with 1500 gallons 15% HCL with additives to reduce pressure and increase volume. (Both wells to be acidized the same day to reduce total cost.)

ESTIMATED COST

3,000 Gallons Acid and 2 Pump Jobs	\$ 2,100
Misc. Labor, Trucking and Material	\$ 100
TOTAL ESTIMATED COST	\$ 2,200

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 692
Placid Oil Company	33.545035%	\$ 738
Humble Oil and Refining Company	16.335860%	\$ 359
Phillips Petroleum Company	16.335860%	\$ 359
Munoco Company	2.096565%	\$ 46
C. F. Lundgren	.238210%	\$ 6

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

M. T. James  
M. T. James

8-18-71  
Date

J. G. Johnson  
J. G. Johnson

8-23-71  
Date

Alvin Simpson  
Alvin Simpson

8/23/71  
Date

MTJ/sb  
August 18, 1971

*Cost*  
*Approved 1609*  
*406.25 each well*

AUTHORITY FOR EXPENDITUREEAST POPLAR UNIT NO. 80-D - SALT WATER DISPOSAL

PRESENT STATUS: Existing pit is used only when the salt water plant is rendered inoperative to keep wells producing and avoid spills.

JUSTIFICATION: Existing pit is leaking and contaminating land. A damage claim was settled last year (1970) for \$105.00. The lined pit will reduce the possibility of additional damage.

PROPOSAL: Dig new pit, line with 30 mil Hypalon pit liner and pipe into station building to salvage oil and dispose of salt water. (Pit capacity approximately 2,834 bbls.. Hold 18 hrs..) (In 1971 budget.)

ESTIMATED COST

Fill Oil Pit and Dig New Pit	\$ 1,600
84' X 54' 30 Mil Hypalon (Dowell) Liner at \$0.40 Sq. Ft.	\$ 1,825
Pipe and Connections	\$ 400
Labor	\$ 400
Misc. Trucking and Material	\$ 500
<b>TOTAL ESTIMATED COST</b>	<b>\$ 4,725</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 1,486
Placid Oil Company	33.545035%	\$ 1,585
Humble Oil & Refining Company	16.335860%	\$ 772
Phillips Petroleum Company	16.335860%	\$ 772
Munoco Company	2.096565%	\$ 99
C. F. Lundgren	.238210%	\$ 11

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

W. T. James  
W. T. James.

8-11-71  
Date

J. I. Johnson  
Date

Date

Alvin Simpson  
Date

Date

MIJ/sb  
August 11, 1971

AUTHORITY FOR EXPENDITUREEAST POPLAR UNIT NO. 80-D - SALT WATER DISPOSAL

PRESENT STATUS: Existing pit is used only when the salt water plant is rendered inoperative to keep wells producing and avoid spills.

JUSTIFICATION: Existing pit is leaking and contaminating land. A damage claim was settled last year (1970) for \$105.00. The lined pit will reduce the possibility of additional damage.

PROPOSAL: Dig new pit, line with 30 mil Hypalon pit liner and pipe into station building to salvage oil and dispose of salt water. (Pit capacity approximately 2,834 bbls. Hold 18 hrs. ) (In 1971 budget.)

ESTIMATED COST

Fill Oil Pit and Dig New Pit	\$ 1,600
84' X 54' 30 Mil Hypalon (Dowell) Liner at \$0.40 Sq. Ft.	1,825
Pipe and Connections	400
Labor	400
Misc. Trucking and Material	500
<b>TOTAL ESTIMATED COST</b>	<b>\$ 4,725</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 1,486
Placid Oil Company	33.545035%	1,585
Humble Oil & Refining Company	16.335860%	772
Phillips Petroleum Company	16.335860%	772
Munoco Company	2.096565%	99
C. F. Lundgren	.238210%	11

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

MTJ/sb  
M. T. James

8-11-71  
Date

J. L. Johnson  
Date

Alvin Simpson  
Alvin Simpson

9/14/71  
Date

MTJ/sb  
August 11, 1971

Date Job Completed - 10-26-71  
Approx Cost - \$3,540.00  
By - R.C.D.

*Bill Brown*

A.F.E. No. 2-1508-10

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION - EAST POPLAR UNIT SALT WATER STATION NO. 3  
(Confirming Pump Repair)

This A.F.E. is to confirm the repairs on the Oilwell P-346 Triplex plunger pump at East Poplar Unit Salt Water Station No. 3.

ESTIMATED COST

Parts	\$ 3,000
Labor	350
TOTAL ESTIMATED COST	\$ 3,350

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 1,054
Placid Oil Company	33.545035%	1,124
Humble Oil and Refining Company	16.335860%	547
Phillips Petroleum Company	16.335860%	547
Munoco Company	2.096565%	70
C. F. Lundgren	.238210%	8

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

*Bill Brown*  
W. G. Brown

*3-29-72*  
Date

*A. W. Simpson*  
A. W. Simpson

*4/4/72*  
Date

WGB/sb  
March 29, 1972

*Est. job completed 3/17/72*  
*Appr. : 3568*  
*By : [Signature]*

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION - EAST POPLAR UNIT NO. 80-D  
SW Section 3, T28N, R51E, Roosevelt County, Montana

NW

Proposal and Justification: It is proposed to acidize this well with 2000 gallons of 28% HCL.

Injection pressure has increased from 480 PSI in February to 580 PSI in August. In an effort to dispose of more water more efficiently this well should be acidized. Injection pressure was 390 PSI on completion while disposing of better than 5000 BWPD.

ESTIMATED COST

2000 Gallons Of Acid and Service	\$ 2,250
Misc. Labor, Material and Equipment	250
<b>TOTAL ESTIMATED COST</b>	<b>\$ 2,500</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 786
Placid Oil Company	33.545035%	\$ 839
Exxon Company, U.S.A.	16.335860%	\$ 408
Phillips Petroleum Company	16.335860%	\$ 408
Munoco Company	2.096565%	\$ 53
C. F. Lundgren	.238210%	\$ 6

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

W. G. Brown

Date

A. W. Simpson

Date

10/2/73

\$2,200

WGB/sb  
 September 14, 1973

This job went as planned. Pressure, as noted above, was 580 PSI prior to acidizing and was dropped to 440 PSI this A.M. (10-3-73). Besides lowering the injection pressure the pump went down more times than usual.

WGB 10-2-73

Hand copies of 10-1-74  
6-12-74  
OK

A.F.E. No. 4-1520-10

AUTHORITY FOR EXPENDITURE  
MURPHY OIL CORPORATION - EAST POPLAR UNIT NO. 80-D  
SW ~~SW~~ Section 3, T28N, R51E, Roosevelt County, Montana  
NW (Acidize Well)

Proposal and Justification: It is proposed to acidize the Dakota perforations with 2,500 gallons of 28% HCL to remove any scale build up.

Pressure has increased from 400 PSI to 650 PSI causing the disposal pumps to operate a full 24 hours rather than shutting off 3 to 5 hours per day. In an attempt to dispose of more water at a lower pressure this well should be acidized.

ESTIMATED COST

2,500 Gallons of 28% HCL and Services	\$ 2,500
Misc. Labor, Trucking and Supervision	\$ 500
TOTAL ESTIMATED COST	\$ 3,000

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 943	503
Placid Oil Company	33.545035%	\$ 1,006	537
Exxon Company, U.S.A.	16.335860%	\$ 490	261
Phillips Petroleum Company	16.335860%	\$ 490	261
Munoco Company	2.096565%	\$ 63	34
C. F. Lundgren	.238210%	\$ 8	4

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

W. G. Brown

Date 6-11-74

A. W. Simpson

Date 6/11/74

Pumped 1,500 Gallons of acid into tubing 800# Pressure Let soak 2 hours Displaced with 340 barrels water at 5.4 BPM down to 4.0 BPM Pressure 800# throughout

Pumped 1,000 Gallons of acid into tubing Displaced with disposal pump

Pressure Before Treatment 660#  
Pressure After Treatment 460#

Date Job Completed 6-21-73  
Approximate Cost \$2,800  
By Floyd O'Brien

WGB/sb  
June 5, 1974

REC. FILED JUN 21 1977

A.F.E. No. 7-1501-10

MURPHY OIL CORPORATION  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW SW Section 3, T28N, R51E, Roosevelt County, Montana  
(Acidize Well)

It is proposed to treat the Dakota perforations with 2,000 gallons of 28% HCL acid. The injection pressure has increased to 830# with both the Oilwell and National J-60 pumps on. It is hoped that this treatment will drop the pressure to the 600# range.

ESTIMATED COST

2000 Gallons of 28% Acid	\$ 1,500
Supervision and Misc.	\$ 100
TOTAL ESTIMATED COST	\$ 1,600

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 503
Placid Oil Company	33.545035%	\$ 537
Exxon Company, U.S.A	16.335860%	\$ 261
Phillips Petroleum Company	16.335860%	\$ 261
Munoco Company	2.096565%	\$ 34
C. F. Lundgren	.238210%	\$ 4

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy G. Melear

Date

A. C. Simpson

Date

1/25/77



A.F.E. No. 7-1501-10-S1

MURPHY OIL CORPORATION  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW SW Section 3, T28N, R51E, Roosevelt County, Montana  
(Supplement No. 1 - Acidize Well)

This A.F.E. was overspent because of the increase in cost of services and materials.

COST

	<u>A.F.E.</u>	<u>Actual</u>	<u>Supplement</u>
2,000 Gallons of 28% Acid	\$1,500	\$2,422	\$ 922
Supervision and Misc.	\$ 100	\$ 108	\$ 8
Total Cost	\$1,600	\$2,530	\$ 930

APPORTIONMENT OF TOTAL COST

Murphy Oil Corporation	31.448370%	\$ 503	\$ 796	\$ 293
Placid Oil Company	33.545035%	\$ 537	\$ 849	\$ 312
Exxon Company, U.S.A.	16.335860%	\$ 261	\$ 413	\$ 152
Phillips Petroleum Co.	16.335860%	\$ 261	\$ 413	\$ 152
Munoco Company	2.096565%	\$ 34	\$ 53	\$ 19
C. F. Lundgren	.238210%	\$ 4	\$ 6	\$ 2

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy C. Melear  
Billy C. Melear

3-24-77  
Date

A. W. Simpson  
A. W. Simpson

3/28/77  
Date

REC. PROD. JUN 30 1978

A.F.E. No. 8-1521-10

MURPHY OIL CORPORATION  
MURPHY OIL CORPORATION - EAST POPLAR UNIT SALT WATER STATION NO. 3  
SW SW Section 3, T28N, R51E, Roosevelt County, Montana

It is proposed to replace the damaged power end of the National J-60 salt water disposal pump. This replacement is justified since the fluid end is not damaged.

ESTIMATED COST

National J-60 Power Pump End	\$ 3,080
Roustabout Labor	\$ 250
Misc. and Supervision	\$ 100
Total Estimated Cost	\$ 3,430

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448370%	\$ 1,079
Placid Oil Company	33.545035%	\$ 1,151
Exxon Company, U.S.A.	16.335860%	\$ 560
Phillips Petroleum Company	16.335860%	\$ 560
Munoco Company	2.096565%	\$ 72
C. F. L. ndgren	.239210%	\$ 8

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy G. Melear  
Billy G. Melear

6-27-78  
Date

A. W. Simpson  
A. W. Simpson

6/30/78  
Date

50c)

AUTHORITY FOR EXPENDITURE

MURPHY OIL CORPORATION - EAST POPLAR UNIT NO. 80-D  
SW SW Section 3, T28N, R51E, Roosevelt County, Montana  
 (Acidize Well)

Proposal and Justification: It is proposed to acidize the Dakota perforations with 2,500 gallons of 28% HCL to remove any scale build up.

Pressure has increased from 400 PSI to 650 PSI causing the disposal pumps to operate a full 24 hours rather than shutting off 3 to 5 hours per day. In an attempt to dispose of more water at a lower pressure this well should be acidized.

ESTIMATED COST

2,500 Gallons of 28% HCL and Services	\$ 2,500
Misc. Labor, Trucking and Supervision	\$ 500
TOTAL ESTIMATED COST	\$ 3,000


APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 943
Placid Oil Company	33.545035%	\$ 1,006
Exxon Company, U.S.A.	16.335860%	\$ 490
Phillips Petroleum Company	16.335860%	\$ 490
Munoco Company	2.096565%	\$ 63
C. F. Lundgren	.238210%	\$ 8

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

  
 W. C. Brown

Date /

A. W. Simpson

Date

WGB/sb

June 5, 1974.

A.F.E. No. 9-1519-10

MURPHY OIL CORPORATION  
AUTHORITY FOR EXPENDITURE - EAST FOPLAR UNIT NO. 80-D  
SW 9W Section 3, T28N, R51E, Roosevelt County, Montana

It is proposed to install cathodic protection on this salt water installation.

ESTIMATED COST

Materials	\$ 1,100
Labor To Install Equipment	\$ 1,220
Technician To Check & Put Equipment Into Operation	\$ 80
Supervision and Misc.	\$ 100
Total Estimated Cost	\$ 2,500

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 787
Placid Oil Company	33.545035%	\$ 839
Exxon Company, U.S.A.	16.335860%	\$ 408
Phillips Petroleum Company	16.335860%	\$ 408
Munoco Company	2.096565%	\$ 52
C. F. Lundgren	.238210%	\$ 6

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy G. Mclear

11-3-79

Date

A. W. Simpson

Date

0-1516-10  
A.F.E. ~~8X1516X10~~

MURPHY OIL CORPORATION  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW 8W Section 3, T28N, R51E, Roosevelt County, Montana  
i/v

It is proposed to install cathodic protection on this salt water installation.

ESTIMATED COST

Materials	\$ 1,190
Labor to install equipment	1,470
Technician to check & put equipment into operation	93
Supervision and miscellaneous	100
Total Estimated Cost	\$ 2,853

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 898
Placid Oil Company	33.545035%	957
Exxon Company, U.S.A.	16.335860%	466
Phillips Petroleum Company	16.335860%	466
Munoco Company	2.096565%	60
C. F. Lundgren	.238210%	6

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy G. Melear      11/8/79

 4/23/80  
Alvin W. Simpson      Date

BGM:CDF:ch  
March 13, 1980

(OFD)

Approximate Cost

original

REC. NO. OCT 24 1980

A.F.E. No. 0-1516-10-S1

MURPHY OIL CORPORATION  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW SW Section 3, T28N, R51E, Roosevelt County, Montana

Labor to install cathodic protection was considerably less than originally estimated.

ESTIMATED COST

	Original A.F.E.	Actual Cost	Over (Under)
Materials	\$ 1,190	\$ 1,135	(\$ 55)
Labor To Install Equipment	\$ 1,470	\$ 827	(\$ 643)
Technician To Check & Put Equipment Into Operation	\$ 93	\$ 93	-----
Supervision and Miscellaneous	\$ 100	\$ 176	\$ 76
Total Estimated Cost	\$ 2,853	\$ 2,231	(\$ 622)

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil Corporation	31.448470%	\$ 898	\$ 702	(\$ 196)
Placid Oil Company	33.545035%	\$ 957	\$ 748	(\$ 209)
Exxon Company, U.S.A.	16.335860%	\$ 466	\$ 364	(\$ 102)
Phillips Petroleum Company	16.335860%	\$ 466	\$ 364	(\$ 102)
C. F. Lundgren	.238210%	\$ 6	\$ 6	
Munoco Company	2.096565%	\$ 60	\$ 47	(\$ 13)

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Billy G. Melear  
Billy G. Melear

10-21-80  
Date

A. W. Simpson 10/20/80  
A. W. Simpson Date

REC. PROB.

APR 27 1984

A.P.E. No. 4-1506-10

MURPHY OIL USA, INC.  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW NW SECTION 3, T28N, R51E, ROOSEVELT COUNTY, MONTANA

PROPOSAL & JUSTIFICATION:

This SWD well needs to have tubing and packer in it. It presently has 3193' of 2 7/8" fiberglass tubing in it. It is doubtful if this tubing can be unscrewed. It is proposed to run 3200' of 2 7/8" tubing and a coated A-D-1 Baker packer with the packer set at 3205'.

ESTIMATED COST

Rig	\$ 2,000
Water truck	400
Tubing	9,500
Packer	2,500
Roustabout	1,100
Supervision and Miscellaneous	500
<b>TOTAL ESTIMATED COST</b>	<b>\$ 16,000</b>

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil USA, Inc.	31.448470%	\$ 5,032
Petro-Lewis Corporation	33.545035%	5,367
Exxon Company, U.S.A.	16.335860%	2,614
Phillips Petroleum	16.335860%	2,614
Munoco Company	2.096565%	335
C. F. Lundgren	.238210%	38

APPROVAL OF EXPENDITURE

Requested by:

Approved by:

Raymond Reede  
 Raymond Reede

Date

W. Simpson  
 W. Simpson

Date

RR/jh  
 April 24, 1984

DATE JOB COMPLETED	8-9-84
APPROXIMATE COST	\$204,780
SYMBOL	RR

(OFD)

Reg 12/3/84

A.F.E. NO. 4-1506-10-S1

MURPHY OIL USA, INC.  
AUTHORITY FOR EXPENDITURE - EAST POPLAR UNIT NO. 80-D  
SW NW SECTION 3, T28N, R51E, ROOSEVELT COUNTY, MONTANA

This A.F.E. was overspent because the coated tubing cost was more than anticipated.

ESTIMATED COST

	Original	Actual	Supplement #1
Rig	\$ 2,000	\$ 1,594	\$ (406)
Water Truck	400	585	185
Tubing	9,500	14,431	4931
Packer	2,500	2,305	(195)
Roustabout	1,100	647	(453)
Supervision & Miscellaneous	500	916	416
TOTAL ESTIMATED COST	\$ 16,000	\$ 20,478	\$ 4478

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil USA, Inc.	31.448470%	5,032	6,440	1,408
Petro-Lewis Corporation	33.545035%	5,367	6,869	1,502
Exxon Company, U.S.A.	16.335860%	2,614	3,345	732
Phillips Petroleum	16.335860%	2,614	3,345	732
Munoco	2.096565%	335	429	94
C. F. Lundgren	.238210%	38	50	10

APPROVAL OF EXPENDITURE

Requested by:

Raymond D. Reede  
Raymond Reede


11/28/84  
Date

Approved by:

A. W. Simpson  
A. W. Simpson

12/3/84  
Date

RR/jh  
November 28, 1984





A.F.E. No. 2-0400-010  
(REVISION - AFE NO. ONLY)

MURPHY OIL USA, INC.  
AUTHORITY FOR EXPENDITURE  
EAST POPLAR UNIT 80-D  
SW NW SECTION 3, T28N, R51E  
ROOSEVELT COUNTY, MONTANA

REPAIR OF SWD PUMP

PROPOSAL & JUSTIFICATION:

The power end on this SWD pump was starting to get noisy. Upon inspection, it was found the slides in the power end were bad, the cross head pins and bushings were bad and all bearings were wore.

The power end on this pump was completely rebuilt and equipped with Kevlar Packing and stainless steel plungers.

ESTIMATED COST

National-Oilwell Machine work and new parts -----	\$19,200
Roustabout -----	500
Supervision & Miscellaneous -----	300
TOTAL ESTIMATED COST	\$20,000

APPORTIONMENT OF TOTAL ESTIMATED COST

Murphy Oil USA, Inc.	60.363718%	\$12,073
Doil Oil & Gas	20.965647%	4,193
Exxon Company U.S.A.	16.335860%	3,267
Munoco Company	2.096565%	419
C.F. Lundgren	.238201%	48

APPROVAL OF EXPENDITURE

Requested by:

Raymond Reede 1-9-92  
Raymond Reede Date

Approved by:

Sidney A. Campbell 1-13-92  
Sidney Campbell Date

Paul E. Ramsey 1-13-92  
Paul Ramsey Date

RR/jh  
January 9, 1992

DATE JOB COMPLETED	_____
APPROXIMATE COST	_____
BY	_____



(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

NOTICE!

THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION

RECEIVED

## SUNDRY NOTICES AND REPORT OF WELLS

JUL 22 1958

OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF MONTANA	
Notice of Intention to Drill	Subsequent Report of Water Shut-off
Notice of Intention to Change Plans	Subsequent Report of Shooting, Acidizing, Cementing
Notice of Intention to Test Water Shut-off	Subsequent Report of Altering Casing
Notice of Intention to Redrill or Repair Well	Subsequent Report of Redrilling or Repair
Notice of Intention to Shoot, Acidize, or Cement	Subsequent Report of Abandonment
Notice of Intention to Pull or Alter Casing	Supplementary Well History
Notice of Intention to Abandon Well	Report of Fracturing
	Workover History

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

July 16, 1958

Following is a ~~notice of intention to do work~~ report of work done on land ~~leased~~ described as follows:

LEASE EPU #3649 (Allotted de Urena  
1-37-Ind-12914)

MONTANA  
(State)

Roosevelt  
(County)

East Poplar  
(Field)

Well No. 80 SW NW Sec. 3 26N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1980 ft. from  $\frac{N}{XS}$  line and 660 ft. from  $\frac{E}{W}$  line of Sec. 3

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

Approved subject to conditions on reverse of form

Date 7-21-58

By John R. H. L. Title

District Office Agent

Company MURPHY CORPORATION

By M. J. James

Title Field Production Superintendent

Address Poplar, Montana

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

JUL 18 1958

## GENERAL RULES

201, 202, 213,  
216, 219, 233.1

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

NOTICE!  
THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION.

RECEIVED

MAR 24 1959

## SUNDRY NOTICES AND REPORT OF WELLS

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement	<input checked="" type="checkbox"/>	Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

March 17, 1959

Following is a { notice of intention to do work } on land { ~~xxxxxx~~ leased } described as follows:

LEASE 1-37-Ind-12914 (deUrena)

MONTANA  
(State)Roosevelt  
(County)East Poplar  
(Field)Well No. 80 SW SW NW Section 3 28N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)The well is located 1982 ft. from { N } line and 761 ft. from { XXXX } line of Sec. 3  
W

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'

## READ CAREFULLY

## DETAILS OF PLAN OF WORK

## READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

Re-acidize the "A" Zone (5456-5474') with 3000 gallons Howco HvAcid. Acidize down casing annulus, pump test.

RECEIVED

MAR 19 1959

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS

Approved subject to conditions on reverse of form

Date 3-23-59

By John P. H. [Signature] Title

District Office Agent

Company Murphy Corporation

By M. Y. James Title Field Production Superintendent

Address Poplar, Montana

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

NOTICE!  
THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION.

APR 17 1959

SUNDRY NOTICES AND REPORT OF WELLS

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	
		Workover History	XXX

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

March 25, 1959

Following is a ~~report of work done~~ on land ~~owned~~ leased described as follows:

LEASE 1-37-Ind-12914 (deUrena)

MONTANA  
(State)

Roosevelt  
(County)

East Poplar  
(Field)

Well No. 80 SW SW NW Section 3 28N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from <sup>N</sup> ~~XXX~~ line and 761 ft. from <sup>XXX</sup> ~~W~~ line of Sec. 3

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

SEE ATTACHED SHEETS

RECEIVED  
APR 7 1959

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

U.S. 4. 8 approved 3-27-59  
Approved subject to conditions on reverse of form

Date 4-15-59

By *John E. H. Smith* Title

District Office Agent

Company Murphy Corporation

By *M. J. James*

Title Field Production Supt.

Address Poplar, Montana

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

OVER

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

NOTICE!  
THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION.

RECEIVED

SUNDRY NOTICES AND REPORT OF WELLS

APR 26 1960

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	
Notice of Intention to Workover	XXX		

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

April 14

19 60

Following is a {notice of intention to do work} on land {~~owned~~ leased} described as follows:

LEASE 1-37-Ind-12914 (deUrena)

MONTANA  
(State)

Roosevelt  
(County)

East Poplar  
(Field)

Well No. 80 SW SW NW Section 3 28N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from {N} line and 761 ft. from {XXX} line of Sec. 3  
{W}

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'.

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

The production has dropped to 3 BOPD from the "A" Zone perforations (5456' to 5474'). Workover to perforate the "A" Zone at 5492' with Dowell abrasive jet 2 holes, 180° apart, acidize with 500 gallons, acidize through retrievable packer to isolate perforation 5456-74'. Test and produce co-mingled, the "A" Zone perforations 5456'-74' and 5492'.

RECEIVED

APR 13 1960

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

Approved subject to conditions on reverse of form

Date 4-25-60

By John R. H. Smith Title

District Office Agent

Company MURPHY CORPORATION

By M. J. James

Title Field Production Superintendent

Address P. O. Box 547, Poplar, Montana

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

WHEN USED AS PERMIT TO DRILL, THIS EXPIRES 90 DAYS FROM DATE OF APPROVAL

OVER

GENERAL RULES  
201, 202, 213,  
216, 219, 233.1

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

NOTICE!

THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION.

RECEIVED

MAY 16 1960

## SUNDRY NOTICES AND REPORT OF WELLS

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	
		Workover History	XX

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

May 9

19 60

Following is a ~~report of work done~~ on land ~~leased~~ described as follows:

LEASE 1-37-Ind-12914 (deUrena)

MONTANA  
(State)Roosevelt  
(County)East Poplar  
(Field)

Well No. 80 SW SW NW Section 3 28N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from { N } line and 761 ft. from { W } line of Sec. 3.  
~~XXXX~~

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

See attached sheets.

RECEIVED

MAY 12 1960

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

Approved subject to conditions on reverse of form

Date 5-13-60

By [Signature] Title

District Office Agent

Company MURPHY CORPORATION

By [Signature]

Title Field Production Superintendent

Address Poplar, Montana

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

WHEN USED AS PERMIT TO DRILL, THIS EXPIRES 90 DAYS FROM DATE OF APPROVAL

OVER

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

SUNDRY NOTICES AND REPORT OF WELLS

NOTICE!  
THIS FORM BECOMES A  
PERMIT WHEN STAMPED  
APPROVED BY AN AGENT  
OF THE COMMISSION.

OCT 1 1962

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well (Temp.)	xx	Report of Fracturing	

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

September 24 1962

Following is a { notice of intention to do work } on land { ~~leased~~ } described as follows:

LEASE 1-37-Ind-12914 (deUrena)

MONTANA Roosevelt East Poplar  
(State) (County) (Field)

Well No. 80 SW SW NW Section 3 28N 51E M.P.M.  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from { N } line and 761 ft. from { W } line of Sec. 3

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069'

READ CAREFULLY

DETAILS OF PLAN OF WORK

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing, etc.)

DETAILS OF WORK  
RESULT

EPU #80. Completions have been attempted & made in the following intervals:

Perforations	Accum. Prod.	Status
5456-5474 (Completion)	47,982 BO, 58,390 BW	Depleted
5492 (WO #3)	187 BO, 9,110 BW	Temporarily Abandoned

EPU #80 has been temporarily abandoned due to production depletion below economical limits. Casing will not be pulled or well plugged until further evaluation studies are made to determine possible use as a pressure maintenance or S.W. Disposal Well.

Approved subject to conditions on reverse of form

Date Sept 28, 1962

By R M Watkins Title

District Office Agent

Company Murphy Corporation

By M J James

Title Field Production Supt.

Address Poplar, Montana

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

WHEN USED AS PERMIT TO DRILL, THIS EXPIRES 90 DAYS FROM DATE OF APPROVAL

OVER




(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

SUNDRY NOTICES AND REPORT OF WELLS



OCT 2 - 1963

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	
Convert to Disposal	XXXXXX		

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

September 30, 1963

Following is a ~~notice of intention to do work~~ notice of intention to do work on land ~~owned~~ leased described as follows:

LEASE A.L. 12914

MONTANA  
(State)

Roosevelt  
(County)

East Poplar Unit  
(Field)

Well No. 80 SW NW Section 3 T28N R51E MPM  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from N line and 761 ft. from E line of Sec. 3

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069 KB

RECEIVED

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudlogging jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

HISTORY: Completed July 29, 1956 from the <sup>A</sup> Zone (5656-74'). Three workovers failed to maintain commercial production, depleted and temporarily abandoned April 1960 pumping at the rate of 7 BOPD, 361 BWPB, uneconomical. From drill stem test structural position etc. there is no known formation capable of commercial production.

To comply with Montana Oil & Gas Commission Order #10-62. Additional disposal capacity is needed to dispose of the salt water produced from East Poplar Unit Wells.

PROPOSAL: To convert EPU #80 to #80-D Disposal into the Dakota Sand. Set cast iron bridge plug at 5300' with 1 sack cement. Cement block squeeze the Dakota Sand 3590' and 3185', selectively perforate and water frac the Dakota Sand. 3218-50', 3284-3410' and 3500-50'. Run 3-1/2" tubing and set on retrievable packer at 3150'.  
Approved subject to conditions on reverse of form

Company Murphy Corporation

Date Oct 1, 1963

By M. J. James

By P. M. Watkins  
Title

Title Field Production Superintendent

District Office Agent

Address P.O. Box 547, Poplar, Montana 59255

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

WHEN USED AS PERMIT TO DRILL, THIS EXPIRES 90 DAYS FROM DATE OF APPROVAL

OVER

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEYSUBMIT IN DUPLICATE  
(Other instructions on reverse side)Form approved.  
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

A.L. 12914

8. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME

East Poplar

8. FARM OR LEASE NAME

9. WELL NO.

EPU #80

10. FIELD AND POOL, OR WILDCAT

East Poplar Unit

11. SEC. T., R., M., OR BLK. AND

Section 3, T28N, R51E,  
SW NW

12. COUNTY OR PARISH

Roosevelt

13. STATE

Montana

## SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>	U. S. GEOLOGICAL SURVEY
2. NAME OF OPERATOR Murphy Corporation	RECEIVED
3. ADDRESS OF OPERATOR P.O. Box 547, Poplar, Montana	OCT 1 1963
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface	BILLINGS, MONTANA

1982' from N line and 761' from A line of Section 3

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GB, etc.)

2069 KB.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

## NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other) Convert to Disposal

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON\*

CHANGE PLANS

## SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

**HISTORY:** Completed July 29, 1956 from the A Zone (5656-74'). Three workovers failed to maintain commercial production, depleted and temporarily abandoned April 1960 pumping at the rate of 7 BOPD, 361 BWPD, uneconomical. From drill stem test structural position etc. there is no known formation capable of commercial production.

To comply with Montana Oil & Gas Commission Order #10-62. Additional disposal capacity is needed to dispose of the salt water produced from East Poplar Unit Wells. **PROPOSAL:** To convert EPU #80 to #80-D Disposal into the Dakota Sand. Set cast iron bridge plug at 5300' with 1 sack cement. Cement block squeeze the Dakota Sand 3590' and 3185', selectively perforate and water frac the Dakota Sand. 3218-50', 3284-3410' and 3500-50'. Run 3-1/2" tubing and set on retrievable packer at 3150'.

Approved OCT 2 1963  
(ORIG. SGD.) HILLARY A. ODEN

District Engineer

18. I hereby certify that the foregoing is true and correct

ORIGINAL SIGNED BY M. T. JAMES

TITLE Field Production Superintendent September 30, 1963

(This space for Federal or State office use)

APPROVED BY  
CONDITIONS OF APPROVAL, IF ANY:


TITLE

DATE

(SUBMIT IN QUADRUPLICATE)

TO

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY



SUNDRY NOTICES AND REPORT OF WELLS

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

Notice of Intention to Drill		Subsequent Report of Water Shut-off	
Notice of Intention to Change Plans		Subsequent Report of Shooting, Acidizing, Cementing	
Notice of Intention to Test Water Shut-off		Subsequent Report of Altering Casing	
Notice of Intention to Redrill or Repair Well		Subsequent Report of Redrilling or Repair	
Notice of Intention to Shoot, Acidize, or Cement		Subsequent Report of Abandonment	
Notice of Intention to Pull or Alter Casing		Supplementary Well History	
Notice of Intention to Abandon Well		Report of Fracturing	
		Report of Workover	XXXX

(Indicate Above by Check Mark Nature of Report, Notice, or Other Data)

January 27, 1964

Following is a ☒ report of work done ☐ on land ☒ leased described as follows:

LEASE A.L. 12914

MONTANA  
(State)

Roosevelt  
(County)

East Poplar Unit  
(Field)

Well No. 80 SW NW Section 3 T28N 51E MPM  
(m. sec.) (Township) (Range) (Meridian)

The well is located 1982 ft. from { N } line and 761 ft. from { E } line of Sec. 3

(Locate accurately on Plat on back of this form the well location, and show lease boundary.)

The elevation of the derrick floor above the sea level is 2069 KB

READ CAREFULLY

DETAILS OF PLAN OF WORK

READ CAREFULLY

(State names of and expected depths to objective sands; show size, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work, particularly all details results Shooting, Acidizing, Fracturing.)

DETAILS OF WORK  
RESULT

See attached workover sheet.

RECEIVED

JAN 25 1964

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA BILLINGS

Approved subject to conditions on reverse of form

Date 1-29-64  
By [Signature] Title  
District Office Agent

Company Murphy Oil Corporation  
By [Signature]  
Title Field Production Superintendent  
Address P.O. Box 547, Poplar, Montana 59255

NOTE:—Reports on this Form to be submitted to the District Agent for Approval in Quadruplicate.

WHEN USED AS PERMIT TO DRILL, THIS EXPIRES 90 DAYS FROM DATE OF APPROVAL

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

SUBMIT IN TRIPLICATE  
(Other instructions on reverse side)

Form approved.  
Budget Bureau No. 42-R1424.

LEASE DESIGNATION AND SERIAL NO.

**I-37-IND-12914**

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

*Fort Pick*

7. UNIT AGREEMENT NAME

**East Poplar**

8. FARM OR LEASE NAME

9. WELL NO.

**SPU #80**

10. FIELD AND POOL, OR WILDCAT

**East Poplar Unit**

11. SEC. T. R. M. OR BLM. AND SURVEY OR AREA

**SW 1/4 Section 3, T28N, R51E**

12. COUNTY OR PARISH

**Reynolds**

13. STATE

**Montana**

**SUNDRY NOTICES AND REPORTS ON WELLS**

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

**Murphy Oil Corporation**

3. ADDRESS OF OPERATOR

**Poplar, Montana**

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.)

At surface

**BILLINGS, MONTANA**

**1982' from N line and 761' from W line of Section 3**

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

**2069 KB.**

18.

**Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data**

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON\*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT

**Workover**

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

**See attached workover sheet.**

18. I hereby certify that the foregoing is true and correct

ORIGINAL SIGNED BY **M. T. JAMES**

SIGNED

TITLE **Field Production Superintendent**

DATE **January 27, 1964**

(This space for Federal or State office use)

**DISTRICT ENGINEER**

APPROVED BY **(ORIG. SIGNED) HILLARY A. GORDON**

TITLE

DATE

**JAN 28 1964**

CONDITIONS OF APPROVAL, IF ANY:

\*See Instructions on Reverse Side

Form 1160-5  
(November 1984)  
(Previously 11-111)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

ADMIT IN TRIPLICATE  
(Other Initials) (You to  
your side)

Form approved  
Budget Bureau No. 1004-0145  
Expiring August 31, 1985  
D. LEASE IDENTIFICATION AND SERIAL NO.  
I-37-IND-12914  
D. INDIAN, ALLOTTEE OR TRIBE NAME

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input checked="" type="checkbox"/> Disposal	2. NAME OF OPERATOR Murphy Oil USA, Inc.	3. ADDRESS OF OPERATOR P.O. Box 547, Poplar, MT 59255	4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1982' from North line and 761' from West line	5. PERMIT NO. EPA# MTS21PE-0026	6. ELEVATIONS (Show whether OP, RT, CR, etc.) 2069' KB	7. FIELD AND POOL, OR WILDCAT East Poplar Unit	8. TERM OR LEASE NAME East Poplar Unit	9. WELL NO. 80-D	10. FIELD AND POOL, OR WILDCAT East Poplar Unit	11. SEC., T., R., M., OR BLE. AND SURVEY OR AREA SW NW Sec. 3, T28N, R51E	12. COUNTY OR PARISH Roosevelt	13. STATE MT
---	---	--	--	------------------------------------	---	---	---	---------------------	--	--	-----------------------------------	-----------------

14. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER Casing <input type="checkbox"/>	WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING Casing <input type="checkbox"/>
ABANDON OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	ABANDONING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input checked="" type="checkbox"/> Emergency Pit Approval	(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

15. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

1. Type of pit: Emergency salt water pit
2. Size of pit: 72' x 42' x 6'
3. Location of pit: SW NW Section 3, T28N, R51E
4. Plumbing to pit: Schematic attached
5. In cut or fill material: Cut Material
6. Fencing: 4' mesh
7. Pit lined: Yes
8. Any problems, potential problems or corrective action required? No

18. I hereby certify that the foregoing is true and correct

SIGNED <u>Raymond Reed</u>	TITLE <u>District Manager</u>	DATE <u>9-8-88</u>
(This space for Federal or State office use)		
APPROVED BY <u>Arnold E. Dargatzis</u>	TITLE <u>ADM-MINERALS</u>	DATE <u>SEP 13 1988</u>
CONDITIONS OF APPROVAL, IF ANY:		

See Attached for  
Conditions of Approval

\*See Instructions on Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

*Received Poplar  
11-05-91*

Ref: 8WM-DW

OCT 31 1991

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, MT 59255

RE: UNDERGROUND INJECTION CONTROL (UIC)  
EPA Permit No. MT2026-00026  
East Poplar Unit (UPU) No. 80-D  
Roosevelt County, Montana

Dear Mr. Reede:

Staff members of the Environmental Protection Agency's (EPA), UIC Implementation Section, reviewed the August 8, 1991, Halliburton Differential Temperature Log and Halliburton Fluid Travel Log for the EPU No. 80-D. They concluded that the Temperature Log shows characteristics which indicate there may be flow behind the longstring above the perforations, and that this flow may extend as high as 3100 feet kelly bushing (KB). The absence of a shut-in Temperature Log makes it difficult to conclusively evaluate conditions behind the pipe. We suggest that a Temperature Log be run after a minimum shut-in time of six (6) hours. We also suggest that the log run commence farther up the hole, i.e., at 150 feet KB, which is the top of the only underground source of drinking water (USDW) identified in the EPU No. 80-D. We also require that an explanation of the cause for the "tool log spike" shown on the Temperature Log be included in the logging report.

The Radioactive Tracer Log continues to be inconclusive. Murphy Oil USA did not utilize the procedural tracer survey guidelines approved by the EPA for detection of flow behind pipe (copy enclosed). The approved method calls for logging the well during injection to monitor the change and movement of the radioactive slug with time. The determination of fluid flow behind the casing would involve the following action:

- a) Place radioactive slug at least 20 feet above injection perforations during injections at a constant rate with a surface pressure close to the normal operating pressure;
- b) Make overlapping logs of the slug as it moves into the perforations;

Mr. Raymond Reede  
EPU No. 80-D  
Page Two


- c) After the slug has moved into the perforations, make several logs up the hole to a point above the disposal zone confining interval; and
- d) Logging should continue until the slug has completely disappeared.

It is observed that neither Halliburton nor Murphy Oil supplied key information on the logs which are necessary for the logs interpretation. Information which must be supplied includes:

- a) The actual injection rate and pressure;
- b) The approximate down hole velocity used to estimate approximate flow time of the slug into the formation; and
- c) A narrative of how the log was run and what the results mean.

Murphy Oil USA, Inc. must conduct a new Radioactive Tracer Survey and Differential Temperature Survey within ninety (90) days of receipt of this letter. If you have any questions in regard to this action or with test procedures, please contact Emmett Schmitz at (303) 293-1436. Please send all communication to the ATTENTION: EMMETT SCHMITZ citing MAIL CODE: 8WM-DW very prominently.

Sincerely,

  
Max H. Dodson, Director  
Water Management Division

Enclosure: Accepted Radioactive Tracer Survey Guideline and Procedure.

cc: Jim Boyter, MO

Debi Madison  
Fort Peck Assiniboine & Sioux Tribes  
Office of Environmental Protection  
Box 1027  
Poplar, MT 59255

## Accepted Radioactive Tracer Survey Guidelines & Procedures

The purpose of running a radioactive tracer survey (RATS) in an injection well is twofold:

1. To show whether injected fluids will leak through a hole or holes in the casing above the casing shoe; and/or
2. To show whether injected fluids will migrate vertically outside the casing after reaching the casing shoe.

### GUIDELINES:

- (a) The gamma ray log may be run up to 60 feet/minute at a time constant (TC) of 1 second or up to 30 ft/min at a TC of 2 sec or up to 15 ft/min at a TC of 4 sec. INDICATE LOGGING SPEED AND TIME CONSTANT on the log heading.
- (b) INCLUDE A COLLAR LOCATOR for depth control.
- (c) Vertical scale may be 1 inch, 2 inches, or 5 inches per 100 ft.
- (d) INDICATE IN API UNITS THE HORIZONTAL SCALE. If one gamma ray curve is recorded, make sure the sensitivity used is such that the tracer material will be obvious when detected and will not be confused with normal "hot spots" in the formations (i.e. gamma ray sensitivity should be such that lithology can be correlated).
- (e) INDICATE BEGINNING AND ENDING CLOCK TIMES on each log pass.
- (f) INDICATE INJECTION RATE (if any) during each log pass.
- (g) INDICATE VOLUME OF FLUID INJECTED between log passes.
- (h) INDICATE VOLUME AND CONCENTRATION OF EACH SLUG of tracer material.

### PROCEDURE:

- (1) Run a base log from below the perforated interval (and/or the injection zone) to at least 500 feet above the zone (or to at least above the confining zone).
- (2) Pump tracer material in and trace the slug with the gamma ray tool. Run short OVERLAPPING log passes following the tracer downhole. It is suggested that pumping not occur during logging; that is, pump only to move tracer downhole between log passes to prevent premature loss of the tracer.



RATS Guidelines & Procedures  
Page 2

- (3) As soon as the tracer reaches the injection zone, stop pumping (or slow as much as possible) and run a log from below the perforated interval (and/or the injection zone) to 500 feet above the injection zone (or to at least above the confining zone).
- (4) As tracer is pumped (at or near the maximum proposed injection pressure and rate) out of the casing into the wellbore, run a few short log passes from an appropriate distance below the slug depth to an appropriate distance above the slug depth, showing the pathway the tracer follows. Continue running passes UNTIL THE TRACER VIRTUALLY DISAPPEARS. The last pass should essentially duplicate the base log.
- (5) More than one pass may be shown on a log segment as long as each gamma ray curve along with its collar locator is distinguishable. Otherwise, make each pass on a separate log segment.
- (6) An interpretation of the log must be supplied by the logging company.
- (7) Include a schematic diagram of the well on the log. The diagram should show the casing diameters and depths, tubing diameter and depth (if any), perforated intervals or open hole, and total or plugged back depth. Indicate the pathway the tracer material appears to have taken using arrows.



POST OFFICE BOX 547  
POPLAR, MONTANA 59255

September 3, 1991


Mr. Emmett Schmitz  
United States Environmental Protection Agency  
Region VIII - Suite 500  
999 18th Street  
Denver Colorado 80202-2405

RE: EPU Permit No. MT2026-00026  
✓ East Poplar Unit No. 80-D

Dear Mr. Schmitz:

We reran the Differential Temperature Log (DTL) and the Tracer Survey on 80-D. These logs are enclosed.

Sincerely,

  
Raymond Reede  
District Manager

Enclosures

cc: Jim Boyter  
Debi Madison  
Paul Ramsey





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII  
ONE DENVER PLACE — 999 18TH STREET — SUITE 1300  
DENVER, COLORADO 80202-2413

FINAL  
UNDERGROUND INJECTION CONTROL AQUIFER EXEMPTION  
Related to UIC Permit Number: MTS21PE-0026

— In compliance with provisions of the Safe Drinking Water Act, as amended, (42 U.S.C. 300f-300j-9, commonly known as SDWA) and attendant regulations incorporated by the U. S. Environmental Protection Agency under Title 40 of the Code of Federal Regulations,

The Dakota Sandstone located:


- 1.) vertically from 3,218 to 3,512 feet below ground level, and
- 2.) Laterally within one-half mile radius from the injection well (commonly called EPU 80-D) located NE/4, SW/4 Section 3, Township 28 North, Range 51 East of Roosevelt County, Montana,

is exempted as an Underground Source of Drinking Water.

This aquifer exemption is expanded in conjunction with the Underground Injection Control Permit issued to Murphy Oil USA, Inc. of El Dorado, Arkansas, for the injection of water for disposal purposes.

This aquifer exemption has no expiration date.

— Signed this 31st day of March, 1986.

  
Max H. Dodson, Director  
Water Management Division

East Poplar Unit

7-1-81

U.S.G.S. Office:

Billings, MT 59103

Operator:

Murphy Oil Co.

Address:

P.O. Box 2550

Address:

Poplar, MT

Site:

F-BAT EPU

To (company representative):

Ray Reede

THE FOLLOWING LIST OF INCIDENTS OF NONCOMPLIANCE WERE FOUND BY U.S.  
GEOLOGICAL SURVEY INSPECTORS ON THE DATE AND AT THE SITE LISTED ABOVE.

## WARNING IS HEREBY GIVEN TO CORRECT THE FOLLOWING DEFICIENCIES:

Incident of Noncompliance (INC)

Corrective Action Taken

Date

Cleanup excessive oil spillage around F-BATTERY - After oil and water is removed and located, dry, cover with clean dirt.

7-8-81

Repair ruptured line between well 80-D and F-BATTERY

re-linked

Reclaim all oil spilled and contained in pit and surrounding area around well 80-D.

7-16-81

Seal all load lines (2) and oil dump lines on 2 tanks and re-link lines on 2 tanks

7-3-81

(If more space is needed attach separate sheet)

YOU ARE HEREBY ORDERED TO SUSPEND (SHUT-IN) THE FOLLOWING OPERATION(S):

(Related INC marked with asterisk\*)

NOT SUSPENDED; HOWEVER, OIL SEALS MUST

Be in place within 72 HRS OR FEED SEALS WILL BE USED.

Signature of U.S.G.S. Representative:

Date: 7-1-81

Time:

Each incident of noncompliance listed must be corrected within <sup>\*</sup>15 days. for cleanup, 72 HRS ON SEALS AND REPAIRThe date each incident of noncompliance was corrected must be reported to the U.S.G.S. office at the address shown within <sup>\*</sup> days from the date of this Notice.

No operation suspended by this order may be resumed until the corrective action has been inspected by the U.S.G.S.

Failure to suspend an operation as ordered, to correct the cited deficiencies within the prescribed time, or to report the corrective action within the prescribed time can result in further enforcement actions being taken in accordance with Title 30 Code of Federal Regulations.

## AUTHORIZATION TO RESUME OPERATION

Signature of U.S.G.S. Representative:

Date:

Time:


DUPLICATE INVOICE

Form <b>4</b>	<b>EPA</b>	UNITED STATES ENVIRONMENTAL PROTECTION AGENCY UNDERGROUND INJECTION CONTROL PERMIT APPLICATION (Collected under the authority of the Safe Drinking Water Act, Sections 1421, 1422, 40 CFR 144)	ID NUMBER	
UIC			T/A	C
READ ATTACHED INSTRUCTIONS BEFORE STARTING FOR OFFICIAL USE ONLY				
Application approved mo day year		Date Received mo day year		Permit/Well Number
				EPU 80-D
II. FACILITY NAME AND ADDRESS			III. OWNER/OPERATOR AND ADDRESS	
Facility Name East Poplar Unit			Owner/Operator Name Murphy Oil USA, Inc.	
Street Address P. O. Box 547			Street Address 200 Peach Street	
City Poplar		State MT	ZIP Code 59255	City El Dorado
		State AR	ZIP Code 71730	
IV. OWNERSHIP STATUS (Mark 'x')			V. SIC CODES	
<input type="checkbox"/> A. Federal <input type="checkbox"/> B. State <input checked="" type="checkbox"/> C. Private				
<input type="checkbox"/> D. Public <input type="checkbox"/> E. Other (Explain)				
VI. WELL STATUS (Mark 'x')				
<input checked="" type="checkbox"/> A. Operating		<input checked="" type="checkbox"/> B. Modification/Conversion <input type="checkbox"/> C. Proposed		
Date Started mo day year 1 3 64		Permitting Existing Well Approved by Rule		
VII. TYPE OF PERMIT REQUESTED (Mark 'x' and specify if required)				
<input checked="" type="checkbox"/> A. Individual <input type="checkbox"/> B. Area		Number of Existing wells	Number of Proposed wells	Name(s) of field(s) or project(s) East Poplar Unit
VIII. CLASS AND TYPE OF WELL (see reversal)				
A. Class(es) (enter code(s))	B. Type(s) (enter code(s))	C. If class is "other" or type is code 'x,' explain		D. Number of wells per type (if area permit)
11 D				
IX. LOCATION OF WELL(S) OR APPROXIMATE CENTER OF FIELD OR PROJECT				
A. Latitude		B. Longitude		Township and Range
Deg Min Sec	Deg Min Sec	Twsp Range Sec	1/4 Sec	Foot from Line
		28N 51E 3	NW	1980 N 660 W
X. INDIAN LANDS (Mark 'x')				
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
XI. ATTACHMENTS				
(Complete the following questions on a separate sheet(s) and number accordingly; see instructions) FOR CLASSES I, II, III (and other classes) complete and submit on separate sheet(s) Attachments A — U (pp 2-6) as appropriate. Attach maps where required. List attachments by letter which are applicable and are included with your application:				
XII. CERTIFICATION				
I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)				
Name and Title (Type or Print)				B. Phone No. (Area Code and No.)
Signature				O. Date Signed

Submit in triplicate to:

**MONTANA BOARD OF OIL AND GAS CONSERVATION**  
Billings or Shelby Office

**Application For Permit To Construct Or Operate An Earthen Pit Or Pond**  
(Production Facility Only)



New pit <input type="checkbox"/>	Existing pit <input checked="" type="checkbox"/>	Lease Name: East Poplar Unit 80-D
Operator Murphy Exploration & production Company		Lease Type (Private/State/Federal): Federal
Address P.O. Box 547		Unit Name: East Poplar Unit
City Poplar	State MT	Field or Area: East Poplar
Zip Code 59255		County: Roosevelt
Telephone Number (406) 768-3612	Telefax Number (406) 768-5497	Location of pit - 1/4 Section, Township, and Range: SW NW Sec. 3, T28N, R51E

Describe the purpose of the earthen pit or pond (If temporary, indicate anticipated time pit will be in use):

Emergency salt water storage. The only time this pit is used is when there is a problem with the SWD system.

Number and type of wells using this pit: \_\_\_\_\_ Oil \_\_\_\_\_ Gas 1 Injection \_\_\_\_\_ Other (specify)

Average water inflow: 0 bbls./day Maximum pit volume: 4000 bbls.

Describe type and origin of fluids, name and location of source wells, producing formations, and approximate fluid volume contributed by each well:

Salt water from the Heath and Madison Formation from wells in the East Poplar Unit approximately 3400 BWPD

Provide a copy of full water analysis with application for new pits only. Board may require a water analysis for existing pits.

The water analysis must include the date and source of sample (treater, wellhead, pit, etc.), and the name, address, and telephone numbers of laboratories. Standard methods must be used for all collection and testing of samples.

<b>BOARD USE ONLY</b>		Signed (Agent) <u>Sidney W. Campbell</u> Typed name and Title <u>Sidney W. Campbell</u> Staff Operations Coordinator Date <u>March 30, 1993</u>
Approved (date) <u>MAR 31 1993</u>	Permit Expires _____	
Accepted for record purposes only		
CONDITIONS OF APPROVAL ON REVERSE.		

SUPPLEMENTAL INFORMATION

Attach the following information to this permit application:

FOR NEW PITS: Attach diagrams of a top view and two side views of the pit or pond. The diagrams must show the length, width, depth, cut and fill, maximum fluid level, area of topsoil stockpile, and the height and width of berms. Identify the location of additional items such as fences, liners, monitoring wells, tanks, lines, siphons, or other equipment if used. Diagrams need not be prepared by an engineer or surveyor.

FOR EXISTING PITS: Attach color 3" x 5" (or larger) photographs of existing pit or pond. Indicate the date photographs were taken and name and address of the photographer. All photographs must accurately portray the size and condition of the pit or pond at the time this application is submitted.

Describe the type and amount of material or liner used, if any, to seal the pit or pond. If a synthetic liner is used, indicate the liner thickness (mils), bursting strength, tensile strength, tear strength, puncture resistance, hydrostatic resistance, or attach the manufacturer's specification sheet to this application.

30 mil Hypalon pit liner manufacturer specifications enclosed

This pit is covered with a 1" square netting.

Describe the proposed method of treatment and/or disposal of the liquid and solid contents upon abandonment of the pit or pond:

Liquids will be pumped down the SWD well.

Solids will be mixed and diluted with available soil to meet state and federal regulations.

NOTE: The Operator must comply with all applicable federal, state, county, and local laws and regulations concerning handling, treatment, and disposal of wastes.

Is pit or pond was previously permitted by Bureau of Land Management (operator(s)) on the 13 / of September, 19 88. Attach a copy(ies) of the previous permit(s).

STANDARD USE ONLY

CONDITIONS OF APPROVAL

The operator must comply with the following condition(s):

Failure to comply with conditions of approval may void this permit.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460ENVIRONMENTAL  
PROTECTION AGENCY

## WELL REWORK RECORD

## NAME AND ADDRESS OF PERMITTEE


Murphy EXPRO.  
P.O. Box 548  
Poplar, Mt 59255-0547

## NAME AND ADDRESS OF CONTRACTOR

H & H Well Service  
P.O. Box 1244  
Poplar, Mt. 59255-1244

MAY 11 1999

MONTANA OFFICE

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

STATE

MT.

COUNTY

Roosevelt

PERMIT NUMBER

MTS 2026-0026

## SURFACE LOCATION DESCRIPTION

1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface 1982'  
Location \_\_\_\_\_ ft. from (N/S) \_\_\_\_\_ Line of quarter section  
and 761 ft. from (E/W) \_\_\_\_\_ Line of quarter section

MT 00026

## WELL ACTIVITY

- ☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

Lease Name

Total Depth Before Rework

3575'

Total Depth After Rework

3575'

Date Rework Commenced

5-4-99

Date Rework Completed

505099

TYPE OF PERMIT

- ☒ Individual  
☐ Area  
 Number of Wells 1

Well Number

80D

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

Received  
Office of Enforcement

MAY 26 1999

Compliance &amp; Env. Justice

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

DESCRIBE REWORK OPERATIONS IN DETAIL

USE ADDITIONAL SHEETS IF NECESSARY

Hydrotest tubing. Run and set  
packer.

WIRE LINE LOGS, LIST EACH TYPE

Log Types

Logged Intervals

REVIEWED

BY: *ja*

DATE: 6/10/99

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Raymond Reede  
District Manager

SIGNATURE

Raymond Reede

DATE SIGNED

May 10, 1999



# Mechanical Integrity Casing or Annulus Pressure Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Implementation Section, 8WM-DW  
999 18th Street, Suite 500, Denver, CO 80202-2466

EPA Witness: Deb Madison Date 5/5/99 Time 1:19 am/pm  
Test conducted by: Hoff; Murphyl  
Others present: Ray Reed

Well: 80-D

Well ID: MTS2026-00026

Field: EPA

Company: Murphy Oil USA

Well Location: SW, NW, Sec 3 T28N

Address: Murphy

R31E Roosevelt Co. Poplar MT 59255

Time	Test #1	Test #2	Test #3
0 min	<u>482</u> psig	_____ psig	_____ psig
5	<u>482</u>	_____	_____
10	<u>482</u>	_____	_____
15	<u>482</u>	_____	_____
20	<u>482</u>	_____	_____
25	<u>482</u>	_____	_____
30 min	<u>482</u>	_____	_____
35	_____	_____	_____
40	_____	_____	_____
45	_____	_____	_____
50	_____	_____	_____
55	_____	_____	_____
60 min	_____	_____	_____
REVIEWED			
BY: <u>Jac</u>			
DATE: <u>6/10/99</u> psig			
Tubing press	_____ psig	_____ psig	_____ psig

Result (circle) Pass Fail      Pass Fail      Pass Fail


Signature of EPA Witness: Deb Madison Ray Reed

See back of page for any additional comments & compliance followup.

This is the front side of two sides

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

## WELL REWORK RECORD




NAME AND ADDRESS OF PERMITTEE

Murphy EXPRO  
P.O. Box 547  
Poplar, MT 59255-0547

NAME AND ADDRESS OF CONTRACTOR

MT00026

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 840 ACRES

STATE

MT

COUNTY

Roosevelt

PERMIT NUMBER

MT52026-0026

SURFACE LOCATION DESCRIPTION

1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface 1982

N

Location \_\_\_\_\_ ft. from (N/S) \_\_\_\_\_ Line of quarter section

and 761

W

\_\_\_\_\_ ft. from (E/W) \_\_\_\_\_ Line of quarter section

WELL ACTIVITY

- ☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

Lease Name

Total Depth Before Rework

3575'

Total Depth After Rework

3575'

Date Rework Commenced

9-10-98

Date Rework Completed

9-11-98

TYPE OF PERMIT

☒ Individual☐ Area

Number of Wells 1

Well Number

80-D

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

DESCRIBE REWORK OPERATIONS IN DETAIL

USE ADDITIONAL SHEETS IF NECESSARY

Found tubing leak. Ran new packer  
and hydrotested tubing to 7000#

WIRE LINE LOGS, LIST EACH TYPE

Log Types

Logged Intervals

REVIEWED

BY: Ray

CERTIFICATION

DATE: 10/2/98

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Raymond Reede  
District Manager

SIGNATURE

Raymond Reede

DATE SIGNED

Sept. 15, 1998



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

Form 7520-12 (Rev. 10-84) EPA Region VIII

# WELL REWORK RECORD

MAY 29 1998

EPA REGION VIII

NAME AND ADDRESS OF PERMITTEE  
Murphy Exploration & Prod. Co.  
P.O. Box 547  
Poplar, MT 59255-0547

NAME AND ADDRESS OF CONTRACTOR  
Diamond B Trucking, Inc.  
P.O. Box 567  
Plentywood, MT

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

STATE MT COUNTY Roosevelt

PERMIT NUMBER  
MTS2026-0026

## SURFACE LOCATION DESCRIPTION

1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location 1982 ft. from (N/S) N Line of quarter section

and 761 ft. from (E/W) W Line of quarter section

## WELL ACTIVITY

- ☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

Lease Name

East Poplar Unit

Total Depth Before Rework

Total Depth After Rework

Date Rework Commenced

Date Rework Completed

## TYPE OF PERMIT

☒ Individual  
☐ Area  
Number of Wells 1

Well Number

80-D

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

DESCRIBE REWORK OPERATIONS IN DETAIL  
USE ADDITIONAL SHEETS IF NECESSARY

Mechanical Integrity Test Attached

## WIRE LINE LOGS, LIST EACH TYPE

Log Types

Logged Intervals

REVIEWED

BY: *ARC*

DATE: 6/3/98

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Raymond Reede  
District Manager

SIGNATURE

*Raymond Reede*

DATE SIGNED

5-27-98



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460  
**APPLICATION TO TRANSFER PERMIT**

NAME AND ADDRESS OF EXISTING PERMITTEE Murphy Exploration & Production Co. P.O. Box 547 Poplar, MT 59255-0547		NAME AND ADDRESS OF SURFACE OWNER Wilbur Lockman P.O. Box 175 Poplar, MT 59255-0175							
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT - 640 ACRES	STATE MT	COUNTY Roosevelt	PERMIT NUMBER MTS2026-0026						
	SURFACE LOCATION DESCRIPTION 1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E								
	LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface Location 1982 ft. from (N/S) N Line of quarter section and 761 ft. from (E/W) W Line of quarter section								
	<table border="0"> <tr> <td>WELL ACTIVITY</td> <td>WELL STATUS</td> <td>TYPE OF PERMIT</td> </tr> <tr> <td> <input type="checkbox"/> Class I  <input checked="" type="checkbox"/> Class II  <input checked="" type="checkbox"/> Brine Disposal  <input type="checkbox"/> Enhanced Recovery  <input type="checkbox"/> Hydrocarbon Storage  <input type="checkbox"/> Class III  <input type="checkbox"/> Other                 </td> <td> <input checked="" type="checkbox"/> Operating  <input type="checkbox"/> Modification/Conversion  <input type="checkbox"/> Proposed                 </td> <td> <input checked="" type="checkbox"/> Individual  <input type="checkbox"/> Area                      Number of Wells 1                 </td> </tr> </table>			WELL ACTIVITY	WELL STATUS	TYPE OF PERMIT	<input type="checkbox"/> Class I <input checked="" type="checkbox"/> Class II <input checked="" type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage <input type="checkbox"/> Class III <input type="checkbox"/> Other	<input checked="" type="checkbox"/> Operating <input type="checkbox"/> Modification/Conversion <input type="checkbox"/> Proposed	<input checked="" type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells 1
	WELL ACTIVITY	WELL STATUS	TYPE OF PERMIT						
<input type="checkbox"/> Class I <input checked="" type="checkbox"/> Class II <input checked="" type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage <input type="checkbox"/> Class III <input type="checkbox"/> Other	<input checked="" type="checkbox"/> Operating <input type="checkbox"/> Modification/Conversion <input type="checkbox"/> Proposed	<input checked="" type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells 1							
Lease Name East Poplar Unit Well Number 80-D									
NAME(S) AND ADDRESS(ES) OF NEW OWNER(S)		NAME AND ADDRESS OF NEW OPERATOR							

Attach to this application a written agreement between the existing and new permittee containing a specific date for transfer of permit responsibility, coverage, and liability between them.

The new permittee must show evidence of financial responsibility by the submission of surety bond, or other adequate assurance, such as financial statements or other materials acceptable to the director.

Effective change of owner/operator from Murphy Exploration and Production Company to

**CERTIFICATION**

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print) Sidney W. Campbell Manager Onshore Operations	SIGNATURE	DATE SIGNED
--	-----------	-------------



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT MILES CITY DISTRICT OFFICE

P.O. Box 940  
Miles City, Montana 59301

IN REPLY REFER TO:

3160  
NTL-2B

DEC 17 1985

Murphy Oil USA, Inc.  
P. O. Box 547  
Poplar, Montana 59255

RE: NTL-2B Approval for the East Poplar Unit

Gentlemen:

We have received your NTL-2B application dated 12/2/85, for the federal wells within the East Poplar Unit boundaries. BLM regulation requires NTL-2B approval for all wells within a federal unit. We will not require additional NTL-2B application for nonfederal wells within the unit, rather this letter will serve as NTL-2B approval for all existing wells in the East Poplar Unit. Produced water from the unit is approved for disposal into the following wells:

EPU SWD No. 1	EPA ID No. MTS21PE-0022,
✓ EPU SWD No. 80	EPA ID No. MTS21PE-0026,
EPU SWD No. 8	EPA ID No. MTS21PE-0023,
EPU SWD No. 5	EPA ID No. MTS21PE-0021, and
EPU SWD No. 29	EPA ID No. MTS21PE-0024.

The following conditions apply to this NTL-2B approval for the disposal of produced water from the referenced unit:

Receipt of this approval does not constitute EPA approval for subsurface injection.

Upon receipt of EPA approval, a copy of the EPA permit must be submitted to this office.

All unauthorized discharges or spills must be reported to this office in accordance with CFR Title 40, Parts 124, 144, 146, and 147.


For future wells, complete NTL-2B applications will not be required. Instead, a Well Completion Report (Form 3160-4) should be used with a statement referring to NTL-2B approval and an explanation of the water source and disposal facilities (see example attached).

Wells outside the unit boundaries will require separate NTL-2B approval.

Any changes to these approved procedures must be submitted via Sundry Notice (Form 3160-5) prior to the commencement of operations.

If you have any questions, please contact Jamie Connell at (406) 232-4331.

Sincerely yours,

A handwritten signature in black ink, appearing to read "Jamie Connell", with a stylized flourish at the end.

Asst. District Manager  
Division of Mineral Resources



## United States Department of the Interior

GEOLOGICAL SURVEY  
Conservation Division  
P.O. Box 2550  
Billings, Montana 59103

March 29, 1977

Murphy Oil Corporation  
P.O. Box 547  
Poplar, Montana 59255

Re: NTL-2B Approval for Salt Water Disposal Wells in the Northeast Benrud Field, East Benrud Field, Volt Field and East Poplar Field, Roosevelt County, Montana

Gentlemen:

We have reviewed your applications concerning approval of the numerous disposal wells. Your applications meet the regulations required under NTL-2B, and approval is hereby given for the following disposal wells:

Mule Creek Allotted No.1-D, Fort Peck (Allotted) 35-009, SW SE, Sec. 20-31N-48E, 928' FSL and 2078' FEL, Northeast Benrud Field;

Wersit No.1-D, Fort Peck (Allotted) 35-072, SW, Sec.36-31N-47E, 1740' FSL and 1740' FWL, East Benrud Field;

Courchene No.1-D, Fort Peck (Allotted) 35-035, SE SW, Sec.4-30N-46E, 801' FSL and 2034' FWL, Volt Field;

East Poplar Unit No.1-D, (Klies) #6104, SE SE SE, Sec.30-29N-51E, East Poplar Field;

East Poplar Unit No.80-D, 1-37-IND-12914, SW NW, Sec.3-28N-51E, 1982' FNL and 761' FWL, East Poplar Field;

East Poplar Unit No.8-D, Fort Peck (Allotted) ---Patented, C NW SE, Sec.10-28N-51E, 1980' FSL and 1980' FEL, East Poplar Field;

East Poplar Unit No.5-D, 1-37-IND-12850, SE SE, Sec.19-29N-51E, 1205' FSL and 660' FEL, East Poplar Field.

However, approval of the emergency pits that you are requesting cannot be given at this time. Each pit will be inspected individually by a staff member of this office. At the time of this inspection, each pit will be checked to see if it meets the criteria as stated under the section of NTL-2B that deals with emergency pits. We would like to remind you that all emergency pits are to be emptied of all fluids within 48 hours following their use. Each emergency use of the pits is to be reported to this office and approval is needed for the method of disposing of the fluid. Inspection of these pits will take place within 30 days. Also, an emergency pit cannot be used as a trash pit.

Sincerely yours,

Virgil L. Pauli  
District Engineer



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

NOV 02 1988

Ref: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Raymond Reede  
District Manager  
Murphy Oil USA, Inc.  
P.O. Box 547  
Poplar, MT 59255

RE: NOTICE OF NONCOMPLIANCE  
UIC Permit #MTS2026-0026  
Murphy East Poplar No. 80-D  
SWNW Section 3-T28N-R51E  
Roosevelt County, Montana

Dear Mr. Reede:

EPA has revised all UIC permit numbers. Note the captioned well changed from MTS21PE-0026 to your new permit number MTS2026-0026. Please use this revised number in all future correspondence relative to this SWD well.

The last quarterly chemical analysis of injected water submitted to this office was your third quarter report of September 16, 1987. A fourth report was due to this office January 1988. Following submission of that fourth quarter analysis of injected fluids, Murphy can request a minor permit modification to reduce the frequency of analyses to not less than once per year (Page 8, Part II. Section D.1.(c) of the UIC Permit.


A compliance file review on the No. 80-D SWD well indicates that we have no signatory authorization for your signature as a Murphy employee. Please have an officer of Murphy Oil send us a letter authorizing your signature on UIC related documents. Refer to 40 CFR 144.32 for signatory requirements.



Mr. Raymond Reede  
Murphy Oil USA, Inc.  
Page 2

Should you have any questions relative to the above comments, please contact Emmett Schmitz, of my staff, at (303) 293-1717 and send the require data to him at the above letterhead address. The requested data must be sent within forty-five (45) days from receipt of this letter.

Sincerely,



Max H. Dodson  
Director  
Water Management Division

UNDERGROUND INJECTION CONTROL PROGRAM

FINAL PERMIT

Class II Salt Water Disposal Well

Permit # MTS21PE-0026

EPU 80-D, Poplar Field  
Roosevelt County, Montana

issued to:

Murphy Oil USA, Inc.  
200 Peach Street  
El Dorado, Arkansas 71730

Date Prepared: March 28, 1986

# TABLE OF CONTENTS

	Page
TITLE SHEET . . . . .	1
TABLE OF CONTENTS . . . . .	2
<u>PART I. AUTHORIZATION TO CONSTRUCT AND INJECT</u> . . . . .	4
<u>PART II. SPECIFIC PERMIT CONDITIONS</u> . . . . .	5
Section A. CONSTRUCTION REQUIREMENTS	
1. Casing and Cementing . . . . .	5
2. Tubing & Packer Specifications . . . . .	5
3. Monitoring Devices . . . . .	5
4. Proposed Changes and Workovers . . . . .	5
Section B. CORRECTIVE ACTION . . . . .	5
Section C. WELL OPERATION	
1. Transition from Rule to Permit Authorization. . . . .	6
2. Mechanical Integrity . . . . .	6
3. Injection Interval . . . . .	7
4. Injection Pressure Limitation . . . . .	7
5. Injection Volume Limitation . . . . .	8
6. Injection Fluid Limitation . . . . .	8
7. Annular Fluid . . . . .	8
Section D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS	
1. Injection Well Monitoring Program . . . . .	8
2. Monitoring Information . . . . .	9
3. Recordkeeping . . . . .	9
4. Reporting of Results . . . . .	9
Section E. PLUGGING AND ABANDONMENT	
1. Notice of Plugging and Abandonment . . . . .	10
2. Plugging and Abandonment Plan . . . . .	10
3. Cessation of Injection Activities . . . . .	10
4. Plugging and Abandonment Report . . . . .	10
Section F. FINANCIAL RESPONSIBILITY . . . . .	10
<u>PART III. GENERAL PERMIT CONDITIONS</u> . . . . .	12
Section A. EFFECT OF PERMIT . . . . .	12
Section B. PERMIT ACTIONS	
1. Modification, Reissuance, or Termination . . . . .	12
2. Transfers . . . . .	12
Section C. SEVERABILITY . . . . .	12

(Table of Contents - Continued)		Page
Section D.	CONFIDENTIALITY . . . . .	.13
Section E.	GENERAL DUTIES AND REQUIREMENTS	
1.	Duty to Comply . . . . .	.13
2.	Penalties for Violations of Permit Conditions . . . . .	.13
3.	Need to Halt or Reduce Activity not a Defense . . . . .	.13
4.	Duty to Mitigate . . . . .	.13
5.	Proper Operation and Maintenance. . . . .	.13
6.	Duty to Provide Information . . . . .	.14
7.	Inspection and Entry . . . . .	.14
8.	Permit Application Records . . . . .	.14
9.	Signatory Requirements . . . . .	.14
10.	Reporting of Noncompliance . . . . .	.14
Appendix A	(Construction Plan) . . . . .	.16
Appendix B	(Reporting Forms) . . . . .	.19
	EPA Form 7520 -7: Application to Transfer Permit	
	EPA Form 7520-10: Well Completion Form	
	EPA Form 7520-11: Annual Well Monitoring Report	
	EPA Form 7520-12: Well Rework Record	
	EPA Form 7520-13: Plugging Record	
Appendix C	(Plugging & Abandonment Plan) . . . . .	.25

PART I - AUTHORIZATION TO CONSTRUCT AND INJECT

Pursuant to the Underground Injection Control Regulations of the U.S. Environmental Protection Agency codified at Title 40 of the Code of Federal Regulations, Parts 124, 144, 146, and 147,

Murphy Oil USA, Inc.  
200 Peach Street  
El Dorado, Arkansas 71730

is hereby authorized to operate a Class II injection well, commonly known as EPU 80-D, located at 1982 feet from North line and 761 feet from West line of Section 3, Township 28N, Range 51E of Roosevelt County, Montana. Injection shall be for the purpose of brine disposal into the Dakota Sandstone, in accordance with conditions set forth herein.

Injection under permit authorization shall commence upon the effective date of this permit.


All conditions set forth herein refer to Title 40 Parts 144, 146, and 147 of the Code of Federal Regulations and are regulations that are in effect on the date that this permit is effective.

This permit consists of a total of 26 pages and includes all items listed in the Table of Contents. Further, it is based upon representations made by the permittee and on other information contained in the administrative record.

This permit and the authorization to inject are issued for the operating life of the well, unless terminated. The permit will be reviewed by EPA at least every five years to determine whether action under 40 CFR 144.36 (a) is warranted. The permit will expire upon delegation of primary enforcement responsibility for the UIC Program to the State of Montana, unless that State has adequate authority, and chooses, to adopt and enforce this permit as a State permit.

Issued this 31st day of March, 1986.

This permit shall become effective thirty days after date of issuance.

  
Max H. Dodson, Director  
Water Management Division \*

\* NOTE: The person holding this title is referred to as the "Director" throughout this permit.

## PART II. SPECIFIC PERMIT CONDITIONS

### A. WELL CONSTRUCTION

1. Casing and Cementing. The construction details submitted with the application comply with Part 146 of the UIC regulations and are hereby incorporated into this permit as Appendix A, and shall be binding on the permittee.

2. Tubing and Packer Specifications. A tubing of two and seven-eighths (2 & 7/8) inches diameter shall be utilized with a packer placed at not less than 3190 feet. Injection between the outermost casing protecting underground sources of drinking water and the wellbore is prohibited. Injection directly through the casing is also prohibited.

3. Monitoring Devices. The operator shall provide and maintain in good operating condition:

- (a) a tap on the injection line or tubing for the purposes of obtaining representative samples of the injection fluids,
- (b) two one-half (1/2) inch FIP fittings, isolated by plug or globe valves, and located: 1) at the wellhead on the tubing and, 2) on the tubing/casing annulus, and positioned to allow attachment of 1/2 inch MIP gauges;
- (c) cumulative volume shall be calculated by the length of time the injection pump is in operation. Calibration of the injection pump shall be done monthly.

4. Proposed Changes and Workovers. The permittee shall give notice to the Director within ten (10) days of any planned physical alterations or additions to the permitted facility. In addition, the permittee shall provide all records of well workovers, logging, or other test data to EPA within sixty (60) days of completion of the activity. Appendix B contains all required reporting forms.

### B. CORRECTIVE ACTION

The operator is not required to take corrective action on any well in the area of review prior to the effective date of this permit.

### C. WELL OPERATION

1. Transition from Rule to Permit Authorization. This well has been operating by rule since June 25, 1984. Adherence to all requirements under 40 CFR 144, 146 and 147, including construction and mechanical integrity, have been verified for this well. Authorization of injection activities for this well is hereby transferred from rule to permit, as set forth herein, upon the effective date of this permit.

#### 2. Mechanical Integrity (Subsequent to Initial Demonstration).

- (a) Method of Demonstrating Absence of Fluid Migration. An injection profile shall be run on the injection well every five years, in order to verify that injected fluids are remaining in the Dakota Sandstone. Such injection profile shall include a radioactive tracer survey and a temperature differential log and shall be run from a distance of at least 250 feet above the injection zone. A copy of the injection profile, with an interpretation of the results shall be submitted to the Director as soon as possible but no later than sixty (60) days after the test has been completed. Such injection profiles and temperature logs shall also be a part of demonstrating continual mechanical integrity as per part (c) of this section.
- (b) Method of Demonstrating Absence of Casing Leaks. A demonstration of the absence of significant leaks in the casing, tubing and/or packer must be made by performing a tubing/casing annulus pressure test. This test shall be for a minimum of 45 minutes at: 1) a pressure of 300 psig measured at the surface, if the well is shut-in, or 2) a pressure differential of at least 200 psig, if injection activities are continued during the test. The tubing/casing annulus shall be filled with a non-corrosive fluid (either a non-toxic liquid or the injection fluid) at least 24 hours in advance of the test. Pressure values shall be recorded at five-minute intervals or less. A well passes the mechanical integrity test if there is less than a ten (10) percent decrease in pressure over the 45 minute period, or if method 2 above is used, less than ten (10) percent increase or decrease in the annulus pressure during the 45 minute test period.
- (c) Schedule for Demonstrations of Mechanical Integrity. A demonstration of mechanical integrity (pressure test and injectivity profile with temperature log) shall be made at regular intervals, no less frequently than every five (5) years from the effective date of this permit, in accordance with 40 CFR 146.8 and paragraph (a) and (b) above, unless otherwise modified. Initiation of mechanical integrity demonstrations will be according to the following provisions.

- (i) It shall be the permittee's responsibility to arrange and conduct the routine five-year demonstrations. The permittee shall notify the Director of his intent to demonstrate mechanical integrity at least thirty (30) days prior to each such demonstration. Results of the test shall be submitted to the Director as soon as possible but no later than sixty (60) days after the demonstration.
- (ii) In addition to any demonstration made under paragraph (i) above, the Director may require a demonstration of mechanical integrity at any time during the permitted life of the well.
- (d) Loss of Mechanical Integrity. If the well fails to demonstrate mechanical integrity during a test, or a loss of mechanical integrity as defined by 40 CFR 146.8 becomes evident during operation, the permittee shall notify the Director in accordance with Part III, Section E. 10. of this permit. Furthermore, injection activities shall be terminated immediately; and operation shall not be resumed until the permittee has taken necessary actions to restore integrity to the well and EPA gives approval to recommence injection.

3. Injection Interval. Injection shall be limited to the Dakota Sandstone. The perforated interval within the Dakota is identified in Attachment G of the permit application as: 3218-3250, 3284-3410 and 3462-3512 feet from Kelly Bushing (KB).

4. Injection Pressure Limitation.

- (a) Injection pressure, measured at the surface, shall not exceed 650 pounds per square inch gauge (psig).
- (b) The pressure limit in paragraph (a) may be increased by the Director if the fracture pressure of the injection formation will not be exceeded, and the permittee demonstrates that the proposed increase in surface injection pressure is necessary: (1) to overcome friction losses in the injection system, or (2) to inject the volume rate of fluid set by Part II, Section C. 5., below. This demonstration shall be made by performing a step rate injection test, using fluid normally injected, to determine both the instantaneous shut-in pressure and the formation breakdown pressure. The Director will determine any allowable increase based upon the test results and other parameters reflecting actual injection operations.
- (c) The permittee shall give thirty (30) days advance notice to the Director if an increase of injection pressure will be sought. Details of the proposed tests shall be submitted at least seven (7) days prior to the tests. Results of all tests shall be submitted to the Director within ten (10) days of the test. Injection at the increased pressure must be approved by the Director, in writing, before the permittee may begin operation at that pressure.



- (d) Any approval by the Director for increased pressure limitations as stated in paragraph (b) above, shall be made part of this permit by minor modification without further opportunity for public comment.

5. Injection Volume-Rate Limitation. No more than 4,500 barrels per day of produced brine wastes shall be injected into this well provided further that in no case shall injection pressure exceed that limit shown in Part II, Section C. 4. of this permit.

6. Injection Fluid Limitation. The permittee shall not inject any hazardous substances, per 40 CFR 261, at any time during the operation of the facility, and further, no substances other than those noted in the permit application shall be injected.

7. Annular Fluid. The annulus between the tubing and the casing shall be filled with fluid treated with corrosion inhibitors and oxygen scavengers. The specific additives were identified by the applicant as Nalco 3900 fluid with Nalco 4300 scale inhibitor.

D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS

1. Injection Well Monitoring Program. Samples and measurements shall be representative of the monitored activity. The permittee shall utilize the applicable analytical methods described in Table I of 40 CFR 136.3, or in Appendix III of 40 CFR 261, or in certain circumstances, by other methods that have been approved by the EPA Administrator. Monitoring shall consist of:

- (a) analysis of the injection fluids, performed:
  - (i) quarterly for Total Dissolved Solids, pH, Specific Conductivity, and Specific Gravity; and
  - (ii) whenever there is a change in the source of injection fluids. A comprehensive water analysis shall be submitted to the Director within thirty (30) days of any change in injection fluids.
- (b) weekly observations of injection pressure, flow rate and cumulative volume. At least one observation of injection pressure, and volume, shall be recorded at regular intervals no greater than thirty (30) days. Cumulative volumes shall be determined weekly, averaged and recorded monthly and reported annually. These determinations shall be made by calibration of the amount of injection fluid that is pumped during a specific period of time, and multiplied by the amount of time the pump is in operation. Calibration of the pumping rate of the pump shall be made monthly.
- (c) The permittee may request that the frequency of analysis in paragraph (a)(i) above, be reduced after the first year if the reduced frequency will yield data representative of the nature of the injected fluids. The reduced frequency shall not be less than once per year.

2. Monitoring Information. Records of any monitoring activity required under this permit shall include:

- (a) the date, exact place, the time of sampling or field measurements;
- (b) the name of the individual(s) who performed the sampling or measurements;
- (c) the exact sampling method(s) used to take samples;
- (d) the date(s) laboratory analyses were performed;
- (e) the name of the individual(s) who performed the analyses;
- (f) the analytical techniques or methods used by laboratory personnel; and
- (g) the results of such analyses.

3. Recordkeeping.

- (a) The permittee shall retain records concerning:
  - (i) the nature and composition of all injected fluids until three (3) years after the completion of plugging and abandonment which has been carried out in accordance with the Plugging and Abandonment Plan shown in Appendix C, and is consistent with 40 CFR 146.10.
  - (ii) all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation and copies of all reports required by this permit for a period of at least five (5) years from the date of the sample, measurement or report during the operating life of the well.
- (b) The permittee shall continue to retain such records after the retention period specified in paragraphs (a)(i) and (a)(ii) unless he delivers the records to the Director or obtains written approval from the Director to discard the records.

4. Reporting of Results. The permittee shall submit an Annual Report to the Director summarizing the results of the monitoring required by Part II, Section D. 1. of this permit. Copies of all monthly records on injected fluids, and any major changes in characteristics or sources of injected fluid shall be included in the Annual Report. The first Annual Report shall cover the period from the effective date of the permit through December 31. Subsequently, the Annual Report shall cover the period of January 1 through December 31, and shall be submitted by January 15 of the following year. Appendix B contains Form 7520-11 which may be copied and used to submit the annual summary of monitoring.

#### E. PLUGGING AND ABANDONMENT

1. Notice of Plugging and Abandonment. The permittee shall notify the Director forty five (45) days before conversion, workover, or abandonment of the well.

2. Plugging and Abandonment Plan. The permittee shall plug and abandon the well as provided in the Plugging and Abandonment Plan, Appendix C of this permit. EPA reserves the right to change the manner in which the well will be plugged if the well is modified during its permitted life or if the well is not made consistent with EPA requirements for construction and mechanical integrity. The Director may ask the permittee to update the estimated plugging cost periodically. Such estimates shall be based upon costs which a third party would incur to plug the well according to the plan.

3. Cessation of Injection Activity. After a cessation of injection into this well for two (2) years, the permittee shall plug and abandon the well in accordance with the Plugging and Abandonment Plan unless the permittee:

- (a) provides notice to the Director, and
- (b) demonstrates that the well will be used in the future, and
- (c) describes actions or procedures, satisfactory to the Director, that will be taken to ensure that the well will not endanger underground sources of drinking water during the period of temporary abandonment.

4. Plugging and Abandonment Report. Within sixty (60) days after plugging the well, the permittee shall submit a report on Form 7520-13 to the Director. The report shall be certified as accurate by the person who performed the plugging operation and the report shall consist of either: (1) a statement that the well was plugged in accordance with the plan, or (2) where actual plugging differed from the plan, a statement that specifies the different procedures followed.

#### F. FINANCIAL RESPONSIBILITY

1. Demonstration of Financial Responsibility. The permittee is required to maintain financial responsibility and resources to close, plug, and abandon the injection well as provided in the plugging and abandonment plan.

- (a) The surety performance bond in the amount of \$25,000 underwritten by United States Fidelity and Guaranty Company of Maryland which names EPA as beneficiary in the event of permittee default in the plugging and abandonment requirements, is hereby incorporated as part of this permit. The standby trust agreement established by the permittee shall remain in effect for the duration of this permit.

- (b) The permittee may, upon request to the EPA, change the type of financial mechanism or instrument utilized. A change in demonstration of financial responsibility must be approved by the Director. A minor permit modification will be made to reflect any change in financial mechanisms, without further opportunity for public comment.

2. Insolvency of Financial Institution. The permittee must submit an alternative demonstration of financial responsibility acceptable to the Director, within sixty (60) days after either of the following events occur.

- (a) the institution issuing the trust or surety bond files for bankruptcy; or
- (b) the authority of the trustee institution to act as trustee, or the authority of the institution issuing the surety bond, is suspended or revoked.

### PART III. GENERAL PERMIT CONDITIONS

#### A. EFFECT OF PERMIT

The permittee is allowed to engage in underground injection in accordance with the conditions of this permit. The permittee, as authorized by this permit, shall not construct, operate, maintain, convert, plug, abandon, or conduct any other injection activity in a manner that allows the movement of fluid containing any contaminant into underground sources of drinking water, if the presence of that contaminant may cause a violation of any primary drinking water regulation under 40 CFR Part 142 or otherwise adversely affect the health of persons. Any underground injection activity not authorized in this permit or otherwise authorized by permit or rule is prohibited. Issuance of this permit does not convey property rights of any sort or any exclusive privilege; nor does it authorize any injury to persons or property, any invasion of other private rights, or any infringement of State or local law or regulations. Compliance with the terms of this permit does not constitute a defense to any enforcement action brought under the provisions of Section 1431 of the Safe Drinking Water Act (SDWA) or any other law governing protection of public health or the environment for any imminent and substantial endangerment to human health, or the environment, nor does it serve as a shield to the permittee's independent obligation to comply with all UIC regulations.

#### B. PERMIT ACTIONS

1. Modification, Reissuance, or Termination. The Director may, for cause or upon a request from the permittee, modify, revoke, and reissue, or terminate this permit in accordance with 40 CFR Sections 124.5, 144.12, 144.39, and 144.40. Also, the permit is subject to minor modifications for cause as specified in 40 CFR Section 144.41. The filing of a request for a permit modification, revocation and reissuance, or termination or the notification of planned changes or anticipated noncompliance on the part of the permittee does not stay the applicability or enforceability of any permit condition.

2. Transfers. This permit is not transferrable to any person except after notice is provided to the Director and the requirements of 40 CFR 144.38 are complied with. The Director may require modification or revocation and reissuance of the permit to change the name of the permittee and incorporate such other requirements as may be necessary under the SDWA.

#### C. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

#### D. CONFIDENTIALITY

In accordance with 40 CFR Part 2 and 40 CFR 144.5, any information submitted to EPA pursuant to this permit may be claimed as confidential by the applicant. Any such claim must be asserted at the time of submission by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, EPA may make the information available to the public without further notice. If a claim is asserted, the validity of the claim will be assessed in accordance with the procedures in 40 CFR Part 2 (Public information). Claims of confidentiality for the following information will be denied:

- The name and address of the permittee, and
- Information which deals with the existence, absence or level of contaminants in drinking water.

#### E. GENERAL DUTIES AND REQUIREMENTS

1. Duty to Comply. The permittee shall comply with all conditions of this permit, except to the extent and for the duration such noncompliance is authorized by an emergency permit. Any permit noncompliance constitutes a violation of SDWA and is grounds for enforcement action, permit termination, revocation and reissuance, or modification. Such noncompliance may also be grounds for enforcement action under the Resource Conservation and Recovery Act (RCRA).

2. Penalties for Violations of Permit Conditions. Any person who violates a permit requirement is subject to civil penalties, fines, and other enforcement action under the SDWA and may be subject to such actions pursuant to the RCRA. Any person who willfully violates permit conditions may be subject to criminal prosecution.

3. Need to Halt or Reduce Activity not a Defense. It shall not be a defense for a permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this permit.

4. Duty to Mitigate. The permittee shall take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance with this permit.

5. Proper Operation and Maintenance. The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems only when necessary to achieve compliance with the conditions of this permit.

6. Duty to Provide Information. The permittee shall furnish the Director, within a time specified, any information which the Director may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The permittee shall also furnish to the Director, upon request, copies of records required to be kept by this permit.

7. Inspection and Entry. The permittee shall allow the Director, or an authorized representative, upon the presentation of credentials and other documents as may be required by law to:

- (a) Enter upon the permittee's premises where a regulated facility or activity is located or conducted, or where records are kept under the conditions of this permit;
- (b) Have access to and copy, at reasonable times, any records that must be kept under the conditions of this permit;
- (c) Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this permit; and
- (d) Sample or monitor, at reasonable times, for the purposes of assuring permit compliance or as otherwise authorized by SDWA any substances or parameters at any location.

8. Records of Permit Application. The permittee shall maintain records of all data required to complete the permit application and any supplemental information submitted for a period of five (5) years from the effective date of this permit. This period may be extended by request of the Director at any time.

9. Signatory Requirements. All reports or other information requested by the Director shall be signed and certified according to 40 CFR 144.32.

10. Reporting of Noncompliance.

- (a) Anticipated Noncompliance. The permittee shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (b) Compliance Schedules. Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this permit shall be submitted no later than thirty (30) days following each schedule date.

(c) Twenty four Hour Reporting.

- (i) The permittee shall report to the Director any noncompliance which may endanger health or the environment. Any information shall be provided orally within twenty four (24) hours from the time the permittee becomes aware of the circumstances by telephoning EPA at 1-800-424-6802. The following shall be included as information which must be reported orally within twenty four (24) hours:
  - (A) Any monitoring or other information which indicates that any contaminant may cause endangerment to an underground source of drinking water.
  - (B) Any noncompliance with a permit condition or malfunction of the injection system which may cause fluid migration into or between underground sources of drinking water.
- (ii) A written submission shall also be provided within five (5) days of the time the permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time it is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance.
- (d) Other Noncompliance. The permittee shall report all other instances of noncompliance not otherwise reported at the time monitoring reports are submitted. The reports shall contain the information listed in Part III, Section E. 10.(C)(ii) of this permit.
- (e) Other Information. Where the permittee becomes aware that he failed to submit any relevant facts in the permit application, or submitted incorrect information in a permit application or in any report to the Director, the permittee shall submit such correct facts or information within two (2) weeks of the time such information became known to him.



APPENDIX A  
(Construction Details)

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460COMPLETION REPORT FOR BRINE DISPOS.  
HYDROCARBON STORAGE, OR ENHANCED RECOVERY WELLForm Approved  
OMB No. 2040-0042  
Approval expires 9-30-86

NAME AND ADDRESS OF EXISTING PERMITTEE Murphy Oil USA, Inc. 200 Peach Street El Dorado, AR 71230		NAME AND ADDRESS OF SURFACE OWNER Willbar P. Lockman Box 175 Poplar, Montana 59255				
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT — 640 ACRES		STATE MT	COUNTY Roosevelt	PERMIT NUMBER		
		SURFACE LOCATION DESCRIPTION N <sup>1</sup> 1/2 OF SW <sup>1</sup> 1/4 OF NE <sup>1</sup> 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E				
		LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface Location 1982 ft. from (N/S) N Line of quarter section and 261 ft. from (E/W) E Line of quarter section				
		WELL ACTIVITY <input checked="" type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage				
		TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____				
		Estimated Fracture Pressure of Injection Zone 2490 psig				
Anticipated Daily Injection Volume (Bbls)		Injection Interval				
Average 1700		Maximum 4500		Feet 3218 to Feet 3512		
Anticipated Daily Injection Pressure (PSI)		Depth to Bottom of Lowermost Freshwater Formation (Feet)				
Average 400		Maximum 650		Warren Corne Water Well 150'		
Type of Injection Fluid (Check the appropriate block(s)) <input checked="" type="checkbox"/> Salt Water <input type="checkbox"/> Brackish Water <input type="checkbox"/> Fresh Water <input type="checkbox"/> Liquid Hydrocarbon <input type="checkbox"/> Other		Lease Name CPU RD-D		Well Number 60-D		
Name of Injection Zone Dakota Sand						
Date Drilling Began 7/2/56		Date Well Completed 7/29/56		Permeability of Injection Zone Data Not Available		
Date Drilling Completed 7/26/56		Porosity of Injection Zone Data Not Available				
CASING AND TUBING			CEMENT		HOLE	
OD Size	Wt/Ft — Grade — New or Used	Depth	Section	Class	Depth	Bit Diameter
13 3/8	48# H-40 New	150.14'	175	G-? 1-1 pos m x	195	17 1/2
9 5/8	35# J-55 New	970.93'	400	G-?	990	12 1/4
5 1/2	15.5# J-55 New	5822.5'	300	G-? 1-1 pos m x	5932	8 3/4
2 7/8	6.5# J-55 New	3169.93'	610	G-?		
INJECTION ZONE STIMULATION			WIRE LINE LOGS, LIST EACH TYPE			
Interval Treated	Materials and Amounts Used	Log Types		Logged Intervals		
3218-3512	1304 Bbls. Water	Elect Survey 2"		979-5832		
		Elect Survey 5"		2000-5832		
		Microlog 5"		2000-5831		
		Gamma Ray Neutron		2650-5775		


Complete Attachments A — E listed on the reverse.

## CERTIFICATION


I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print) Alvin W. Simpson Manager of Operations		DATE SIGNED March 14, 1985
UIC Permit MTS21PE-0026		

PU 80-D Subsurface Well Design



APPENDIX B  
(Reporting Forms)

<div style="display: flex; justify-content: space-between;"><div style="text-align: left;"><div>UNITED STATES ENVIRONMENTAL PROTECTION AGENCY WASHINGTON, DC 20460</div></div><div style="text-align: right;">AGENCY</div></div> <div style="text-align: center; margin-top: 5px;"><b>APPLICATION TO TRANSFER PERMIT</b></div>																																																																																																				
<div style="display: flex;"><div style="flex: 1; border-right: 1px solid black; padding-right: 5px;">NAME AND ADDRESS OF EXISTING PERMITEE</div><div style="flex: 1; padding-left: 5px;">NAME AND ADDRESS OF SURFACE OWNER</div></div>																																																																																																				
<div>LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT — 360 ACRES</div> <div style="border: 1px solid black; padding: 5px; margin-top: 5px;"><div style="display: flex; justify-content: space-between; border-bottom: 1px solid black; margin-bottom: 5px;"><span>N</span><span>W</span><span>E</span><span>S</span></div><table border="1" style="width: 100%; border-collapse: collapse; text-align: center;"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td><td>8</td><td>9</td><td>10</td></tr><tr><td>11</td><td>12</td><td>13</td><td>14</td><td>15</td><td>16</td><td>17</td><td>18</td><td>19</td><td>20</td></tr><tr><td>21</td><td>22</td><td>23</td><td>24</td><td>25</td><td>26</td><td>27</td><td>28</td><td>29</td><td>30</td></tr><tr><td>31</td><td>32</td><td>33</td><td>34</td><td>35</td><td>36</td><td>37</td><td>38</td><td>39</td><td>40</td></tr><tr><td>41</td><td>42</td><td>43</td><td>44</td><td>45</td><td>46</td><td>47</td><td>48</td><td>49</td><td>50</td></tr><tr><td>51</td><td>52</td><td>53</td><td>54</td><td>55</td><td>56</td><td>57</td><td>58</td><td>59</td><td>60</td></tr><tr><td>61</td><td>62</td><td>63</td><td>64</td><td>65</td><td>66</td><td>67</td><td>68</td><td>69</td><td>70</td></tr><tr><td>71</td><td>72</td><td>73</td><td>74</td><td>75</td><td>76</td><td>77</td><td>78</td><td>79</td><td>80</td></tr><tr><td>81</td><td>82</td><td>83</td><td>84</td><td>85</td><td>86</td><td>87</td><td>88</td><td>89</td><td>90</td></tr><tr><td>91</td><td>92</td><td>93</td><td>94</td><td>95</td><td>96</td><td>97</td><td>98</td><td>99</td><td>100</td></tr></table></div>	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10																																																																																											
11	12	13	14	15	16	17	18	19	20																																																																																											
21	22	23	24	25	26	27	28	29	30																																																																																											
31	32	33	34	35	36	37	38	39	40																																																																																											
41	42	43	44	45	46	47	48	49	50																																																																																											
51	52	53	54	55	56	57	58	59	60																																																																																											
61	62	63	64	65	66	67	68	69	70																																																																																											
71	72	73	74	75	76	77	78	79	80																																																																																											
81	82	83	84	85	86	87	88	89	90																																																																																											
91	92	93	94	95	96	97	98	99	100																																																																																											

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460COMPLETION REPORT FOR BRINE DISPOSAL,  
HYDROCARBON STORAGE, OR ENHANCED RECOVERY WELLForm Approved  
OMB No. 2040-0042  
Approval expires 9-30-86

NAME AND ADDRESS OF EXISTING PERMITTEE

NAME AND ADDRESS OF SURFACE OWNER

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

N							
S							

STATE

COUNTY

PERMIT NUMBER

## SURFACE LOCATION DESCRIPTION

1/4 OF	1/4 OF	1/4 SECTION	TOWNSHIP	RANGE
--------	--------	-------------	----------	-------

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location \_\_\_\_\_ ft. from (N/S) \_\_\_\_\_ Line of quarter section

and \_\_\_\_\_ ft. from (E/W) \_\_\_\_\_ Line of quarter section

## WELL ACTIVITY

## TYPE OF PERMIT

- ☐ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

- ☐ Individual  
☐ Area  
Number of Wells \_\_\_\_\_

Estimated Fracture Pressure  
of Injection Zone

Anticipated Daily Injection Volume (Bbls)

Injection Interval

Average

Maximum

Feet

to Feet

Anticipated Daily Injection Pressure (PSI)

Depth to Bottom of Lowermost Freshwater Formation  
(Feet)

Average

Maximum

Type of Injection Fluid (Check the appropriate block(s))

- ☐ Salt Water ☐ Brackish Water ☐ Fresh Water  
☐ Liquid Hydrocarbon ☐ Other

Lease Name

Well Number

Name of Injection Zone

Date Drilling Began

Date Well Completed

Permeability of Injection Zone

Date Drilling Completed

Porosity of Injection Zone

## CASING AND TUBING

## CEMENT

## HOLE

CD Size

Wt/Ft — Grade — New or Used

Depth

Sacks

Class

Depth

Bit Diameter

## INJECTION ZONE STIMULATION

## WIRE LINE LOGS LIST EACH TYPE

Interval Treated

Materials and Amount Used

Log Types

Logged Intervals

Complete Attachments A — E listed on the reverse.

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

DATE SIGNED



ANNUAL DISPOSAL/INJECTION WELL MONITORING REPORT

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

Revised OMB No. 2001-0047 Approval expires 9-30-01

NAME AND ADDRESS OF EXISTING PERMITTEE

NAME AND ADDRESS OF SURFACE OWNER

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

N									
S									

STATE

COUNTY

PERMIT NUMBER

SURFACE LOCATION DESCRIPTION

1/4 OF

1/4 OF

1/4 SECTION

TOWNSHIP

RANGE

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface

Location \_\_\_\_\_ ft. from (N/S) \_\_\_\_\_ Line of quarter section

and \_\_\_\_\_ ft. from (E/W) \_\_\_\_\_ Line of quarter section

WELL ACTIVITY

TYPE OF PERMIT

☐ Effluent Disposal

☐ Individual

☐ Enhancer Recovery

☐ Area

☐ Hydrocarbon Storage

Number of Wells \_\_\_\_\_

Lease Name

Well Number

INJECTION PRESSURE

TOTAL VOLUME INJECTED

TUBING — CASING ANNULUS PRESSURE  
(OPTIONAL MONITORING)

MONTH

YEAR

AVERAGE PSIG

MAXIMUM PSIG

BSL

MCF

MINIMUM PSIG

MAXIMUM PSIG

CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Rel. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

SIGNATURE

DATE SIGNED

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY WASHINGTON, DC 20460																																																								
WELL REWORK RECORD																																																								
NAME AND ADDRESS OF PERMITTEE	NAME AND ADDRESS OF CONTRACTOR																																																							
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT — 640 ACRES  <div style="text-align: center;">                     N                       S                 </div> <div style="display: flex; justify-content: space-between; width: 100px; margin: 0 auto;"> <span>W</span> <span>E</span> </div>	STATE _____ COUNTY _____ PERMIT NUMBER _____  SURFACE LOCATION DESCRIPTION 1/4 OF _____ 1/4 OF _____ 1/4 SECTION _____ TOWNSHIP _____ RANGE _____ LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface Location _____ ft. from (N/S) _____ Line of quarter section and _____ ft. from (E/W) _____ Line of quarter section <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">                             WELL ACTIVITY  <input type="checkbox"/> Brine Disposal  <input type="checkbox"/> Enhanced Recovery  <input type="checkbox"/> Hydrocarbon Storage                               Lease Name _____                         </td> <td style="width: 50%;"> <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Total Depth Before Rework _____</td> <td rowspan="2">TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____</td> </tr> <tr> <td>Total Depth After Rework _____</td> </tr> <tr> <td>Date Rework Commenced _____</td> <td rowspan="2">Well Number _____</td> </tr> <tr> <td>Date Rework Completed _____</td> </tr> </table> </td> </tr> </table>	WELL ACTIVITY <input type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage  Lease Name _____	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Total Depth Before Rework _____</td> <td rowspan="2">TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____</td> </tr> <tr> <td>Total Depth After Rework _____</td> </tr> <tr> <td>Date Rework Commenced _____</td> <td rowspan="2">Well Number _____</td> </tr> <tr> <td>Date Rework Completed _____</td> </tr> </table>	Total Depth Before Rework _____	TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____	Total Depth After Rework _____	Date Rework Commenced _____	Well Number _____	Date Rework Completed _____																																															
	WELL ACTIVITY <input type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage  Lease Name _____	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td>Total Depth Before Rework _____</td> <td rowspan="2">TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____</td> </tr> <tr> <td>Total Depth After Rework _____</td> </tr> <tr> <td>Date Rework Commenced _____</td> <td rowspan="2">Well Number _____</td> </tr> <tr> <td>Date Rework Completed _____</td> </tr> </table>	Total Depth Before Rework _____	TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____		Total Depth After Rework _____	Date Rework Commenced _____		Well Number _____	Date Rework Completed _____																																														
	Total Depth Before Rework _____	TYPE OF PERMIT <input type="checkbox"/> Individual <input type="checkbox"/> Area Number of Wells _____																																																						
	Total Depth After Rework _____																																																							
	Date Rework Commenced _____	Well Number _____																																																						
Date Rework Completed _____																																																								
WELL CASING RECORD — BEFORE REWORK																																																								
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Casing</th> <th colspan="2">Cement</th> <th colspan="2">Perforations</th> <th rowspan="2">Acid or Fracture Treatment Record</th> </tr> <tr> <th>Size</th> <th>Depth</th> <th>Sacks</th> <th>Type</th> <th>From</th> <th>To</th> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table>		Casing		Cement		Perforations		Acid or Fracture Treatment Record	Size	Depth	Sacks	Type	From	To																																										
Casing		Cement		Perforations		Acid or Fracture Treatment Record																																																		
Size	Depth	Sacks	Type	From	To																																																			
WELL CASING RECORD — AFTER REWORK <i>Indicate Additions and Changes Only</i>																																																								
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th colspan="2">Casing</th> <th colspan="2">Cement</th> <th colspan="2">Perforations</th> <th rowspan="2">Acid or Fracture Treatment Record</th> </tr> <tr> <th>Size</th> <th>Depth</th> <th>Sacks</th> <th>Type</th> <th>From</th> <th>To</th> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table>		Casing		Cement		Perforations		Acid or Fracture Treatment Record	Size	Depth	Sacks	Type	From	To																																										
Casing		Cement		Perforations		Acid or Fracture Treatment Record																																																		
Size	Depth	Sacks	Type	From	To																																																			
DESCRIBE REWORK OPERATIONS IN DETAIL USE ADDITIONAL SHEETS IF NECESSARY	WIRE LINE LOGS, LIST EACH TYPE <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th>Log Types</th> <th>Logged Intervals</th> </tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	Log Types	Logged Intervals																																																					
Log Types	Logged Intervals																																																							
<b>CERTIFICATION</b> <i>I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).</i>																																																								
NAME AND OFFICIAL TITLE (Please type or print)	SIGNATURE _____  DATE SIGNED _____																																																							



APPENDIX C  
(Plugging & Abandonment Plan)


UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

## PLUGGING AND ABANDONMENT PLAN

NAME AND ADDRESS OF FACILITY

EPU No. 80-D  
Poplar, Montana

NAME AND ADDRESS OF OWNER/OPERATOR

Murphy Oil USA, Inc.  
200 Peach St.  
Clayton, Ark 71730LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT - 640 ACRES

STATE

COUNTY

PERMIT NUMBER

MT

Rosevelt

SURFACE LOCATION DESCRIPTION

N 1/4 OF S 1/4 OF N 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface  
Location 195.2 ft. from (N/S) N Line of quarter section  
and 76.1 ft. from (E/W) W Line of quarter section

TYPE OF AUTHORIZATION

WELL ACTIVITY

- ☒
- Individual Permit
- 
- ☐
- Area Permit
- 
- ☐
- Rule

- ☐
- CLASS I
- 
- ☒
- CLASS II
- 
- ☐
- Better Disposal
- 
- ☐
- Enhanced Recovery
- 
- ☐
- Hydrocarbon Storage
- 
- ☐
- CLASS III

Number of Wells 1

Lease Name EPU

Well Number 80-D

## CASING AND TUBING RECORD AFTER PLUGGING

SIZE	WT/LF (FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE
17 3/8	48.8		164.14	17 1/4
9 5/8	36.8		966.93	12 1/4
5 1/2	15.56		5810.5	6 3/4

## METHOD OF EMPLACEMENT OF CEMENT PLUGS

- ☒
- The Balance Method
- 
- ☐
- The Dump Bailer Method
- 
- ☐
- The Two-Plug Method
- 
- ☐
- Other

## CEMENTING TO PLUG AND ABANDON DATA

	PLUG #1	PLUG #2	PLUG #3	PLUG #4	PLUG #5	PLUG #6	PLUG #7
Size of Hole or Pipe in which Plug Will Be Placed (inches)	5 1/2	5 1/2	9 5/8				
Depth to Bottom of Tubing or Drill Pipe (ft.)	3166'	700'	100'				
Sacks of Cement To Be Used (each plug)	10	10	20				
Slurry Volume To Be Pumped (cu. ft.)	11.5'	11.5'	23'				
Calculated Top of Plug (ft.)	3092'	614'	15'				
Measured Top of Plug (ft. tagged ft.)							
Slurry Wt. (Lb./Gall.)							
Type Cement or Other Material (Class III)	C	C	C				

## LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (If any)

From	To	From	To
3218'	3250'		
3284'	3310'		
3462'	3512'		

Estimated Cost to Plug Wells

\$25,000.00

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print)

Alvin W. Simpson, Manager of Operations

SIGNATURE

DATE SIGNED

March 14, 1985

## ADDENDUM TO THE STATEMENT OF BASIS

The following sections of the statement of Basis have been modified to accommodate public comments:

### Part II Section A. 3.

#### Monitoring Devices

#### Condition 3

EPA is also requiring the permittee to install a sampling tap for the purpose of collecting injection fluid samples on the injection line. For measuring cumulative volumes of injected fluid, EPA is allowing the submission of calculations for determination of cumulative volume measurements. These calculations are based upon the amount of time the injection pump is operating and the volume of fluid which can be pumped during that period of time. EPA is requiring the permittee to calibrate the pumping rates every month so each month will start with a newly determined pumping rate. Values for cumulative volume shall be taken weekly, averaged and recorded monthly and reported annually to the Denver EPA Office.

### Part II. Section C. 7.

#### Annular Fluid

#### Condition 7

The applicant stated that the tubing/casing annulus is to be filled with fluid treated with corrosion inhibitors and oxygen scavengers.

### Part II. Section D. 1. (b).

#### Injection Well Monitoring Program

#### (Condition 1)

Injection pressure, flow rate and cumulative volume measurements are required to be made weekly with a monthly averaging and recording and reported annually. These measurements may be taken at the wellhead or at the pumping station, provided that the measurements taken are comparable. Calculations of flow rate and cumulative volumes are made by comparing time with volume of fluid pumped by the pump. So cumulative volume is calculated by time the pump was operating multiplied by the flow rate of the pump. The pumping rate shall be calibrated monthly.

U.S. ENVIRONMENTAL PROTECTION AGENCY

Address(EPA Regional Office)  
US EPA, Region VIII  
999 18th Street, Suite 500  
Denver, Colorado 80202-2405

Notice of Inspection

Date

9-25-87

Hour

9:15 AM

Firm Name

Murphy Oil

Firm Address

80-D

Inspector Name & Title

Marc Herman

Inspector Signature

Marc Herman

Notice of Inspection is hereby given according to Section 1445(b)  
if Safe Drinking Water Act (42 U.S.C. §300 f et seq.).

Reason for Inspection

Routine inspection of SWD well.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

ONE DENVER PLACE — 999 18TH STREET — SUITE 1300

DENVER, COLORADO 80202-2413

REC. PROD. JAN 17 1986

JAN 10 1986

REF: 8WM-DW

CERTIFIED MAIL  
RETURN RECEIPT REQUESTED

Mr. Al Simpson  
Murphy Oil Corp.  
200 Peach Street  
El Dorado, Arkansas 71730

RE: UIC Draft Permit  
EPA # MTS21PE-0026  
Well # EPU 80-D

Dear Mr. Simpson

Enclosed is the Draft Underground Injection Control Permit for the EPU 80-D well defined in your application referenced above. This well is located in the East Poplar Field, Roosevelt County, Montana.

The public comment period will run 30 days from date of publication in Billings Gazette and the Wolf Point Herald. This is also Murphy Oil's opportunity to review and comment on the draft permit action; failure to do so, may result in unsatisfactory operating conditions for this facility.

You may call Edna Walton at (303) 293-1421 for information concerning the publication date. If you wish to make any comments, please make them in writing to the attention of Angus Campbell of this office, or phone (303) 293-1420.

Sincerely,

A handwritten signature in cursive script, reading "Max H. Dodson".

Max H. Dodson, Director  
Water Management Division

Enclosures



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII  
ONE DENVER PLACE — 999 18TH STREET — SUITE 1300  
DENVER, COLORADO 80202-2413

PUBLIC NOTICE

INTENT TO ISSUE AN UNDERGROUND INJECTION CONTROL  
CLASS II PERMIT  
TO  
MURPHY OIL CORPORATION

PURPOSE OF PUBLIC NOTICE

The purpose of this notice is to solicit public comment on the proposal by the Region VIII Office of the U. S. Environmental Protection Agency (EPA) to issue a permit to inject fluids underground via a Class II injection well; identified by well number EPU 80-D.

BACKGROUND

EPA Region VIII is currently reviewing an application for an Underground Injection Control Permit from Murphy Oil Corporation, 200 Peach Street, El Dorado, Arkansas 71730, regarding current water disposal practices. The injection fluid now being disposed of is a combination of brine produced in conjunction with the extraction of oil from the Mississippian age Madison Limestone and Heath Formation. Murphy Oil has been using the well known as EPU 80-D located in the SW/4, NW/4, Section 3, Township 28N, Range 51E of the East Poplar Field in Roosevelt County, Montana, since 1963, for the purpose of disposing fluids into the Dakota Sandstone. This well is currently constructed and operated within EPA guidelines for injection wells.

The Dakota Sandstone was exempted for a 1/4 mile radius from the wellbore and vertically between 3218 - 3512 feet from the Kelly Bushing since June 1984, when this well became authorized to inject by rule. However, due to the volumes of fluid being injected, the aquifer exemption is being expanded to 1/2 mile.

EPA has made a preliminary determination to approve the permit application and that by doing so, all underground sources of drinking water will be protected. Therefore, EPA is hereby serving notice of intent to issue a permit for the current underground injection activities. This action is being taken as provided by Part C of the Safe Drinking Water Act and attendant regulations.

PUBLIC COMMENTS

All data, except confidential business information, submitted by the applicant, as well as the draft permit prepared by EPA, are contained in the administrative record for Murphy Oil, well number, East Poplar Unit (EPU) 80-D. This information is available for public inspection at these locations from 9:00 a.m. to 5:00 p.m., or by contacting one of the following offices:

Environmental Protection Agency  
Region VIII (8WM-DW)  
Ground Water Section  
One Denver Place, Suite 1300  
999 18th Street  
Denver, Colorado 80202-2413  
Telephone (303) 293-1420  
ATTN: Angus Campbell

Environmental Protection Agency  
Montana Office  
Federal Office Building  
Drawer 10096  
301 South Park  
Helena, Montana 59626  
Telephone (406) 449-5414

Public comments are encouraged and will be accepted, in writing, at the Denver Office for a period of thirty (30) days after publication of this notice. A request for a public hearing should be made in writing and should state the nature of the issues proposed to be raised at the hearing. A PUBLIC HEARING WILL BE HELD ONLY IF SIGNIFICANT INTEREST IS SHOWN.

JAN 21 1986

Date of Publication



Max H. Dodson, Director  
Water Management Division



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII  
ONE DENVER PLACE — 999 18TH STREET — SUITE 1300  
DENVER, COLORADO 80202-2413

DRAFT

UNDERGROUND INJECTION CONTROL AQUIFER EXEMPTION

Related to UIC Permit Number: MTS21PE-0026

In compliance with provisions of the Safe Drinking Water Act, as amended, (42 U.S.C. 300f-300j-9, commonly known as SWDA) and attendant regulations incorporated by the U. S. Environmental Protection Agency under Title 40 of the Code of Federal Regulations,

The Dakota Sandstone located:

- 1.) vertically from 3,218 to 3,512 feet below ground level, and
- 2.) Laterally within one-half mile radius from the injection well (commonly called EPU 80-D) located NE/4, SW/4 Section 3, Township 28 North, Range 51 East of Roosevelt County, Montana.

is exempted as an Underground Source of Drinking Water.

This aquifer exemption is expanded in conjunction with the Underground Injection Control Permit issued to Murphy Oil USA, Inc. of El Dorado, Arkansas, for the injection of water for disposal purposes.

This aquifer exemption has no expiration date.


Signed this \_\_\_\_\_ day of \_\_\_\_\_, 1986.

**DRAFT**

\_\_\_\_\_  
Max H. Dodson, Director  
Water Management Division



Form-4	EPA	UNITED STATES ENVIRONMENTAL PROTECTION AGENCY UNDERGROUND INJECTION CONTROL PERMIT APPLICATION (Collected under the authority of the Safe Drinking Water Act, Sections 1421, 1422, 40 CFR 144)	Form approved, OMB No. 2040-0042, Expires 9-30-84	I. EPA ID NUMBER	T/A
READ ATTACHED INSTRUCTIONS BEFORE STARTING FOR OFFICIAL USE ONLY					
Application approved mo day year		Date Received mo day year		Permit/Well Number	
				EPU 80-D	
II. FACILITY NAME AND ADDRESS			III. OWNER/OPERATOR AND ADDRESS		
Facility Name East Poplar Unit			Owner/Operator Name Murphy Oil USA, Inc.		
Street Address P. O. Box 547			Street Address 200 Peach Street		
City Poplar		State MT	ZIP Code 59255	City El Dorado	State AR
				ZIP Code 71730	
IV. OWNERSHIP STATUS (Mark 'x')			V. SIC CODES		
<input type="checkbox"/> A. Federal <input type="checkbox"/> B. State <input checked="" type="checkbox"/> C. Private			1311		
<input type="checkbox"/> D. Public <input type="checkbox"/> E. Other (Explain)					
VI. WELL STATUS (Mark 'x')					
<input checked="" type="checkbox"/> A. Operating		Date Started mo day year 1 3 64		<input checked="" type="checkbox"/> B. Modification/Conversion <input type="checkbox"/> C. Proposed	
Permitting Existing Well Approved by Rule					
VII. TYPE OF PERMIT REQUESTED (Mark 'x' and specify if required)					
<input checked="" type="checkbox"/> A. Individual <input type="checkbox"/> B. Area		Number of Existing wells 1	Number of Proposed wells	Name(s) of field(s) or project(s) East Poplar Unit	
VIII. CLASS AND TYPE OF WELL (see reverse)					
A. Class(es) (enter code(s)) 11 D		B. Type(s) (enter code(s))		C. If class is "other" or type is code "x," explain	
D. Number of wells per type (if area permit)					
IX. LOCATION OF WELL(S) OR APPROXIMATE CENTER OF FIELD OR PROJECT					
A. Latitude		B. Longitude		Township and Range	
Deg Min Sec	Deg Min Sec	Twsp Range Sec	1/4 Sec	Feet from Line	Feet from Line
1 1 1	1 1 1	28N 51E 3	NW	1982 N	761 W
X. INDIAN LANDS (Mark 'x')					
<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No					
XI. ATTACHMENTS					
(Complete the following questions on a separate sheet(s) and number accordingly; see instructions) FOR CLASSES I, II, III (and other classes) complete and submit on separate sheet(s) Attachments A — U (pp 2-6) as appropriate. Attach maps where required. List attachments by letter which are applicable and are included with your application: A, E, G, H, M; O, R, and U.					
XII. CERTIFICATION					
I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)					
A. Name and Title (Type or Print) GLENN M. FEDDERSON Vice President			B. Phone No. (Area Code and No.) 501/862-6411		
C. Signature			D. Date Signed 12/4/84		

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY WASHINGTON, DC 20460			
EPA COMPLETION FORM FOR INJECTION WELLS			
ADMINISTRATIVE INFORMATION			
1. Permittee			
MURPHY OIL USA, INC.			
Address (Permanent Mailing Address) (Street, City, State, and ZIP Code)			
P. O. Box 547, Poplar, Montana 59255 (District Office)			
200 Peach Street, El Dorado, Arkansas 71730 (Home Office)			
2. Operator			
MURPHY OIL USA, INC.			
Address (Street, City, State, and ZIP Code)			
SAME AS ABOVE			
3. Facility Name			Telephone Number
EAST POPLAR UNIT 80D			District Office 406-768-3611
			Home Office 501-862-6411
Address (Street, City, State, and ZIP Code)			
Murphy Oil USA, Inc. (District Office)			
P. O. Box 547			
Poplar, Montana 59255			
4. Surface Location Description of Injection Well(s)			
State		County	
Montana		Roosevelt	
1/4 of	1/4 of	1/4 section	
	SW	NW 3	
Township		Range	
28N		51E	
Feet from (N/S)		Line of quarter section and	
1982		N	
Feet from (E/W)		Line of quarter section	
761'		W	
Submit with this Completion Form the attachments listed in Attachments for Completion Form.			
CERTIFICATION			
I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).			
NAME AND OFFICIAL TITLE (Please type or print)		SIGNATURE	DATE SIGNED
GLENN M. FEDDERSON Vice President			12/4/84



WASHINGTON, DC 20460

**COMPLETION REPORT FOR BRINE DISPOSAL,  
HYDROCARBON STORAGE, OR ENHANCED RECOVERY WELL**


OMB No. 2040-0042  
Approval expires 9-30-86

NAME AND ADDRESS OF HOSTING PERMITTEE  
Murphy Oil USA, Inc.  
200 Peach Street  
El Dorado, AR 71730

EPU 80-D

NAME AND ADDRESS OF SURFACE OWNER  
Willbar P. Lockman  
Box 175  
Poplar, Montana 59255

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES



STATE COUNTY

MT Roosevelt

PERMIT NUMBER

SURFACE LOCATION DESCRIPTION

5<sup>th</sup> NE 1/4 OF NW 1/4 OF 3<sup>rd</sup> SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location 1982 ft. from (N/S) N Line of quarter section  
and 761 ft. from (E/W) W Line of quarter section

WELL ACTIVITY

TYPE OF PERMIT

- ☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage

- ☐ Individual  
☐ Area  
Number of Wells

Estimated Fracture Pressure  
of Injection Zone 2490 psig

Anticipated Daily Injection Volume (Bbls)

Injection Interval

Average

Maximum

Feet

to Feet

1700

4500

3218

3512

Anticipated Daily Injection Pressure (PSI)

Depth to Bottom of Lowermost Freshwater Formation (Feet)

Average

Maximum

Feet

400

650

Warren Corne Water Well 150'

Type of Injection Fluid (Check the appropriate block(s))

- ☒ Salt Water ☐ Brackish Water ☐ Fresh Water  
☐ Liquid Hydrocarbon ☐ Other

Lease Name

EPU

Well Number

80-D

Name of Injection Zone

Dakota Sand

Date Drilling Began

7-2-56

Date Well Completed

7-29-56

Permeability of Injection Zone

DATA NOT AVAILABLE

Date Drilling Completed

7-26-56

Porosity of Injection Zone

DATA NOT AVAILABLE

CASING AND TUBING

CEMENT

HOLE

OD Size	Wt/Ft — Grade — New or Used	Depth	Sacks	Class	Depth	Bit Diameter
13 3/8	48# H-40 New	161.39	175	G-? 1-1 pos	mix 195	17 1/2
9 5/8	35# J-55 New	980.68	400	G-?	990	12 1/2
5 1/2	15.5# J-55 New	5831	300	G-? 1-1 pos	mix 5932	8 3/4
2 7/8	6.5# J-55 New	3189.93	510	G-?		

INJECTION ZONE STIMULATION

WIRE LINE LOGS, LIST EACH TYPE

Interval Treated	Materials and Amount Used	Log Types	Logged Intervals
3218-3512	1304 Bbls Water	Elect Survey 2"	979-5832
		Elect Survey 5"	2000-5832
		Microlog 5"	2000-5831
		Gamma Ray Beutron	2850-5779

Complete Attachments A — E listed on the reverse.


CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)


GLENN M. FEDDERSON

Vice President



DATE SIGNED

12/4/84

<b>WEPA</b>		<b>PLUGGING AND ABANDONMENT PLAN</b>	
NAME AND ADDRESS OF FACILITY Murphy Oil USA, Inc. Poplar, MT 59255		NAME AND ADDRESS OF OWNER/OPERATOR Murphy Oil USA, Inc. 200 Peach Street El Dorado, AR 71730	
EPU NO. 80-D		PERMIT NUMBER	
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT - 640 ACRES		STATE MT	COUNTY Roosevelt
		SURFACE LOCATION DESCRIPTION NE 1/4 OF SW 1/4 OF 1/4 SECTION 3 TOWNSHIP 28N RANGE	
		LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING	
		Surface Location 1982 ft. from (N/S) N Line of quarter section and 761 ft. from (E/W) W Line of quarter section	
TYPE OF AUTHORIZATION <input checked="" type="checkbox"/> Individual Permit <input type="checkbox"/> Area Permit <input type="checkbox"/> Rule Number of Wells 1		WELL ACTIVITY <input type="checkbox"/> CLASS I <input checked="" type="checkbox"/> CLASS II <input checked="" type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage <input type="checkbox"/> CLASS III	
Lease Name EPU		Well Number 80-D	

CASING AND TUBING RECORD AFTER PLUGGING					METHOD OF EMPLACEMENT OF CEMENT PLUGS	
SIZE	WT(LB/FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE	<input type="checkbox"/> The Balance Method <input checked="" type="checkbox"/> The Dump Bailer Method <input type="checkbox"/> The Two-Plug Method <input type="checkbox"/> Other	
13 3/8	48#		155.39	17 1/2		
9 5/8	36#		974.68	12 1/2		
5 1/2	15.5#		5825	8 3/4		
CEMENTING TO PLUG AND ABANDON DATA:					PLUG #1	PLUG #2
Size of Hole or Pipe in which Plug Will Be Placed (inches)					5 1/2	5 1/2
Depth to Bottom of Tubing or Drill Pipe (ft.)					3168	700
Sacks of Cement To Be Used (each plug)					10	10
Slurry Volume To Be Pumped (cu. ft.)					11.5	11.5
Calculated Top of Plug (ft.)					3082	614
Measured Top of Plug (if tagged ft.)						
Slurry Wt. (Lb./Gal.)						
Type Cement or Other Material (Class III)						
LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (If any)						
From		To		From		To
3218		3250				
3284		3410				
3462		3512				
Estimated Cost to Plug Wells						

<b>CERTIFICATION</b>		
<i>I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment, (Ref. 40 CFR 144.32)</i>		
NAME AND OFFICIAL TITLE (Please type or print)	SIGNATURE	DATE SIGNED

EPU 80-D

A. Area of Review

Fixed Radius of 1/4 mile - Field Plat attached. No wells within the area of review.

E. Name and Depth of USDWs (Class II)

<u>Depth</u>	<u>Name</u>	<u>Local Name</u>
150'	Tertiary Sand	Unknown

G. Geological Data

<u>ZONE</u>	<u>NAME</u>	<u>DESCRIPTION</u>	<u>DEPTH</u>	<u>THICKNESS</u>	<u>FRAC PRESSURE</u>
Upper Confining	Skull Creek	Gray Shale w/ Traces of Red Silt.	2980'±	130'±	Unknown
Injection	* Dakota	White, fine grain, Pouous Sandstone	3110'±	350'±	1 psi/foot
Lower Confining	Fuson	Dark Gray Shale w/trace of sand	3600'±	300'±	Unknown

\*The Dakota Sand is overlain by the Dakota Silt.

H. Operating Data

- (1) Average Injection Volume - 1700 Bbls/Day  
Maximum Injection Volume - 4500 Bbls/Day  
Injection Rate 122 Bbls/Hour
- (2) Average Injection Pressure - 400 psi  
Maximum Injection Pressure - 650 psi
- (3) Annulus Fluid - Corrosion Inhibited Fluid
- (5) Source of Injection Fluid - Mississippian Formation fluid produced from the East Poplar Field.
- (6) SWD Station No. 3 operates with one pump and a backup pump.  
See Attached Analysis

M. Schematics Attached

Q. Plugging and Abandonment Plan -  
EPA Form 7520-14 is attached

R. Necessary Resources  
See attached financial statement

U. Description of Business - EPU Well No. 80-D is used to dispose of part of the produced salt water from the East Poplar Unit wells. The salt water is separated from the produced fluid and comes to the disposal facility at SWD Station No. 1 through closed flowlines. The salt water is held in the salt water storage tanks until the salt water disposal pumps are engaged through automatic level switches. The salt water disposal pumps dispose of the salt water into the tubing of the wellbore and then into the formation.

The produced fluids are mixed in the flowlines and the resulting final TDS is approximately 130,000 TDS.

The SWD Station No. 3 operates an average of 14 hours per day.





POPLAR AREA  
ROOSEVELT COUNTY, MONTANA



CONTOUR INTERVAL:

DATE:

SCALE 1" = 400'








East Poplar, Unit  
SWD STATION NO. 3  
EPU WELL NO. 80-D



EPU 80-D Subsurface Well Design





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

# PLUGGING AND ABANDONMENT PLAN

NAME AND ADDRESS OF FACILITY

EPU NO. 80-D  
POPLAR, MONTANA

NAME AND ADDRESS OF OWNER/OPERATOR

MURPHY OIL USA, INC.  
200 Peach St.  
El Dorado, Arkansas 71730

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

N							
S							
W				E			

STATE MT COUNTY Roosevelt

PERMIT NUMBER

SURFACE LOCATION DESCRIPTION

NE 1/4 OF SW 1/4 OF 1/4 SECTION 3 TOWNSHIP 28 RANGE 51

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location 1982 ft. from (N/S) N Line of quarter section

and 261 ft. from (E/W) W Line of quarter section

TYPE OF AUTHORIZATION

- ☐ Individual Permit  
☐ Area Permit  
☐ Rule

Number of Wells

Lease Name

WELL ACTIVITY

- ☐ CLASS I  
☒ CLASS II  
☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage  
☐ CLASS III

Well Number

CASING AND TUBING RECORD AFTER PLUGGING

SIZE	WT(LB/FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE
13 3/8	48#		146.14	17 1/2
9 5/8	36#		966.93	12 1/2
5 1/2	15.5#		5818.5	8 3/4

METHOD OF EMPLACEMENT OF CEMENT PLUGS

- ☐ The Balance Method  
☒ The Dump Bailer Method  
☐ The Two-Plug Method  
☐ Other

CEMENTING TO PLUG AND ABANDON DATA:

	PLUG #1	PLUG #2	PLUG #3	PLUG #4	PLUG #5	PLUG #6	PLUG #7	PLUG #8	PLUG #9
Size of Hole or Pipe in which Plug Will Be Placed (inches)	5 1/2	5 1/2							
Depth to Bottom of Tubing or Drill Pipe (ft.)	3168								
Sacks of Cement To Be Used (each plug)	2	10							
Slurry Volume To Be Pumped (cu. ft.)	2	10							
Calculated Top of Plug (ft.)	3149	10							
Measured Top of Plug (if tagged ft.)									
Slurry Wt. (Lb./Gal.)									
Type Cement or Other Material (Class III)									

LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (If any)

From	To	From	To
3218	3250		
3284	3410		
3462	3512		

Estimated Cost to Plug Wells

\$10,000

## CERTIFICATION


I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print)

SIGNATURE

DATE SIGNED

## PLUGGING AND ABANDONMENT PLAN

NAME AND ADDRESS OF FACILITY Murphy Oil USA, Inc. Poplar, MT 59255		NAME AND ADDRESS OF OWNER/LESSOR Murphy Oil USA, Inc. 200 Peach Street El Dorado, AR 71730	
EPU NO. 80-D		STATE MT	COUNTY Roosevelt
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT — 640 ACRES		PERMIT NUMBER	
		SURFACE LOCATION DESCRIPTION NE 1/4 OF SW 1/4 OF 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E	
LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface Location 1982 ft. from (N/S) N Line of quarter section and 761 ft. from (E/W) W Line of quarter section		TYPE OF AUTHORIZATION <input checked="" type="checkbox"/> Individual Permit <input type="checkbox"/> Area Permit <input type="checkbox"/> Rule Number of Wells 1	
Lease Name EPU		WELL ACTIVITY <input type="checkbox"/> CLASS I <input checked="" type="checkbox"/> CLASS II <input type="checkbox"/> Brine Disposal <input type="checkbox"/> Enhanced Recovery <input type="checkbox"/> Hydrocarbon Storage <input type="checkbox"/> CLASS III Well Number 80-D	

CASING AND TUBING RECORD AFTER PLUGGING					METHOD OF EMPLACEMENT OF CEMENT PLUGS		
SIZE	WT(LB/FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE	<input type="checkbox"/> The Balance Method		
13 3/8	48#		155.39	17 1/2	<input checked="" type="checkbox"/> The Dump Bailer Method		
9 5/8	36#		974.68	12 1/2	<input type="checkbox"/> The Two-Plug Method		
5 1/2	15.5#		5825	8 3/4	<input type="checkbox"/> Other		
CEMENTING TO PLUG AND ABANDON DATA:					PLUG #1	PLUG #2	PLUG #3
Size of Hole or Pipe in which Plug Will Be Placed (inches)					5 1/2	5 1/2	9 5/8
Depth to Bottom of Tubing or Drill Pipe (ft.)					3168	700	100
Sacks of Cement To Be Used (each plug)					10	10	20
Slurry Volume To Be Pumped (cu. ft.)					11.5	11.5	23
Calculated Top of Plug (ft.)					3082	614	15
Measured Top of Plug (if tagged ft.)							
Slurry Wt. (Lb./Gal.)							
Type Cement or Other Material (Class III)							
LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (If any)							
From		To		From		To	
3218		3250					
3284		3410					
3462		3512					
Estimated Cost to Plug Wells							

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print)	SIGNATURE	DATE SIGNED

# PLUGGING AND ABANDON DATA

EPU NO. 80-D  
POPLAR, MONTANA

MURPHY OIL USA, INC.  
200 Peach St.  
El Dorado, Arkansas 71730

LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

STATE MT COUNTY Roosevelt

SURFACE LOCATION DESCRIPTION

NE 1/4 OF SW 1/4 OF 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location 1982 ft. from (N/S) N Line of quarter section  
and 761 ft. from (E/W) W Line of quarter section

TYPE OF AUTHORIZATION

- ☒ Individual Permit  
☐ Area Permit  
☐ Rule

Number of Wells 1

WELL ACTIVITY

- ☐ CLASS I  
☒ CLASS II  
☒ Brine Disposal  
☐ Enhanced Recovery  
☐ Hydrocarbon Storage  
☐ CLASS III

Lease Name EPU

Well Number 80-D

## CASING AND TUBING RECORD AFTER PLUGGING

SIZE	WT(LB/FT)	TO BE PUT IN WELL (FT)	TO BE LEFT IN WELL (FT)	HOLE SIZE
13 3/8	48#		146.14	17 1/2
9 5/8	36#		966.93	12 1/2
5 1/2	15.5#		5818.5	8 3/4

## METHOD OF EMPLACEMENT OF CEMENT PLUGS

- ☐ The Balance Method  
☒ The Dump Bailer Method  
☐ The Two-Plug Method  
☐ Other

## CEMENTING TO PLUG AND ABANDON DATA:

	PLUG #1	PLUG #2	PLUG #3	PLUG #4	PLUG #5	PLUG #6	PLUG #7
Size of Hole or Pipe in which Plug Will Be Placed (inches)	5 1/2 *	5 1/2					
Depth to Bottom of Tubing or Drill Pipe (ft.)	3168						
Sacks of Cement To Be Used (each plug)	2	10					
Slurry Volume To Be Pumped (cu. ft.)	2	10					
Calculated Top of Plug (ft.)	3153	10					
Measured Top of Plug (if tagged ft.)							
Slurry Wt. (Lb./Gal.)							
Type Cement or Other Material (Class III)							

## LIST ALL OPEN HOLE AND/OR PERFORATED INTERVALS AND INTERVALS WHERE CASING WILL BE VARIED (if any)

From	To	From	To
3218	3250		
3284	3410		
3462	3512		

Estimated Cost to Plug Wells \$ 10,000

\*Cast Iron Bridge Plug will be set at 3168' with 2 sacks of cement on top. Top plug will be within 10' of surface. Casing will be cut off 4' below ground and a plate welded on top.

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32)

NAME AND OFFICIAL TITLE (Please type or print)

GLENN M. FEDDERSON  
Vice President

SIGNATURE

DATE SIGNED

12/4/84



LOCATE WELL CORRECTLY

X			

R51E

T28N

(SUBMIT IN TRIPLICATE)  
TOOIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA  
BILLINGS OR SHELBY

## LOG OF WELL

RECEIVED

Form No. 4  
(Gen. Rule 208.3 & 231)

NOV 15 1956

OIL AND GAS CONSERVATION  
OF THE STATE OF MONTANACompany MURPHY CORPORATION Lease 1-37-Ind-12914 Well No. 80Address Poplar, Montana Field (or Area) East PoplarThe well is located 1982 ft. from <sup>(N)</sup><sub>(S)</sub> line and 761 ft. from <sup>(E)</sup><sub>(W)</sub> line of Sec. 3Sec. 3; T. 28N; R. 51E; County Roosevelt; Elevation 2069' K.B.  
(D.F., R.B. or G.L.)Commenced drilling July 2, 1956; Completed July 29, 1956

The information given herewith is a complete and correct record of the well. The summary on this page is for the condition of the well at the above date.

Completed as Oil Well  
(oil well, gas well, dry hole)Signed M. Y. JamesTitle Field Production Supt.Date November 1, 1956

## IMPORTANT ZONES OF POROSITY

(denote oil by O, gas by G, water by W; state formation if known)

From <u>5456</u> to <u>5474</u> "A-1" <u>0</u>	From _____ to _____
From _____ to _____	From _____ to _____
From _____ to _____	From _____ to _____
From _____ to _____	From _____ to _____

## CASING RECORD

Size Casing	Weight Per Ft.	Grade	Thread	Casing Set	From	To	Sacks of Cement	Cut and Pulled from
13 3/8"	48#	H-40	8rd	161.39			175	
9 5/8"	36#	J-55	8rd	980.68			400	
5 1/2"	15.50#	J-55	8rd	5831.00			300	

## TUBING RECORD

Size Tubing	Weight Per Ft.	Grade	Thread	Amount	Perforations
2 3/8"	4.70#	J-55	8rd	5483.85	Open Ended

## COMPLETION RECORD

Rotary tools were used from 0 to 5832'

Cable tools were used from \_\_\_\_\_ to \_\_\_\_\_

Total depth 5832 ft.; Plugged back to 5779 T.D.; Open hole from \_\_\_\_\_ to \_\_\_\_\_

PERFORATIONS			ACIDIZED, SHOT, SAND FRACED, CEMENTED			
Interval		Number and Size and Type	Interval		Amount of Material Used	Pressure
From	To		From	To		
5456	5474	1 1/2" jets per ft.	5456	5474	500 gallons	2500#

(If P&amp;A show plugs above)

## INITIAL PRODUCTION

Well is producing from Madison (pool) formation.I. P. 125 barrels of oil per 24 hours Pumping  
(pumping or flowing)neg. Mcf of gas per \_\_\_\_\_ hours.  
48 barrels of water per 24 hours, or 28 % W.C.

(OVER)

4 4 1 3

Pressures (if measured): Tubing \_\_\_\_\_ psi flowing; \_\_\_\_\_ psi shut;  
Casing \_\_\_\_\_ psi flowing; \_\_\_\_\_ psi shut;

IN THE DISTRICT COURT OF THE UNITED STATES FOR THE DISTRICT OF COLUMBIA

4470 1

4470 1

• • • • •

SEE ATTACHED PAGE 3

1

DATE: 1975 10 17

GEOLOGICAL PROSPECTUS

Division Billings Lease No. 3649  
Operator Murphy Corporation Well Name East Poplar Unit Well No. 80  
Location: Section SW NW 3 Township 28 North Range 51 East  
Pool Name: East Poplar County Roosevelt State Montana  
Type of Well: Oil X Gas      Exploratory      Development X  
Objective Formation Madison "C" Zone Projected Depth 5800'  
Well Elevation 2065' K.B. (est.)

Judith River-----	725 (+1340)	Piper Shale-----	4260 (-2195)
Eagle-----	1129 (+ 936)	Piper Limestone-----	4345 (-2280)
Niobrara-----	1983 (+ 82)	Spearfish-----	4593 (-2528)
Greenhorn-----	2345 (- 280)	Amsden-----	4733 (-2668)
Muddy-----	2912 (- 847)	Heath-----	4825 (-2760)
Dakota-----	3118 (-1053)	Otter-----	5017 (-2952)
Morrison-----	3547 (-1482)	Kibbey Sandstone-----	5113 (-3048)
Swift-----	3563 (-1498)	Kibbey Limestone-----	5275 (-3210)
Rierdon-----	3912 (-1847)	Madison-----	5370 (-3305)

Anticipated Pay Horizons, Net Pay and Expected Depths:

Madison  
"A" Zone----- 10' -----5478 (-3413)  
"B-1" Zone----- 9' -----5620 (-3555)  
"B-2" Zone----- 16' -----5638 (-3573)  
"C" Zone----- 15' -----5773 (-3708)

Recommended Coring and Formation Testing Program:

Circulate Heath & Kibbey sandstones and core on show.  
Test if warranted.

Recommended Sampling and Logging Program:

20' samples from 2000' to 4000'	2" E.S. base surface pipe to total depth
10' samples from 4000' to total depth.	5" E.S. 2000' to total depth.
	5" M.L. 2000' to total depth
	25" M.L. 5350' to total depth.

Remarks (Including pertinent data relative to location accessibility, unusual drilling problems due to surface and subsurface conditions, etc.)

  
Division Geologist

5-31-56  
Date

FW/vf



WELL DRILLING PLAN

Field or Area East Poplar Unit Division Billings

County or Parish Roosevelt Total Anticipated Depth 5800'

Lease East Poplar Unit Well Name East Poplar Unit Well No. 80

Well Location SW NW Section 3-T28N-R51E

Lowest fresh water sand (for surface casing program): 90'

Casing and tubing program:

	<u>From</u>	<u>To</u>	<u>Size</u>	<u>Weight</u>	<u>Grade</u>	<u>Bit Size</u>
Conductor	<u>0</u>	<u>150'</u>	<u>13-3/8"</u>	<u>48#</u>	<u>H</u>	<u>17-1/4"</u>
Surface	<u>0</u>	<u>1000'</u>	<u>9-5/8"</u>	<u>32.75#</u>	<u>J</u>	<u>12-1/4"</u>
Intermediate						
Production	<u>0</u>	<u>5800'</u>	<u>5-1/2"</u>	<u>15.50#</u>	<u>J</u>	<u>8-3/4"</u>
Tubing	<u>0</u>	<u>5800'</u>	<u>2-7/8"</u>	<u>4.60#</u>	<u>J</u>	<u>EUE</u>

Potential Drilling Hazards Gas and water flow may be expected from the Judith River Sand.

Mud Program Raise mud weight to 11 $\frac{1}{2}$  to 12 PPG while drilling the Judith River sand.

Usual procedure under surface casing.

Coring Method and Dize Core Bits to be used None

Intervals Cores to be Analyzed None

Method of Drill Stem Testing None

Anticipated Completion Zone "B-1" and "B-2" Zones

Method of opening pay, perforation or open hole, and approximate interval: Commingled completion

Expected Formation Treatments 1000 gallons etching acid in each zone.

Expected logs for Development, Evaluation, or Completion Purposes Radio-active logs from T.D. to 3000' inside production string plus the logs indicated on the Geological Prospectus.

Remarks:

Date 5/31/56

Production Superintendent *Holden*

80-D

Area of Review

Fixed Radius of 1/4 mile - Field Plat attached. No wells within the area of review.

E. Name and Depth of USDWs (Class II)

<u>Depth</u>	<u>Name</u>	<u>Local Name</u>
150'	Tertiary Sand	Unknown

Judith River

G. Geological Data

<u>ZONE</u>	<u>NAME</u>	<u>DESCRIPTION</u>	<u>DEPTH</u>	<u>THICKNESS</u>	<u>FRAC PRESSURE</u>
Upper Confining	Skull Creek	Gray Shale w/ Traces of Red Silt.	2980'±	130'±	Unknown
Injection	* Dakota	White, fine grain, Pouous Sandstone	3110'±	350'±	1 psi/foot
Lower Confining	Fuson	Dark Gray Shale w/trace of sand	3600'±	300'±	Unknown

\*The Dakota Sand is overlain by the Dakota Silt.

H. Operating Data

- (1) Average Injection Volume - 1700 Bbls/Day  
Maximum Injection Volume - 4500 Bbls/Day
- (2) Average Injection Pressure - 400 psi ok  
Maximum Injection Pressure - 650 psi ok my max = 730 psi -
- (3) Annulus Fluid - Corrosion Inhibited Fluid
- (5) Source of Injection Fluid - Mississippian Formation fluid produced from the East Poplar Field.
- (6) SWD Station No. 3 operates with one pump and a backup pump.  
See Attached Analysis
- Injection Rate 122 Bbls/Hour
- 700  
294

M. Schematics AttachedQ. Plugging and Abandonment Plan -  
EPA Form 7520-14 is attachedR. Necessary Resources  
See attached financial statementU. Description of Business - EPU Well No. 80-D is used to dispose of part of the produced salt water from the East Poplar Unit wells. The salt water is separated from the produced fluid and comes to the disposal facility at SWD Station No. 1 through closed flowlines. The salt water is held in the salt water storage tanks until the salt water disposal pumps are engaged through automatic level switches. The salt water disposal pumps dispose of the salt water into the tubing of the wellbore and then into the formation.


The produced fluids are mixed in the flowlines and the resulting final TDS is approximately 130,000 TDS.

The SWD Station No. 3 operates an average of 14 hours per day.

PA

COMPLETION REPORT FOR BRINE DISPOSAL  
HYDROCARBON STORAGE, OR ENHANCED RECOVERY WELLNAME AND ADDRESS OF HOSTING PERMITTEE  
Murphy Oil USA, Inc.  
200 Peach Street  
El Dorado, AR 71730

EPU 80-D

NAME AND ADDRESS OF SURFACE OWNER  
Willbar P. Lockman  
Box 175  
Poplar, Montana 59255LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

STATE MT COUNTY Roosevelt PERMIT NUMBER

SURFACE LOCATION DESCRIPTION

NE 1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface  
Location 1982 ft. from (N/S) N Line of quarter section  
and 761 ft. from (E/W) W Line of quarter section

WELL ACTIVITY

TYPE OF PERMIT

- ☒
- Brine Disposal
- 
- ☐
- Enhanced Recovery
- 
- ☐
- Hydrocarbon Storage

- ☐
- Individual
- 
- ☐
- Area

Estimated Fracture Pressure  
of Injection Zone

2490 psig

Anticipated Daily Injection Volume (Bbls)

Injection Interval

Average

Maximum

Feet

to Feet

1700

4500

3218

3512

Anticipated Daily Injection Pressure (PSI)

Depth to Bottom of Lowermost Freshwater Formation  
(Feet)

Average

Maximum

400

650

Warren Corne Water Well 150'

Type of Injection Fluid (Check the appropriate block(s))

- ☒
- Salt Water
- ☐
- Brackish Water
- ☐
- Fresh Water
- 
- ☐
- Liquid Hydrocarbon
- ☐
- Other

Lease Name

EPU

Well Number

80-D

Name of Injection Zone

Dakota Sand

Date Drilling Began

7-2-56

Date Well Completed

7-29-56

Permeability of Injection Zone

DATA NOT AVAILABLE

Date Drilling Completed

7-26-56

Porosity of Injection Zone

DATA NOT AVAILABLE

## CASING AND TUBING

## CEMENT

## HOLE

OD Size	WT/Ft — Grade — New or Used	Depth	Secks	Class	Depth	Bit Diameter
13 3/8	48# H-40 New	150.14' ok	175	G-? 1-1 pos	mix 195	17 1/2
9 5/8	35# J-55 New	970.93' ok	400	G-?	990	12 1/2
5 1/2	15.5# J-55 New	5822.5' ok	300	G-? 1-1 pos	mix 5932	8 3/4
2 7/8	6.5# J-55 New	3189.93' ok	610	G-?		

## INJECTION ZONE STIMULATION

## WIRE LINE LOGS, LIST EACH TYPE

Interval Treated	Materials and Amount Used	Log Types	Logged Intervals
3218-3512	1304 Bbls Water	Elect Survey 2"	979-5832
		Elect Survey 5"	2000-5832
		Microlog 5"	2000-5831
		Gamma Ray Neutron	2850-5779

Complete Attachments A — E listed on the reverse.


## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

GLENN M. FEDDERSON

Vice President



DATE SIGNED

12/4/84


COMPLETION REPORT FOR BRINE DISPOSAL,  
HYDROCARBON STORAGE, OR ENHANCED RECOVERY WELL

## NAME AND ADDRESS OF EXISTING PERMITTEE

Murphy Oil USA, Inc.  
200 Peach Street  
El Dorado, AR 71730

EPU 80-D

## NAME AND ADDRESS OF SURFACE OWNER

Willbar P. Lockman  
Box 175  
Poplar, Montana 59255LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRES

STATE

MT

COUNTY

Roosevelt

PERMIT NUMBER

## SURFACE LOCATION DESCRIPTION

NE 1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

## LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface  
Location 1982 ft. from (N/S) N Line of quarter section  
and 261 ft. from (E/W) W Line of quarter section

## WELL ACTIVITY

☒ Brine Disposal☐ Enhanced Recovery☐ Hydrocarbon Storage

## TYPE OF PERMIT

☐ Individual☐ Area

Number of Wells

Estimated Fracture Pressure  
of Injection Zone  
2490 psig

## Anticipated Daily Injection Volume (Bbls)

Average

1700

Maximum

4500

## Injection Interval

Feet

3218

to Feet

3512

## Anticipated Daily Injection Pressure (PSI)

Average

400

Maximum

650

Depth to Bottom of Lowermost Freshwater Formation  
(Feet)

Warren Corne Water Well 150'

## Type of Injection Fluid (Check the appropriate block(s))

☒ Salt Water☐ Brackish Water☐ Fresh Water☐ Liquid Hydrocarbon☐ Other

## Lease Name

EPU

## Well Number

80-D

## Name of Injection Zone

Dakota Sand

## Date Drilling Began

7/2/56

## Date Well Completed

7/29/56

## Permeability of Injection Zone

Data Not Available

## Date Drilling Completed

7/26/56

## Porosity of Injection Zone

Data Not Available

## CASING AND TUBING

OD Size	Wt/Ft — Grade — New or Used	Depth	Sacks	Class	Depth	Bit Diameter
13 3/8	48# H-40 New	150.14'	175	G-? 1-1 pos mix	195	17 1/2
9 5/8	35# J-55 New	970.93'	400	G-?	990	12 1/2
5 1/2	15.5# J-55 New	5822.5'	300	G-? 1-1 pos mix	5932	8 3/4
2 7/8	6.5# J-55 New	3189.93'	610	G-?		

## CEMENT

## HOLE

## INJECTION ZONE STIMULATION

## WIRE LINE LOGS, LIST EACH TYPE

Interval Treated	Materials and Amount Used	Log Types	Logged Intervals
3218-3512	1304 Bbls. Water	Elect Survey 2"	979-5832
		Elect Survey 5"	2000-5832
		Microlog 5"	2000-5831
		Gamma Ray Neutron	2850-5779

Complete Attachments A — E listed on the reverse.

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Alvin W. Simpson  
Manager of Operations

DATE SIGNED

March 14, 1985

## Cement Calculations

5 1/2" casing in 8 3/4" hole

$$300 \text{ sx} = 1.15 \text{ cu/sx} = 345 \text{ cu ft.}$$

Vol & Hight between Csg & hole  
3.9589 Lb ft / cu ft.

$$345 \text{ ft}^3 \times 3.9589 \text{ ft/ft}^3 = 1365.8 \text{ ft of cement}$$

$$5822.5' - 1365.8$$

$$\text{TOC} = 4456.68$$

Block Squeeze cement at 3595  $610 \text{ sx} \times 1.15 = 701.5 \text{ ft}^3$

$$701.5 \text{ ft}^3 \times 3.9589 \text{ ft/ft}^3 = 2777.16 \text{ ft}$$


$$1679.5 - 4456.6 - 2777.16 = 1679 \text{ ft}$$

Block Squeeze at 3595 ft. assume no  
displacement downward because of mud and mud cake  
 $3595 - 2777.16 = 817.84 \text{ feet} = \text{TOC}$

TOC is inbetween 817.84 and 1679 ft

$$\approx 1000'$$

EPU 80-D Subsurface Well Design



Permit Application & Attachments

3342.1

=====

C O M P L E T I O N   D A T A

=====

CASING:

- 7-2-56: 195' Ran 4 joints (150.14') of 13 3/8", 48#, H-40, 8rd thd., ST&C, R-2 and 3, Class "A" American casing. Landed 11.25' below RKB at 161.39'. Ran Howco guide shoe on bottom. Cemented with 175 sacks of 1.1 Pozmix with 3% CaCl<sub>2</sub>. Ran 10 barrels of water ahead, left 10 sacks of cement on top of plug. Bumped plug with 600# at 2:45 A.M., 7-3-56. Bled pressure to 300#, circulated approximately 100 sacks of clean cement to surface.
- 7-5-56: 990' Ran 30 joints (970.93') of 9 5/8", 36#, J-55, 8rd thd., ST&C, R-2, Class "A" American casing. Landed 9.75' below RKB at 980.68'. Ran Howco float shoe on bottom and 1 Howco centralizer at 965', circulated to clean hole 30 minutes. Cemented with 400 sacks of regular cement with 2% CaCl<sub>2</sub>. Ran 10 barrels of water ahead of cement. Left 10 sacks of cement on top of plug. Circulated approximately 100 sacks of clean cement to surface. Bumped plug at 8:17 A.M. with 1050# psi, released pressure, float held ok. Packed off 9 5/8" to 13 3/8" with Norris head. Waited on cement 16 hours. Tested casing with 1000# for 30 minutes, held ok.
- 7-26-56: TD 5932' Ran 187 joints (5822.50') of 5 1/2", J-55, 15.50#, 8rd thd., R-2, ST&C, Class "A" American casing. Landed 8.50' below RKB and set 1' off bottom at 5831'. Ran Howco differential fillup shoe at 5831', and Howco baffle collar at 5797'. Ran 6 Weatherford centralizers at 5818', 5588', 5640', 5515', 5450', and 5204'. Ran 73 Weatherford scratchers from 5156-5831' spaced as follows: 15' 5156-5281', none from 5281-5373', 15' 5373-5434', 5' 5434-5509', 10' 5509-5645', 5' 5645-5735', 10' 5735-5797', 5' 5797-5831'. Cemented with 300 sacks of 1.1 Pozmix, 22% NaCl 2% gel. Reciprocated casing 40' while circulating 30 minutes and during cementing. Bumped plug at 12:30 P.M., 7-26-56. Released pressure, float held. Set slips. Released Zach Brooks rig at 6:30 P.M., 7-26-56. To complete with pulling unit.
- COMPLETION:
- 7-27-56: Preparing to log, moving off rig.
- 7-28-56: PSTD 5779' Ran Schlumberger Gamma Ray Neutron and Collar logs from TD to 2850'. Perforated "A-1" Zone 5456-5474' with Schlumberger's casing jet gun, 4 jets per foot. Ran tubing and circulated out with water.
- 7-29-56: Acidized "A-1" Zone 5456-5474' with 500 gallons of Dowell etching acid. Formation broke at 2500#, back to 2300#. Bled 1/2 barrel from casing. Began injecting at .4 BPM at 1300#. Pressure increased slowly to 2000# while injected remaining 3 barrels acid at .4 BPM. Final pressure 1750#. Bled down pressure 1460#. Opened well to bit at 9:00 A.M. Flowed weak stream 30 minutes and died. Swabbed displacement oil, spent acid and began showing oil at 10:04 A.M. Swabbed 7 hours. On last 2 hours, swabbed at the rate of 16 BPPH, 60% water.
- 7-30-56: Testing "A-1" Zone. Shut well in overnight. SICP=725#, SITP=475#.

Completion Data Continued

Opened well up. Flowed off head and began flowing small heads. Swabbed well 2 hours to pit, then 2 hours in test tank. 1st hour swabbed 10.5 BF, 90% water; 2nd hour swabbed 26 BF, 10% water. Fluid level lowered from 2000' to 3000' while swabbing in tank. Swabbed to pit 1 hour. Fluid level remained constant at 3000', water cut 15%. Put well on 16/64" choke. Well filled up and flowed 5 barrels in 11 hours. Flowed 2.30 BJ in 6 hours flowing small weak heads. TFP = 0#, CP = 375#, 20/64" choke. To circulate water out of tubing with oil.

- 7-31-56: Flow rate on an 8-hour test = 96 BFPD, 25% BS&W (72 BOPD, 24 BWPD).
- 8-1-56: Circulating tubing out with oil. Tied in flowline. Flowed on a 2-hour test at the rate of 81 BFPD, 1.6% BS&W (80 BOPD, 1 BWPD), CFP = 450#, TFP = 0#.
- 8-2-56: Testing on open flow 49 BFPD, .6 of 1% BS&W.
- 8-3-56: Flowing on a 24-hour test at the rate of 61 BFPD, 4.5% BS&W (53 BOPD, 3 BWPD), CFP = 400#, TFP = 0#, open flow.
- 8-4-56: Flowing on a 4-hour test at the rate of 34 BFPD, 6% water (32 BOPD, 2 BWPD).
- 8-5-56: Flowing on a 4-hour test at the rate of 47 BFPD, 13% water (41 BOPD, 6 BWPD). Well produced 54 BOPD in tank.
- 8-6-56: Flowing on a 24-hour test at the rate of 49 BOPD plus 13% BS&W.
- 8-7-56: Setting pumping unit. 2-hour fluid test, flowed 65 BFPD, 10% water (53 BOPD, 7 BWPD). Production 32 barrels oil, flowed 12 hours through treater.
- 8-8-56: Setting pumping unit. Production 24 hours, open flow 43 barrels oil.
- 8-9-56: Flowing on a 24-hour test, open flow, 70 BFPD, 15% water (59 BOPD, 11 BWPD).
- 8-10-56: Setting pumping unit.
- 8-11&12-56: Waiting on pulling unit to null tubing and run rods and moving in pulling unit.
- 8-13-56: Preparing to pump "A" Zone. Pulled 114 joints of tubing, put in pin collar and seating nipple. Ran rods.
- 8-15&16-56: Waiting on grout to set.
- 8-17&18-56: Pumping, no tests.
- 8-19-56: Pumping. On a 2-hour test pumped at the rate of 146 BFPD, 32% water (99 BOPD, 47 BWPD).



Completion Data Continued

---

8-20-56: Pumping 211 BFPD, 28% water (152 BOPD, 59 EFPD). Pumping on  
4 1/2 x 16 SPM (barrel, 1 1/2" bore spaced at 3500').

8-21-56: Pumping rate 162 BFPD, 30% water (113 BOPD, 49 EFPD).

8-22-56: Pumping on a 3-hour test, pumped at the rate of 119 BFPD, 28%  
water (86 BOPD, 33 EFPD).

8-23-56: Pumping on a 17-hour test at the rate of 155 BFPD, 30% water  
(109 BOPD, 46 EFPD).

8-24-56: Pumping on a 6-hour test through treater at the rate of 173 BFPD,  
28% water (125 BOPD, 48 EFPD). Potential test. To drop from report.

Completion Data (Tubing and Rod Record)

TUBING: 2 3/8", 4.70#, J-55, 8rd thd., Class "A" and "B" American:

Below RKB	6.75
Top joint	30.72
112 jts 2 3/8" tbg	3478.72
Seating nipple	1.16
1 joint	31.53
Pin collar	.50
62 joints 2 3/8" tbg	1934.47
Total	5483.85

ROD RECORD: 2 6' 3/4" scraper subs  
1 8' 3/4" scraper subs  
39 3/4" scraper rods  
20 3/4" plain rods  
80 5/8" plain rods  
Axelson 2" x 1-1/2" x 16', top hold down insert pump

=====

E L E C T R O L O G D A T A

=====

TYPE OF LOGINTERVAL LOGGED

Schlumberger Electrical Survey 2"	979'-5832'
Schlumberger Electrical Survey 5"	2000'-5832'
Schlumberger Microlog 5"	2000'-5831'
Schlumberger Gamma Ray Neutron 5"	2850'-5779'

LOG TOPS

Niobrara	2003	+ 66	
Greenhorn	2340	- 271	
Graneros	2545	- 476	
U. Muddy	2682	- 613	
Muddy Sd	2920	- 855	
Dakota	3114	-1045	
Vanguard	3902	-1833	
Rierdon	4085	-2016	
Piper Sh	4254	-2185	
Piper Ls	4338	-2269	
Gypsum Sprgs	4393	-2324	
Spearfish	4588	-2519	
Amsden	4693	-2624	
Heath	4825	-2756	
Otter	5030	-2961	
Kibbey Sd	5124	-3055	
Kibbey Por.	5150	-3081	
Kibbey Ls	5280	-3211	
Madison	5375	-3311	
A-1	5457	-3388	4'
A-2	5469	-3400	4'
A-3	5489	-3420	17'
A-4	5501	-3432	27'
B-1	5641	-3572	9'
B-2	5659	-3590	17'
B-3	5679	-3610	2'
B-4	5712	-3643	6'
B-5	5753	-3684	?
C-1	5794	-3725	?
C-2	5809	-3740	?

=====

DRILL STEM TESTS

=====

- D.S.T. #1: 5650.5'-5659' ("B-2" Zone) with Halliburton single packer test, 1/2" bottom choke, no water cushion. Tool opened with good blow and remained same thruout test. Tool open 2 hours, shut in 30 minutes. Recovered 2051' gas, 273' clean oil, 182' oily muddy salt water, and 1647' salt water. Pressures - IBHFP - 112#, FBHFP - 1745#, BHSIP - 2938#, Hydro - 3260#.
- D.S.T. #2: 5634'-5646' ("B-1" Zone) with Halliburton straddle packer test, 1/2" bottom choke, no water cushion. Tool opened with medium blow and remained same thruout test. Tool open 2 hours, shut in 20 minutes. Recovered 546' gas, 30' clean oil, 60' oil-and-gas cut mud, and 800' salt water. Pressures - IBHFP - 30#, FBHFP - 140#, BHSIP - 2555#, Hydro - 3260#.
- D.S.T. #3: 5669'-5686' ("B-3" Zone) Packer failed when set, misrun.  
(Misrun)
- D.S.T. #3: 5669'-5686' ("B-3" Zone) with Halliburton double packers, bottom packer set at 5669', 1/2" bottom choke, no WC. Tool opened with weak blow, increased to medium blow in 15 minutes, and remained same thruout test. Tool open 2 hours, shut in 20 minutes. Recovered 795' salt water, no show of oil. Pressures: IBHFP - 30#, FBHFP - 385#, SIHFP - 2935#, Hydro - 3260#.
- D.S.T. #4: 5790.5'-5808' to test fractures above "C" Inter-crystalline zone, Halliburton single packer test, 1/2" bottom choke, 1/4" top choke, no water cushion. Tool opened with good blow and remained same thruout test. Tool open 2 hours, shut in 20 minutes. Recovered 3367' muddy salt water. IBHFP - 58#, FBHFP - 1582#, BHSIP - 3070#, Hydro - 3315#.
- D.S.T. #5: 5485.5'-5496' ("A" Zone) with Halliburton hookwall test, set straddle packer. 1/2" bottom choke, no water cushion. Tool opened with weak blow, increased to medium blow after 15 minutes and remained same thruout test. Tool open 2 hours, shut in 20 minutes. Recovered 200' gas, 45' clean oil, 45' mud-cut oil, and 130' salt water. Pressures: IBHFP - 30#, FBHFP - 112#, BHSIP - 2990#, Hydro - 3152#.

# CORE ANALYSIS REPORTS

Company MURPHY CORPORATION Date 7-25-56 Lab No. 2742 Well No. Unit #80 Location C SW NW 3-28N-51E  
 Formation B-1, B-2 & B-3 Zones Field East Poplar County Roosevelt State Montana Depth 5625-5689.0'

Sample Interval		Footage	PERMEABILITY			Total Porosity Per Cent	SATURATION % PORE SPACE	
No.	Feet		Max.	90°	Matrix		Residual Oil	Water
			Core No. 1 5652-59° Cut 34° Recovered 33°					
	5625-35.5	10.5	-	-		-	-	
				<u>B-1 Zone</u>				
1	5635.5-35.8	0.3	0.4	0.4		7.2	Trace	100.0
	5635.8-36.6	0.8	-	-		7.2	Trace	100.0
2	5636.6-37.3	0.7	-	-	4.8	12.5	Trace	78.4
3	5637.3-38.2	0.9	5.9	4.0		4.2	Trace	81.0
	5638.2-38.5	0.3	-	-		4.2	Trace	81.0
4	5638.5-39.3	0.8	3.7	2.1		6.4	Trace	39.1
5	5639.3-40.2	0.9	4.8	1.6		7.6	11.5	61.8
6	5640.2-41.5	1.3	3.4	2.5		10.6	Trace	90.6
	5641.5-42.5	1.0	-	-		-	-	-
	5642.5-53.5	11.0	-	-		-	-	-
				<u>B-2 Zone</u>				
7	5653.5-54.0	0.5	17	11		11.4	7.9	51.8
8	5654.0-55.2	1.2	7.4	5.6		17.4	Trace	50.3
9	5655.2-55.7	0.5	13	11		16.7	3.4	54.5
10	5655.7-56.3	0.6	2.6	2.5		10.6	1.9	66.0
11	5656.3-58.0	1.7	9.3	6.1		15.2	11.2	48.0
	5658.0-59.0	1.0	-	-		-	-	-
			Core No. 2 5659-86° Cut 27° Recovered 30°					

## CORE ANALYSIS REPORTS CONTINUED

Sample No.	Interval Feet	Footage	PERMEABILITY		Total Porosity Per Cent	SATURATION % PORE SPACE	
			Max.	90° Matrix		Residual Oil	Water
12	5659.0-59.7	0.7	2.8	0.1	16.7	1.2	61.1
13	5659.7-60.4	0.7	6.3	4.4	9.5	Trace	100.0
14	5660.4-61.0	0.6	311	192	8.3	Trace	75.9
15	5661.0-61.8	0.8	2.0	0.2	6.4	Trace	100.0
	5661.8-63.1	1.3	-	-	6.4	Trace	100.0
16	5663.1-64.1	1.0	13	6.9	16.3	Trace	57.7
17	5664.1-65.0	0.9	6.4	4.5	19.7	Trace	47.7
18	5665.0-66.0	1.0	14	7.6	13.3	2.3	97.7
19	5666.0-67.0	1.0	11	9.0	16.7	1.0	99.0
20	5667.0-68.0	1.0	20	7.9	20.1	Trace	79.6
21	5668.0-69.0	1.0	13	12	16.7	7.2	87.4
	5669.0-75.0	6.0	-	-	-	-	-
<u>B-3 Zone</u>							
22	5675.0-76.0	1.0	0.7	0.6	14.1	Trace	85.0
23	5676.0-77.0	1.0	1.7	1.3	18.9	Trace	92.1
24	5677.0-78.0	1.0	1.4	1.2	16.7	Trace	73.7
25	5678.0-79.4	1.4	1.1	0.6	14.5	Trace	89.7
	5679.4-79.8	0.4	-	-	14.5	Trace	89.7
26	5679.8-80.5	0.7	1.2	0.7	13.5	Trace	26.7
27	5680.5-81.0	0.5	0.6	0.5	13.8	Trace	96.4
	5681.0-89.0	8.0	-	-	-	-	-
<u>SUMMARY</u>							
<u>B-1 Zone</u>							
	5635.5-41.5	6.0	4.1*		7.9	Trace (14.5)	79.2
<u>B-2 Zone</u>							
	5653.5-58.0	4.5	9.2		14.9	6.3	52.2
	5659.0-69.0	10.0	31*		13.8	1.1	83.3
<u>B-3 Zone</u>							
	5675.0-81.0	6.0	1.2*		15.4	Trace	79.9

\*Does not include permeability of open fractures. B-1 Zone has 1.8° of open fractures; B-2 Zone 1.3° and B-3 Zone 0.4°. Production tests required to determine type of fluid recovery from fractures. Fractures could load into oil.

C O R E D E S C R I P T I O N S

Core No. 1 5625 - 5659, recovered 33':

- 3'6" Anhydrite: hard, gray, dense salt inclusions.
- 7'0" Anhydrite: hard, dark gray, dense, no salt.
- 7'0" Limestone: dark gray brown, finely crystalline with good permeability and porosity, good oil odor, spotted to even staining 1 1/2', 2" from top of unit, hard tight, poor permeability and porosity.
- 11'0" Anhydrite: hard, dense, dark gray.
- 4'6" Limestone: dark gray, brown, finely crystalline, good oil odor, spotted florescence, fair permeability and porosity.

Core No. 2 5659 - 5686, recovered 30':

- 10'0" Limestone: dark gray brown, finely crystalline, spotted golden florescence, poor to fair permeability and porosity, sulfur odor at bottom of unit.
- 6'0" Limestone: black banded, lithographic thin bands of saturation, permeability and porosity.
- 6'0" Dolomite: limy at top, becoming more dolomitic with depth, light gray brown, earthy, fair oil odor and sooty florescence.
- 8'0" Anhydrite: light gray, dense.

Core No. 3 5785 - 5808, recovered 20':

- 4'6" Limestone: black hard, dense, no permeability and porosity, no show, bottom 1 1/2' of unit open vertical fracture, no show on fracture planes.
- 0'5" Limestone: dark brown, micro crystalline, poor permeability and porosity, spotted golden florescence, weak oil odor.
- 5'6" Limestone: dark gray to black, dense, no permeability and porosity, open vertical fractures with spotted florescence on fracture plane, no matrix show.
- 0'6" Limestone: dark gray brown, micro crystalline, poor permeability and porosity, spotted golden florescence, weak oil odor.

Core Descriptions Continued

9'0" Limestone: dark gray to black, dense, open vertical fractures, no show on fracture planes; scattered anhydrite inclusions top 2 1/2' unit.



# MUD PROGRAM SUMMARY

MUD SERVICE CO.:

Period

MUD ADDITIVES AND COST:

Material	Surface Hole		Surface -- T.D.		Total	
	Amt.	Cost	Amt.	Cost	Amt.	Cost
Aquagel			90	207.00	90	207.00
Barafos	6	165.00			6	165.00
Bariod	738	2,258.28			738	2,258.28
Carbonox			13	65.00	13	65.00
Caustic			52	709.80	52	709.80
Driscose			12	510.00	12	510.00
Hulls			27	126.90	27	126.90
Smeritox	4	28.24	2	11.12	6	42.36
Tannex	11	148.50	79	1,056.50	90	1,215.00
Fibertex			7	28.00	7	28.00
Cement	5	9.50			5	9.50
Total Mud		2,609.52		2,757.32		5,366.84
Drayage		475.33		71.51		546.84
TOTAL		3,084.85		2,831.83		5,916.68
Crude Oil			165	429.00	165	429.00
TOTAL		3,084.85		3,260.83		6,345.68

UNIT MUD COSTS:	Total	Feet	Cost/Ft.	Days	Cost/Day
	Cost	Drld.		Used	
Spud - T.D.	6,345.68	5823	1.09	25	253.83
Spud - Surface	3,084.85	990	3.12	5	616.97
Surface - T.D.	3,260.83	4833	.67	20	163.04

MUD PROPERTIES:

Depth	Weight	Viscosity	Water Loss	pH	Salt	% Crude	Remarks
700	12.5	59					
4468	10.45	36	10.4	12.8	Nil		Before Adding Crude oil.
4859	10.5	51	9.2	12.5	500	6	
5130	10.3	54	7.4	12.5	900	8	
5412	10.6	59	7.2	12.5	2500	7	
5658	10.6	56	7.4	11.5	20,000	7	Drld Salt.
5730	10.5	66	11.1	11.5	25,000	8	
5803	10.7 - 10.4	53	8.4	11.5	22,000	8	Lost Circ w/ wt. 10.7. Cut wt to 10.4 & added lost circ. material.
5823	10.5	68	7.2	11.5	23,000	7	

## Mud Program Summary

### SUMMARY:

Weighted up to 12.5 # per gallon with Baroid at 600' to drill Judith River Gas Sand. Tannex was used as a thinner for surface mud.

Drilled to 5350' with water and native mud. At this depth mud converted to high pH red mud with 100#/50# caustic soda - tannex. After weight built up to 10.5# per gallon 25 barrels crude oil were added on successive days. There after 20 barrels were added daily. Caustic soda - tannex and caustic - carbonox were alternately used as treatments. Driscose was used to keep water loss below 10 cc while drilling producing zones.

Three cores were cut and 5 drill stem tests run including Test #5 with Halliburton open hole hook wall to test the A zone from 5485.5-5496' after drilling to TD. No difficulty was encountered running logs and casing.

The lost circulation at 5823' and the mud properties required to run the open hole hook wall test accounted for the above normal mud cost below surface.

EPU NO. 80  
DRILLING BIT RECORD

Bit No.	Make	Size	Type	Ser. No	Depth Out
	Security	17 1/2"	Pilot	Re-run	175
	"	12 1/4"	S3	Re-run	990
1	"	8 3/4"	S3	133932	3030
2	"	"	S4	135158	3505
3	Hughes	"	Q/V	28981	3505
4	Security	"	S6	134190	3730
5	"	"	S6J	135498	3990
6	"	"	"	135102	4319
7	"	"	S6	135479	4482
8	"	"	S6J	135214	4725
9	Hughes	"	Q/V	28982	4915
10	"	"	"	28313	5000
11	"	"	"	28308	5112
12	Security	"	M4N	132437	5204
13	"	"	"	133238	5270
14	Hughes	"	Q/V	29496	5350
15	"	"	"	25808	5550
16	"	"	"	85346	5625
17	"	"	"	42045	5780
18	"	"	"	28985	5823 TD

T O T C O R E C O R D

<u>Depth Out</u>	<u>Degrees Off</u>
400	1
1716	1
3714	3/4
4884	3/4
5204	3/4
5523	1/2

Christensen Diamond Bit Coring Record

Bit No. A-5968 6 1/8 x 3 1/2"

Core No.	At Seal	From	To	Footage
1		5625	5629	34'
2		5659	5686	27'
3		5785	5808	23'
				84'

# ===== S A M P L E   D E S C R I P T I O N =====

2000 2120 Shale: light gray with white calcareous snecks, traces of fine grain sand.

2120 2340 Shale: light gray shale.

2340 Sample Top Greenhorn

2340 2460 Shale: gray with tan to buff calcareous snecks.

2460 2540 Shale: light gray traces of white limestone.

2540 2700 Shale: light gray with traces of brown sandy shale.

2700 2900 Shale: gray with traces of light gray waxy siltstone; traces of medium grained white sand, no show.

2905 Sample Top Muddy

2900 2980 Sand: medium grained gray, poor permeability and porosity, no show, salt and pepper appearance, dark gray shale.

2980 3110 Shale: dark gray siltstone.

3110 Sample Top Dakota Siltstone

3110 3320 Shale: gray micaceous traces of medium grained sand, no show.

3320 3380 Sand: light gray, hard, tight, fine grained.

3380 3460 Shale: light gray, hard fine grained, gray sand.

3460 3520 Sand: light gray to white hard, tight, fine grained.

3520 3560 Shale: dark gray splintery shale, trace of above sand.

Swift?

3560 3600 Sand: dark gray, glauconitic shale as above, traces of buff colored limestone.

3600 3760 Shale: dark gray to black with stringers of gray glauconitic sand.

3760 3900 Shale: dark gray, traces of above sand.

3900 Sample Top Vanguard

3900 3960 Sand: fine grained, gray, hard, well cemented, fair permeability and porosity, no show; shale as above.

Sample Description Continued

---

3960 4090 Shale: dark gray to black, trace of above sand.

4085 Sample Top Rierdon

4090 4140 Sand: medium trace fine grained, well rounded and cemented; fair permeability and porosity, no show, gray black shale.

4140 4250 Shale: dark gray to black, traces of pyrite and mica, traces of above sand.

4250 Sample Top Piper Shale

4250 4330 Shale: dark gray with trace of red sandy shale.

4330 Sample Top Piper Shale

4330 4400 Limestone: dark gray and buff colored limestone, also a light gray shaley limestone.

4400 Sample Top Gypsum Springs

4400 4590 Shale: light gray traces of red; traces of soft, white anhydrite; some buff colored limestone.

4590 Sample Top Spearfish

4590 4620 Sand: red, shaley with the above sand, light gray shale.

4620 4700 Shale: dark red sandy shale.

4700 Sample Top Amsden

4700 4710 Sand: as above with trace of tan, dense limestone and white dolomite.

4710 4810 Shale: gray and red with stringers of limestone.

4810 4820 Shale: as above with traces of limestone.

4820 Sample Top Heath

4830 4840 Sand: red, hard, dense quartz; no permeability, no show. Circulated out samples 4845. Sample description: Sand: medium grained red and white, poor permeability and porosity, sub angular, no show.

4840 4860 Sand: as above.

4860 4990 Shale: multi-color red, black and grays, traces of the above sand.

4995 Sample Top Otter

Sample Description Continued

4990 5010 Shale: multi-colored with traces of green shale, some white and buff colored limestone.

5010 5060 Shale: as above with increase in limestone.

5060 5170 Limestone: white to buff with trace of permeability and porosity in fine grained limestone, shale as above.

5120 Sample Top Kibbey Sand

5120 5200 Sand: fine to medium, hard, tight, poor to no permeability and porosity, no show.

5200 5230 Shale: multi-colored black and red with stringers of above sand.

5230 5260 Sand: medium grained, fair permeability and porosity, stringers of soft white limestone.

5260 5280 Sand: as above with inter-bedded black massive shale.

5280 Sample Top Kibbey

5280 5300 Limestone: light gray, fine grained to dense white soft, amorphous traces of black marine shale.

5300 5370 Shale: dark gray to black with traces of above limestone.

5375 Sample Top Madison

5370 5420 Anhydrite: soft white, dark gray, dense; traces of gray bedded limestone.

5420 5430 Limestone: dark gray, dense with dense gray anhydrite.

5430 5440 Anhydrite: light gray to white, hard, dense.

5440 5450 Limestone: dark gray, dense, traces of above anhydrite.

5450 5480 Limestone: dark gray to black, finely crystalline with fair intergranular permeability and porosity, spotted golden fluorescence, good celli cut.

5480 5500 Anhydrite: dark gray to white, hard, dense.

5500 5520 Limestone: dark gray to black, fine crystalline; traces of oolitic, fair permeability and porosity, fair golden fluorescence and cut.

5520 5560 Anhydrite and limestone: dark gray, dense limestone, gray to white anhydrite.

5560 5590 Salt Section

Sample Description Continued

5590 5625 Anhydrite: dark gray, dense.  
5625 Core No. 1 5625-5659  
5659 Core No. 2 5659-5686  
5680 5710 Anhydrite: dark gray, dense, stringers of limestone.  
5710 5720 Limestone: dark gray to black, dense with stringers of above  
anhydrite.  
5730 5740 Anhydrite: dark gray, dense.  
5740 5750 Limestone: dark gray to black, dense.  
5750 5785 Anhydrite: dark gray, dense.  
5785 5808 Core No. 3 Cut 23', Recovered 20'.

Location: SW NW Sec. 3-T28N-R51E

Spacing - 160 acres

Elevation: 2069 K.B. - 2049 Gr.

Spudded: 7-2-56

Completed: 7-29-56

D.D.: 5832' Driller - 5823 Schl.

Prod. Zones: A-1 (5456-5474)

## Schlumberger Tops

	Depth	Datum	Thickness
Judith River	----	-----	
Greenhorn	2340	- 271	
Muddy Sd	2904	- 835	
akota Silt	3110	-1041	
Tipper Ls	4340	-2271	
msden	4693	-2624	
Leath	4845	-2776	
atter	4992	-2923	
ibbey Sd	5124	-3055	
ibbey Ls	5280	-3211	
Madison	5375	-3306	
-1	5457	-3388	4'
-2	*5469	-3400	4'
-3	*5489	-3420	17"
-4	*5501	-3432	27"
-1	*5641	-3572	9"
-2	*5659	-3590	17"
-3	*5679	-3610	7"
-4	5712	-3643	6"
-5	5753	-3684	?
-1	*5794	-3725	?
-2	5809	-3740	?

## Coring Intervals:

#1 5625-5659 Rec. 33' B-1

#2 5659-5686 Rec. 30' B-2 &amp; 3

#3 5785-5808 Rec. 20' C-1 &amp; 2

## Drill Stem Tests:

DST #1 5650.5-5659 B-2 w/Hall single pkr test,  $\frac{1}{2}$ " bot cke, no W.C. Tool opnd w/good blo & remained thruout. Tool opn 2 hrs, SI 30 min. Rec. 2051' gas, 273' cln oil, 182' oily muddy s.w. & 1647' salt wtr. Press. IBHFP 112, FBHFP 1745, BHSIP 2988, Hydro 3260.

DST #2 5634-5646 B-1. w/Hall strdl pkr test,  $\frac{1}{2}$ " bot cke, no W.C. Tool opnd w/med blo & remained same thruout test. Tool Opn 2 hrs, SI 20 min. Rec. 546' gas, 30' cln oil, 60' o & g cut mud & 800' s.w. IBHFP 30 FBHFP 1440, BHSIP 2555, Hydro 3260.

DST #3 5669-5686 B-3. Pkr failed when set. Mis-run.

DST #3 re-run 5669-5686 B-3 w/Hall dbl pkrs, bot pkr set at 5669',  $\frac{1}{2}$ " bot cke, no W.C. Tool opnd w/weak blo, incr'd to med blo in 15 min & remained same thruout test. Tool opn 2 hrs, SI 20 min. Rec. 795' s.w., no show of oil. IBHFP 30, FBHFP 385, BHSIP 2935, Hydro 3260.

DST #4 5790.5-5808 C-1. Hall single pkr test,  $\frac{1}{2}$ " bot cke,  $\frac{1}{4}$ " top cke, no W.C. Tool opnd w/good blo & remained same thruout test. Opn 2 hrs, SI 20 min. Rec. 3367' muddy s.w. IBHFP 58, FBHFP 1582, BHSIP 3070, Hydro 3315.

DST #5 5485.5-5496' A-3. w/Hall hookwall test, set strdl pkr,  $\frac{1}{2}$ " bot cke, no W.C. Tool opnd w/weak blo, incr to med blo, after 15 min remained same thruout test. Tool opn 2 hrs, SI 20 min. Rec. 200' gas, 45' cln oil, 45' med-cut oil & 130' s.w. IBHFP 30 FBHFP 112 BHSIP 2990 Hydro 3152.

## History Subsequent to Completion:

None

\*\*Probable prod. Zones (From DST structural position, etc.)

\*Shows

Drill Pipe Corrections (Made)

4480 Driller - 4490 SLM (+10')



OPERATOR

Murphy Corporation

LAB. NO.

2742

PAGE NO.

2

Sample No.	Interval feet	Footage	K Max.	PERMEABILITY, Md.			Total Porosity Per Cent	SATURATION % PORE SPACE		Matrix Density	DESCRIPTION
				K 90°	K Matrix	K Vertical		Residual Oil	Water		
14	5660.4-61.0	0.6	31.1	192		4.3	8.3	Trace	75.9		HF VF
15	5661.0-61.8	0.8	2.0	0.2		0.4	6.4	Trace	100.0		
	5661.8-63.1	1.3	-	-		-	6.4	Trace	100.0		OVF Similar to No. 15
16	5663.1-64.1	1.0	13	6.9		12	16.3	Trace	57.7		
17	5664.1-65.0	0.9	6.4	4.5		5.1	19.7	Trace	47.7		
18	5665.0-66.0	1.0	14	7.6		3.2	13.3	2.3	97.7		
19	5666.0-67.0	1.0	11	9.0		10	16.7	1.0	99.0		
20	5667.0-68.0	1.0	20	7.9		6.2	20.1	Trace	79.6		
21	5668.0-69.0	1.0	13	12		16	16.7	7.2	87.4		
	5669.0-75.0	6.0	-	-		-	-	-	-		Dense
<u>B-3 Zone</u>											
22	5675.0-76.0	1.0	0.7	0.6		0.3	14.1	Trace	85.0		
23	5676.0-77.0	1.0	1.7	1.3		0.4	18.9	Trace	92.1		
24	5677.0-78.0	1.0	1.4	1.2		0.7	16.7	Trace	72.7		
25	5678.0-79.4	1.4	1.1	0.6		0.5	14.5	Trace	89.7		
	5679.4-79.8	0.4	-	-		-	14.5	Trace	89.7		OIF Similar to No. 25
26	5679.8-80.5	0.7	1.2	0.7		0.3	13.5	Trace	26.7		
27	5680.5-81.0	0.5	0.6	0.5		0.3	13.8	Trace	96.4		
	5681.0-89.0	8.0	-	-		-	-	-	-		Anhydrite

SUMMARYProbable ProductionB-1 Zone

5635.5-41.5      6.0      4.1\*      7.9 Trace-14.5      79.2      Water

B-2 Zone

5653.5-58.0      4.5      9.2      14.9      6.3      52.2      Oil & Water  
5659.0-69.0      10.0      31\*      13.8      1.1      83.3      Water

B-3 Zone

5675.0-81.0      6.0      1.2\*      15.4      Trace      79.9      Water

\*Does not include permeability of open fractures. B-1 Zone has 1.8' of open fractures; B-2 Zone 1.3' and B-3 Zone 0.4'. Production tests required to determine type of fluid recovery from fractures. Fractures could lead into oil.

OPERATOR

Murphy Corporation

LAB. NO. 2742

PAGE NO. 3

Sample No.	Interval Feet	Footage	K 90°	PERMEABILITY, Md.		K Vertical	Total Porosity Per Cent	SATURATION % PORE SPACE		Matrix Density	DESCRIPTION
				K Matrix	K Vertical			Residual Oil	Water		

OVF = Open Vertical Fracture (slabs)

VF = Vertical Fracture

V = Vuggy

OIF = Open Inclined Fracture

HF = Horizontal Fracture

CORE DESCRIPTION

by Kent Brouillette

CORE NO. 1 5625-59' Cut 34' Rec. 33'

1' Anhydrite; hard dense dark grey with salt inclusions.

7' Anhydrite, hard dense dark grey. No salt.

B-1 11' Limestone; dark grey brown finely crystalline with good porosity and permeability; good oil odor; spotty to even staining 1½', 2' from top of unit. Hard tight; poor porosity and permeability.

11' Anhydrite; hard dense dark grey.

B-2 4' Limestone; dark grey brown finely crystalline; good oil odor; good fluorescence; fair porosity and permeability.

CORE NO. 2 5659-66' Cut 27' Rec. 30'

B-2 10' Limestone; dark grey brown finely crystalline spotty golden fluorescence. Poor to fair porosity and permeability; sulfur odor at bottom of unit.

6' Limestone; black; lithographic; thinly banded saturation and porosity and permeability.

B-3 5' Dolomite; limey at top becoming more dolomitic with depth; light grey brown earthy; fair oil odor top 3'; spotty fluorescence; poor to fair porosity and permeability.

8' Anhydrite; light grey dense.

SERVICE & TESTING



## WORKOVER HISTORY NO. I

July 15, 1958

Lease and Well No.: East Poolar Unit Well No. 80Field: East Poolar County: Roosevelt State: MontanaWell Location: SW NW Section 3, T28N, R51EStatus Prior to Present Job:Date Completed: July 29, 1958 Date Last Workover: NoneT.D.: 5832' PBTD: 5779' Producing Zone: "A" Zone of MadisonFormation Perforations: 5456'-5474' Cumulative ProductionPresent Zone: 36,479 Bbls. Oil; 27,316 Bbls. Water Latest Test: Pumping68 WPD, 84% Water (11 BOPD, 57 WPD)Justification for Workover: Increase fluid production.Summary of Workover:

- 6-18-58 (First Report of Workover #1 to acidize with 1000 gallons to increase production. Last well test made on June 17, 1958, 24 hour test, 68 WPD, 84% water (11 BOPD, 57 WPD). Acidized "A" Zone (5456'-5474') with 1000 gallons Halliburton HV acid. Spotted acid down casing. Injected 16 bbls acid at rate of .2 BPM at 1400 psi. Injected last 8 bbls acid at rate of 1/2 BPM at 2000 psi. Injection pressure governed by well head equipment. Bleed down pressure 1100 psi. Started well to pumping. Will test today.
- 6-19-58 PBTD 5779'. On a 2 hour test, pumped at the rate of 86 WPD, 37% water (54 BOPD, 32 WPD). Pumping load oil.
- 6-20-58 PBTD 5779'; on a 21 hour test, pumped at rate of 130 WPD, 32% water (88 BOPD, 42 WPD).
- 6-21-58 PBTD 5779'; on a 21 hour test, pumped at rate of 113 WPD, 75% water (28 BOPD, 85 WPD).
- 6-22-58 PBTD 5779'. No test.
- 6-23-58 PBTD 5779'. On a 24 hour test, pumped 106 WPD, 76% water (26 WPD, 80 WPD). This is the workover potential test for the A Zone. To drop from report.

RECEIVED

JUL 18 1958

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA - BILLINGS

Recap of Workover:

1. Final Perforations: 5456'-5474' Unchanged
2. Final P3TD: 5779' Unchanged
3. Initial Potential after Workover: Pumping 106 BPD, 76% Water  
(26 BPD, 80 BPD)
4. Geologic Name of Producing Zone: "A" Zone of Madison Formation
5. Downhole Equipment: Unchanged

Results of Workover: Oil production increased from 11 BPD to 26 BPD, water cut decreased slightly. Workover successful.

RECEIVED

WORKOVER HISTORY NO. 2

APR 17 1959

March 25, 1959

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

Lease and Well Number: East Poplar Unit Well No. 80

Field: East Poplar County: Roosevelt State: Montana

Well Location: SW NE/Section 3, T28N, R51E

Status Prior to Present Job:

Date Completed: July 29, 1956 Date of Last Workover: June 23, 1958

T.D.: 5832' PBTD: 5779' Producing Zone: A Zone of Madison

Formation Perforations: 5456'-5474' Cumulative Production through

December, 1958: 42,254 BO and 40,665 BW Latest Test: March 3, 1959,

pumping 14 BOPD, 47 BWPD.

Justification for Workover: to increase production.

Summary of Workover:

- 3-18-59 PBTD 5779' - Acidized A Zone (5456'-5474') with 3000 gallons HV acid. Spotted acid down casing annulus. Injected acid at the rate of 3 BPM at 2300#. Over-flushed acid with 10 barrels oil. Bleed down pressure 1900#. Left acid on formation 4 hours, then started pumping.
- 3-19-59 PBTD 5779' - No test, will test today.
- 3-20-59 PBTD 5779' - On 4 hour test, pumped at the rate of 106 BFPD, 83% water (18 BOPD, 88 BWPD).
- 3-21-59 PBTD 5779' - On 24 hour test, pumped at the rate of 102 BFPD, 76% water (24 BOPD, 77 BWPD).
- 3-22-59 PBTD 5779' - On 24 hour test, pumped at the rate of 98 BFPD, 71% water (28 BOPD, 70 BWPD).
- 3-23-59 PBTD 5779' - No test.
- 3-24-59 PBTD 5779' - On 3 hour test, pumped at the rate of 108 BFPD, 74% water (28 BOPD, 80 BWPD). This is the Workover Potential, to drop from report.

March 29 =

Recap of Workover:

1. Final Perforations: 5456'-5474' (unchanged)
2. Final PBTD: 5779' (unchanged)
3. Workover Potential: Pumping 108 BFPD, 74% water (28 BOPD, 80 BWPD).
4. Geologic Name of Producing Zone: A Zone of Madison Formation  
(unchanged)
5. Downhole Equipment: Unchanged

Results of Workover: Oil production increased from 14 BPD to 28 BPD and  
water production increased from 47 BPD to 80 BPD. Workover Successful.

RECEIVED

APR 17 1959

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MISSISSIPPI

WORKOVER HISTORY NO. 3

December 27, 1963

WELL LEASE AND NUMBER: East Poplar Unit Well No. 30

FIELD: East Poplar Unit COUNTY: Roosevelt STATE: Montana

WELL LOCATION: SW NW Section 3, T28N, R51E

STATUS PRIOR TO PRESENT JOB:

Date Completed: July 29, 1956 Date of Last Workover: April 29, 1960

T.D.: 5832' FBTD: 5779' Producing Zone: A-1 & A-2 of Madison Formation

Perforations: 5456-5474 & 5492' Cumulative Production of Present Zone: 48,160 BC

67,500 BW Latest Test: Shut in and depleted

JUSTIFICATION FOR WORKOVER: To prepare for Salt Water Disposal

SUMMARY OF WORKOVER:

- 11-27-63 FBTD 3575' - Rigged up pulling unit and layed down 5483' of 2-1/8" reg. Ran J.B. & G.2. on Wireline to 5300'. Ran Baker Model "K" C.I. bridge plug on Wireline and set at 3300'. Dumped one sack cement on top of bridge plug using dump bailer. Perforated 3595' to 3596' with 4 shots per ft. Set Baker Model "K" cmt. retainer on Wireline at 3575'. Shut in overnight.
- 12-23-63 FBTD 3575' - Ran 3575' of 2-7/8" tubing string into Model "K" cmt. retainer at 3596', broke circulations outside of 5-1/2" casing with 1800# at the rate of 6 BPH. Circulated out mud and shut down overnight waiting on cement.
- 12-29-63 FBTD 3575' - Cemented 5-1/2" casing with 360 sacks 1 to 1 pozzin with 8% gel tailed in with 100 sacks 1 to 1 pozzin 2% gel displaced cement through Model "K" cmt. retainer at 3575' out perf. at 3596'. Full returns out surface casing while cementing. Maximum pressure 3000#. Released pressure. Back pressure valve would not hold. Circulated out under pressure. Caught cement plug. Shut in overnight.
- 12-30-63 FBTD 3575' - Tested cement job, would not hold. Pumping into formation with 800# at the rate of 1 BPH. Shut down overnight waiting on HOWCO pump truck to test to determine if hole will circulate and recement.



### SUMMARY OF WORKOVER CONTINUED:

- 12-31-63 PSTD 3575' - Broke formation through perf. at 3595' with approximately 75 bbls. water, did not circulate. Pumped into formation at the rate of 5 BPM, 1800# pressure. Cemented with 150 sacks regular cement with 100# Halida #9 added. Pumped into formation at 1800#, stopped pump and pressure dropped to 1400# immediately and slowly bled to 1000# and stabilized. Shut in overnite.
- 1-01-64 PSTD 3575' - Tested cmt. job to 2000#, held. Wireline perforated with 4 shots per foot from 3218' to 3250'. Formation broke down at 2000#. Injected 256 bbls. water at the rate of 10 BPM and 2400 PSI. Made run with dummy gun, could not get below 3525' because of cmt. in casing. Wireline perforated with 4 shots per foot from 3462' to 3512' and 3284' to 3410'. Set packer at 3275' and broke formation down at 2000 PSI. Injected 100 bbls. water at the rate of 3 BPM and 2800 PSI. Dropped 100 ECM balls and injected 143 bbls. at the rate of 8 BPM and 2900 PSI. Dropped 25 ECM balls, injected 190 bbls. at the rate of 8 BPM and 2900 PSI. Dropped 25 ECM balls and injected 271 bbls. at the rate of 8 BPM and 2900 PSI. Reset packer and pumped into perforation 3462'-3512'. Injected a total of 120 bbls. water at the rate of 8 BPM and 3050 PSI. 7 BPM and 3000 PSI, 5 BPM and 2800 PSI, and 3 BPM and 2200 PSI. Reset packer at 3197' and injected into all perforations 50 bbls. at the rate of 9 1/2 BPM and 2400 PSI, 100 bbls. at 7 BPM and 1900 PSI, 150 bbls. at 4 1/2 BPM and 1500 PSI and 120 bbls at 3 BPM and 1200 PSI. Instant shut in pressure 1000 PSI. 5 min. bleed down 800 PSI. Shut well in over holidays. (Perforated with wireline through tubing gun.)
- 1-02-64 PSTD 3575' - Ran tubing with Larkin Neoseal Rock Wall Packer. Packer would not set. Came out of hole with tubing. Packer rubber damaged and slips were dull. Shut in overnite.
- 1-03-64 PSTD 3575' - Ran 93 jts. 3-1/2" Tube Cote Tubing with Baker Model "E" Packer with 2" bore. Circulated annulus with 59 bbls. of fresh water with 15 gal. of inhibitor added and 2 bbls. oil on top. Set Packer at 2934'. To Drop From Report.
- 1-13-64 PSTD 3575' - Station started in operation January 9, 1964, with 3000# pressure. Pressure dropped to 400# by Friday, January 10, 1964. Injecting at the rate of 3.7 BPM (5328 LFD) and maintaining 390# pressure. TO DROP FROM REPORT.

### RECAP OF WORKOVER:

1. Final Perforations: 3218'-3250', 3462'-3512', 3284'-3410'
2. Final PSTD: 3575'
3. Geologic Name: EPU #80-D Salt Water Disposal (DAXOTA SAND)

WORKOVER HISTORY NO. 3

RECEIVED

April 29, 1960 MAY 16 1960

Lease and Well Number: East Poplar Unit Well No. 80

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

Field: East Poplar County: Roosevelt State: Montana

Well Location: SW NW Section 3, T28N, R51E

Status Prior to Present Job:

Date Completed: July 29, 1956 Date of Last Workover: March 24, 1959

T.D.: 5832 PBTD: 5779 Producing Zone: A zone of Madison Formation

Perforations: 5456-5474 Cumulative Production 47,764 BO, 56,391 BW

Latest Test: Pumping 4 BOPD, 34 BWPD

Justification for Workover: Present production uneconomical.

Summary of Workover:

- 4-11-60 PBTD 5779'. Rigged up pulling unit & pulled rods and tubing. Ran tubing with collar locator and abrasive jet. Picked collars on short joint of casing at 5645' and 5621'. Tubing measurements were .48' deeper. Zeroed in on casing collars. Installed well head and shut in overnight.
- 4-12-60 PBTD 5779'. Perforated A zone 5492' with Dowell Abrasive jet- cut 2 notches 3" wide. Made trip with tubing to remove abrasive jet and pick up company owned lane wells packer. Packer failed. Made trip to pick up Baker full bore packer to swab test.
- 4-13-60 PBTD 5779'. Ran tubing with Baker full bore packer. Set packer at 5480' and swabbed A zone perforations 5492'. Swabbed dry with show of oil. Acidized A zone perforations 5492' with 500 gallons Dowell etching acid. Pressured up to 3000# and let acid soak, keeping pressure built to 3000#. Injected 2.5 barrels acid in 2 hours. Increased pressure to 3900#. Formation broke back to 1600# with 5 barrels acid in formation. Injected remainder of acid at rate of  $\frac{1}{2}$  BPM at 1600#. Opened to pit, flowed 1" stream. Swabbed 1 hour. Recovered salt water, spent acid and oil. Water cut at end of swabbing 60% water. Fluid level standing 2000#feet from top.
- 4-14-60 PBTD 5779'. Made trip with tubing to remove packer. Ran 2" x 1 3/4" x 15' tubing liner pump spaced at 3500'. Fluid entry 5500'. Started pumping at 1-15 p.m., April 14, 1960. Water cut 99%.
- 4-15-60 PBTD 5779'. Pumping on 44" stroke, 15 SPM, 3 hr. test. Pumped 260 BFPD 100% water.
- 4-16-60 PBTD 5779'. Pumping on 64" stroke, 15 SPM, pumped 292 BFPD, 100% water.
- 4-17-60 PBTD 5779'. Pumped at rate of 315 BFPD, 100% water.

- 4-18-60 PBTD 5779'. Pumping at rate of 319 BFPD, 98 % water. (313 BWPD, 6 BOPD).
- 4-19-60 PBTD 5779'. Pumping, no test. Water cut 90%.
- 4-20-60 PBTD 5779'. Pumping, 3 hr. test. Pumped at rate of 325 BFPD, 95 % water. (16 BOPD, 309 BWPD).
- 4-21-60 PBTD 5779'. Pumping 381 BFPD, 98% water. (8 BOPD, 373 BWPD).
- 4-22-60 PBTD 5779'. Pumping, no test. 98% water.
- 4-23-60 PBTD 5779'. Pumping, 4 hr. test. Pumped at rate of 390 BFPD, 95 % water. (20 BOPD, 370 BWPD).
- 4-24-60 PBTD 5779'. Pumping, no test.
- 4-25-60 PBTD 5779'. Pumping, 4 hr. test. Pumped at rate of 365 BFPD, 97% water. (11 BOPD, 354 BWPD).
- 4-26-60 PBTD 5779'. Pumping, no test.
- 4-27-60 PBTD 5779'. Water draw test, 368 BFPD, 98% water. (7 BOPD, 361 BWPD).  
This is the A zone potential test. To Drop from Report.

Recap of Workover:

1. Final Perforations: 5456-5474; and 5492
2. Final PBTD 5779'. (unchanged)
3. Workover Potential: Pumping 7 BOPD, 361 BWPD.
4. Geologic name of Producing zone: A zone of Madison formation.
5. Downhole equipment: Unchanged

Results of Workover:

Oil production increased from 4 BOPD to 7 BOPD. Water production increased from 34 BWPD to 361 BWPD. Workover unsuccessful.

RECEIVED

MAY 16 1960

OIL AND GAS CONSERVATION COMMISSION  
OF THE STATE OF MONTANA

WORKOVER HISTORY NO. 2

December 27, 1963

WELL LEASE AND NUMBER: East Poplar Unit Well No. 80

FIELD: East Poplar Unit COUNTY: Roosevelt STATE: Montana

WELL LOCATION: SW NW Section 3, T28N, R51E

STATUS PRIOR TO PRESENT JOB:

Date Completed: July 29, 1955 Date of Last Workover: April 29, 1960

T.D. : 5832' PBTD: 5779' Producing Zone: A-1 & A-3 of Madison Formation

Perforations: 5456-5474 & 5492' Cumulative Production of Present Zone: 48,169 BO

67,500 BW Latest Test: Shut in and depleted

JUSTIFICATION FOR WORKOVER: To prepare for Salt Water Disposal

SUMMARY OF WORKOVER:

- 12-27-63 PBTD 3575' - Rigged up pulling unit and layed down 5483' of 2-3/8" tbg. Ran J.B. & G.R. on Wireline to 5300'. Ran Baker Model "K" C.I. bridge plug on Wireline and set at 5300'. Dumped one sack cmt. on top of bridge plug using dump bailer. Perforated 3595' to 3596' with 4 shots per ft. Set Baker Model "K" cmt. retainer on Wireline at 3575'. Shut in overnite.
- 12-28-63 PBTD 3575' - Ran 3575' of 2-7/8" tubing stung into Model "K" cmt. retainer at 3596', broke circulations outside of 5-1/2" casing with 1800# at the rate of 6 BPM. Circulated out mud and shut down overnite waiting on cement.
- 12-29-63 PBTD 3575' - Cemented 5-1/2" casing with 360 sacks 1 to 1 pozmix with 8% gel tailed in with 100 sacks 1 to 1 pozmix 2% gel displaced cement through Model "K" cmt. retainer at 3575' out perf. at 3596'. Full returns out surface casing while cementing. Maximum pressure 3000#. Released pressure. Back pressure valve would not hold. Circulated out under pressure. Caught cement flag. Shut in overnite.
- 12-30-63 PBTD 3575' - Tested cement job, would not hold. Pumping into formation with 800# at the rate of 1 BPM. Shut down overnite waiting on HOWCO pump truck to test to determine if hole will circulate and recement.

SUMMARY OF WORKOVER CONTINUED:

- 12-31-63 PSTD 3575' - Broke formation through perf. at 3595' with approximately 75 bbls. water, did not circulate. Pumped into formation at the rate of 5 BPM, 1800# pressure. Cemented with 150 sacks regular cement with 100# Halide #9 added. Pumped into formation at 1800#, stopped pump and pressure dropped to 1400# immediately and slowly bled to 1000# and stabilized. Shut in overnite.
- 1-01-64 PSTD 3575' - Tested cmt. job to 2000#, held. Wireline perforated with 4 shots per foot from 3218' to 3250'. Formation broke down at 2000#. Injected 256 bbls. water at the rate of 10 BPM and 2400 PSI. Made run with dummy gun, could not get below 3525' because of cmt. in casing. Wireline perforated with 4 shots per foot from 3462' to 3512' and 3284' to 3410'. Set packer at 3275' and broke formation down at 2000 PSI. Injected 100 bbls. water at the rate of 8 BPM and 2800 PSI. Dropped 100 RON balls and injected 143 bbls. at the rate of 8 BPM and 2900 PSI. Dropped 25 RON balls, injected 190 bbls. at the rate of 8 BPM and 2900 PSI. Dropped 25 RON balls and injected 271 bbls. at the rate of 8 BPM and 2900 PSI. Reset packer and pumped into perforation 3462'-3512'. Injected a total of 120 bbls. water at the rate of 8 BPM and 3050 PSI. 7 BPM and 3000 PSI, 5 BPM and 2800 PSI, and 3 BPM and 2200 PSI. Reset packer at 3197' and injected into all perforations 50 bbls. at the rate of 9½ BPM and 2400 PSI, 100 bbls. at 7 BPM and 1900 PSI, 150 bbls. at 4½ BPM and 1500 PSI and 180 bbls at 3 BPM and 1200 PSI. Instant shut in pressure 1000 PSI. 5 min. bleed down 800 PSI. Shut well in over holidays. (Perforated with wireline through tubing gun.)
- 1-02-64 PSTD 3575' - Ran tubing with Larkin Neoseal Hook Wall Packer. Packer would not set. Came out of hole with tubing. Packer rubber damaged and slips were dull. Shut in overnite.
- 1-03-64 PSTD 3575' - Ran 93 jts. 3-1/2" Tube Cote Tubing with Baker Model "R" Packer with 2" bore. Circulated annulus with 39 bbls. of fresh water with 15 gal. of inhibitor added and 2 bbls. oil on top. Set Packer at 2934'. To Drop From Report.
- 1-13-64 PSTD 3575' - Station started in operation January 9, 1964, with 800# pressure. Pressure dropped to 400# by Friday, January 10, 1964. Injecting at the rate of 3.7 BPM (5328 BPD) and maintaining 390# pressure. TO DROP FROM REPORT.

RECAP OF WORKOVER:

1. Final Perforations: 3218'-3250', 3462'-3512', 3284'-3410'
2. Final PSTD: 3575'
3. Geologic Name: EPU #80-D Salt Water Disposal (TAKOTA SAND)

# ARROW OIL TOOLS, Inc.

P.O. Drawer 7649 / Tulsa, Oklahoma 74105 / Telephone: (918) 445-0411 / Outside Oklahoma Wats: 1-800-331-4042



*run in hole*

## ARROWSET I PACKER

Combines advantages of mechanically-set retrievable packer and permanent packer.

Arrow's Arrowset I Single-String Retrievable Production Packer effectively meets several zone isolation, production, and injection requirements. Full opening design gives unrestricted flow and allows wireline tools to pass. Mechanical lock-setting action holds substantial pressures from above or below without tubing weight or tension. No hydraulic anchor is required to prevent packer movement, even with high differential pressures.

Packer's ability to absorb tubing expansion or con-

traction forces makes the Arrowset I right for both pumping and injection wells.

After packer is set, tubing can be left in tension, compression, or neutral.

Large internal bypass reduces swabbing effect when running or retrieving. When packer is set, bypass is automatically sealed and closed.

When the Arrowset I Packer is run with the Arrow On/Off Tool, tubing can be pulled without disturbing packer.

SPECIFICATIONS — ARROWSET I PACKER

CASING		CASING I.D. RANGE		MAX. O.O. OF TOOL	PACKER BORE	THREAD SPECIFICATION BOX UP & PIN DOWN
O.D.	WEIGHT LBS./FT.	MINIMUM	MAXIMUM			
2 1/4"	6.4-6.5	2.375	2.469	2.250	.625	1.050 EU 10 Rd
4	9.5-11.0	3.406	3.548	3.250	1.500	1.900 EU 10 Rd
4 1/2	15.1-16.6	3.719	3.844	3.562		
	9.5-13.5	3.900	4.090	3.750		
5	24.2				1.938	
	15.0-20.8	4.156	4.469	4.000		2.375 EU 8 Rd
	11.5-15.0	4.312	4.562	4.125		
5 1/2	20.0-23.0	4.656	4.858	4.500	2.000	
	14.0-17.0	4.812	5.094	4.625	2.375	
			5.031			
6 1/4	24.0-32.0					
7	38.0	5.656	5.937	5.500		
6 3/4	20.0	5.969	6.219	5.812		
	28.0-35.0				2.500	2.875 EU 8 Rd
7	17.0-32.0	6.031		5.875		
	17.0-26.0	6.219	6.538	6.000		
7 1/4	45.3	6.625	7.031	6.453		
	24.0-39.0					
8 1/4	40.0-49.0	7.469	7.775	7.250		
				7.312	4.000	4.500 EU 8 Rd
	28.0-40.0	7.719	8.031	7.500	2.500	2.875 EU 8 Rd
				7.531		
9 1/4	43.5-53.5	8.469	8.781	8.250		
	32.3-43.5	8.719	9.031	8.500	4.000	4.500 EU 8 Rd
10 1/4	71.1-81.0	9.219	9.469	9.000		
	51.0-65.7	9.531	9.875	9.312		
	32.7-45.5	9.906	10.219	9.687		

\*29-32# CASING REQUIRES SPECIAL PACKING ELEMENTS

*run in hole*  
*to set pick up turn to right 1/4 come down*  
*to release find Free point turn Right & pick up*  
*set down 5 to 6000' & turn to right 1/4 turn*  
*all torque & pull up*

*To set pick up turn to Right 1/4 come down*  
*to release find Free point turn Right & pick up*  
*set down 5 to 6000' & turn to right 1/4 turn*  
*all torque & pull up*

Downhole Water Analysis  
Copyright 1991, 1993, Nalco Chemical Company

12/27/1993  
Max A. Jensen

CLIENT NAME : Murphy Exploration & Production  
CLIENT LOCATION: Poplar, Montana

Well Number : EPU 80D SWD Water Analysis

Page 2

>>> Scaling Indices <<<

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60.0	-1.07	-51.85	NA	NA
80.0	-0.87	-52.17	NA	NA
100.0	-0.63	-52.26	NA	NA
120.0	-0.35	-51.68	NA	NA
140.0	-0.03	-50.97	NA	NA
160.0	0.34	-49.79	NA	NA
180.0	0.75	-48.81	NA	NA
200.0	1.20	NA	NA	NA
220.0	NA	NA	NA	NA
240.0	NA	NA	NA	NA
260.0	NA	NA	NA	NA
280.0	NA	NA	NA	NA
300.0	NA	NA	NA	NA
320.0	NA	NA	NA	NA

Positive values indicate scaling tendencies

CLIENT NAME : Murphy Exploration & Production  
CLIENT LOCATION: Poplar, Montana

Well Number : EPU 80D SWD Water Analysis

Page 1

DISSOLVED SOLIDS

Cations	mg/l	meq/l		mg/l
Sodium Na+	48719.4	2118.2	as NaCL	0.0
Calcium Ca++	2002.2	99.9	as CaCO3	5000.0
Magnesium Mg++	485.7	40.0	as CaCO3	2000.0
Barium Ba++	0.0	0.0	as CaCO3	0.0
Strontium Sr++	0.0	0.0	as CaCO3	0.0
Total Cations	51207.3	2258.1		
Anions	mg/l	meq/l		mg/l
Chloride Cl-	79467.9	2241.5	as NaCL	131000.0
Sulfate SO4=	432.8	9.0	as Na2SO4	640.0
Carbonate CO3=	0.0	0.0	as CaCO3	0.0
Bicarb. HCO3-	463.2	7.6	as CaCO3	380.0
Total Anions	80363.9	2258.1		
Total Solids	131571.2			

METALS

Total Iron, Fe	5.0	as Fe	5.0
Acid to Phen, CO2	118.8	as CaCO3	270.0

OTHER PROPERTIES

pH	5.9
Specific Gravity	1.1
Turbidity jtu	0.0
Oxygen, as O2 ppm	0.0
Sulfide as H2S ppm	0.0
Temperature F	60.0

max a. j.  
12/27/93



CLIENT NAME : MURPHY EXPL. & PROD. CO.  
CLIENT LOCATION: POPLAR MT

Well Number : EPU 80D  
Water Source : 12-13-94

Page 2

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60.0	-1.93	-96.08	NA	NA
80.0	-1.73	-96.48	NA	NA
100.0	-1.49	-96.54	NA	NA
120.0	-1.21	-95.61	NA	NA
140.0	-0.88	-94.89	NA	NA
160.0	-0.51	-93.71	NA	NA
180.0	-0.09	-92.75	NA	NA
200.0	0.37	NA	NA	NA
220.0	NA	NA	NA	NA
240.0	NA	NA	NA	NA
260.0	NA	NA	NA	NA
280.0	NA	NA	NA	NA
300.0	NA	NA	NA	NA
320.0	NA	NA	NA	NA

Positive values indicate scaling tendencies

CLIENT NAME : MURPHY EXPL. & PROD. CO.  
CLIENT LOCATION: POPLAR MT

Well Number : EPU 80D  
Water Source : 12-13-94

Page 1

DISSOLVED SOLIDS

Cations	mg/l	meq/l		mg/l
Sodium Na+	70021.0	3044.4	as NaCL	0.0
Calcium Ca++	240.3	12.0	as CaCO3	600.0
Magnesium Mg++	121.4	10.0	as CaCO3	500.0
Barium Ba++	0.0	0.0	as CaCO3	0.0
Strontium Sr++	0.0	0.0	as CaCO3	0.0
Total Cations	70382.7	3066.4		
Anions	mg/l	meq/l		mg/l
Chloride Cl-	107979.3	3045.7	as NaCL	178000.0
Sulfate SO4=	608.6	12.7	as Na2SO4	900.0
Carbonate CO3=	0.0	0.0	as CaCO3	0.0
Bicarb. HCO3-	487.6	8.0	as CaCO3	400.0
Total Anions	109075.5	3066.4		
Total Solids	179458.2			

METALS

Total Iron,Fe	2.5	as Fe	2.5
Acid to Phen,CO2	77.0	as CaCO3	175.0

OTHER PROPERTIES

pH	5.9
Specific Gravity	1.1
Turbidity jtu	0.0
Oxygen, as O2 ppm	0.0
Sulfide as H2S ppm	0.0
Temperature F	100.0

>>> Scaling Indices <<<

Downhole Water Analysis  
Copyright 1991-1995, Nalco Chemical Company

1/5/96  
DON S. WHISONANT

CLIENT NAME : MURPHY EXPLORATION AND PRODUCTION  
CLIENT LOCATION: POPLAR MT

Well Number : EPU 80D PRODUCED ✓  
Water Source : NOV 14, 1995 SAMPLE

DISSOLVED SOLIDS

Cations	mg/l	meq/l		mg/l
Sodium Na+	68787.4	2990.8	as NaCL	0.0
Calcium Ca++	240.3	12.0	as CaCO3	600.0
Magnesium Mg++	121.4	10.0	as CaCO3	500.0
Barium Ba++	0.0	0.0	as CaCO3	0.0
Strontium Sr++	0.0	0.0	as CaCO3	0.0
Total Cations	69149.1	3012.7		
Anions	mg/l	meq/l		mg/l
Chloride Cl-	106159.4	2994.4	as NaCL	175000.0
Sulfate SO4=	574.8	12.0	as Na2SO4	850.0
Carbonate CO3=	0.0	0.0	as CaCO3	0.0
Bicarb. HCO3-	390.1	6.4	as CaCO3	320.0
Total Anions	107124.3	3012.7		
Total Solids	176273.4			

METALS

Total Iron, Fe	2.5	as Fe	2.5
Acid to Phen, CO2	35.2	as CaCO3	80.0

OTHER PROPERTIES

pH	5.9
Specific Gravity	1.0
Turbidity jtu	0.0
Oxygen, as O2 ppm	0.0
Sulfide as H2S ppm	50.0
Temperature F	130.0

*Don S. Whisonant*

>>> Scaling Indices <<<

Downhole Water Analysis  
Copyright 1991-1995, Nalco Chemical Company

12/13/96  
Don Whisonant

CLIENT NAME : Murphy Exploration and Production  
CLIENT LOCATION: Poplar, MT

Well Number : EPU 80D produced water  
Water Source : 12-13-96

DISSOLVED SOLIDS

Cations	mg/l	meq/l	mg/l
Sodium Na+	62835.9	2732.0	as NaCL 0.0
Calcium Ca++	268.3	13.4	as CaCO3 670.0
Magnesium Mg++	121.4	10.0	as CaCO3 500.0
Barium Ba++	0.0	0.0	as CaCO3 0.0
Strontium Sr++	0.0	0.0	as CaCO3 0.0
Total Cations	63225.6	2755.4	

Anions	mg/l	meq/l	mg/l
Chloride Cl-	97060.0	2737.7	as NaCL 160000.0
Sulfate SO4=	541.0	11.3	as Na2SO4 800.0
Carbonate CO3=	0.0	0.0	as CaCO3 0.0
Bicarb. HCO3-	390.1	6.4	as CaCO3 320.0
Total Anions	97991.1	2755.4	

Total Solids 161216.7

METALS

Total Iron, Fe	2.5	as Fe	2.5
Acid to Phen, CO2	35.2	as CaCO3	80.0

OTHER PROPERTIES

pH	5.8
Specific Gravity	1.0
Turbidity jtu	0.0
Oxygen, as O2 ppm	0.0
Sulfide as H2S ppm	50.0
Temperature F	70.0

>>> Scaling Indices <<<

# WATER ANALYSIS REPORT

Company : Murphy Oil Co.  
 Address : Poplar, Mt.  
 Lease : 80-D  
 Well : 80-D S.W.D.  
 Sample Pt. : Pump

Date : 12-19-97  
 Date Sampled : 12-18-97  
 Analysis No. : 2

ANALYSIS		mg/L		* meq/L
1. pH	7.0			
2. H2S	Pos.			
3. Specific Gravity	1.100			
4. Total Dissolved Solids		140694.1		
5. Suspended Solids		clear		
6. Dissolved Oxygen		.5 ppm		
7. Dissolved CO2		500		
8. Oil In Water				
9. Phenolphthalein Alkalinity (CaCO3)				
10. Methyl Orange Alkalinity (CaCO3)				
11. Bicarbonate	HCO3	195.0	HCO3	3.2
12. Chloride	Cl	85080.0	Cl	2400.0
13. Sulfate	SO4	900.0	SO4	18.7
14. Calcium	Ca	4752.0	Ca	237.1
15. Magnesium	Mg	518.1	Mg	42.6
16. Sodium (calculated)	Na	49249.0	Na	2142.2
17. Iron	Fe	0.1		
18. Barium	Ba	0.0		
19. Strontium	Sr	0.0		
20. Total Hardness (CaCO3)		14000.0		

## PROBABLE MINERAL COMPOSITION


*milli equivalents per Liter	Compound	Equiv wt	X meq/L	= mg/L
237 *Ca <----- *HCO3	Ca(HCO3)2	81.0	3.2	259
----- /----->	CaSO4	68.1	18.7	1276
43 *Mg -----> *SO4	CaCl2	55.5	215.2	11941
----- <----- /	Mg(HCO3)2	73.2		
2142 *Na -----> *Cl	MgSO4	60.2		
----- +----->	MgCl2	47.6	42.6	2029
Saturation Values Dist. Water 20 C	NaHCO3	84.0		
CaCO3 13 mg/L	Na2SO4	71.0		
CaSO4 * 2H2O 2090 mg/L	NaCl	58.4	2142.2	125190
BaSO4 2.4 mg/L				

REMARKS:

Petrolite Oilfield Chemicals Group

Respectfully submitted,  
 Ken Kolstad

*Ken Kolstad*



A Baker Hughes company

# SCALE TENDENCY REPORT

Company : Murphy Oil Co. Date : 12-19-97  
Address : Poplar, Mt. Date Sampled : 12-18-97  
Lease : 80-D Analysis No. : 2  
Well : 80-D S.W.D. Analyst : Ken Kolstad  
Sample Pt. : Pump

## STABILITY INDEX CALCULATIONS (Stiff-Davis Method) CaCO3 Scaling Tendency

S.I. = 0.9 at 120 deg. F or 49 deg. C  
S.I. = 0.9 at 140 deg. F or 60 deg. C  
S.I. = 1.0 at 160 deg. F or 71 deg. C  
S.I. = 1.1 at 180 deg. F or 82 deg. C  
S.I. = 1.2 at 200 deg. F or 93 deg. C

\*\*\*\*\*

## CALCIUM SULFATE SCALING TENDENCY CALCULATIONS (Skillman-McDonald-Stiff Method) Calcium Sulfate


S = 3423 at 120 deg. F or 49 deg C  
S = 3483 at 140 deg. F or 60 deg C  
S = 3447 at 160 deg. F or 71 deg C  
S = 3399 at 180 deg. F or 82 deg C  
S = 3307 at 200 deg. F or 93 deg C

Petrolite Oilfield Chemicals Group

Respectfully submitted,  
Ken Kolstad



A Baker Hughes company



# WATER ANALYSIS REPORT

Company : Murphy Oil Co.  
Address : Poplar, Mt.  
Lease : S.W.D.  
Well : 80-D  
Sample Pt. : Pump

Date : 1/5/99  
Date Sampled : 1/4/99  
Analysis No. : 1

ANALYSIS	mg/L	* meq/L
1. pH	7.2	
2. H2S	pos.	
3. Specific Gravity	1.075	
4. Total Dissolved Solids	127561.5	
5. Suspended Solids		
6. Dissolved Oxygen	.1	
7. Dissolved CO2	450	
8. Oil In Water	trace	
9. Phenolphthalein Alkalinity (CaCO3)		
10. Methyl Orange Alkalinity (CaCO3)		
11. Bicarbonate	HCO3 317.0	HCO3 5.2
12. Chloride	Cl 76680.0	Cl 2163.0
13. Sulfate	SO4 1350.0	SO4 28.1
14. Calcium	Ca 3240.0	Ca 161.7
15. Magnesium	Mg 980.0	Mg 80.6
16. Sodium (calculated)	Na 44923.7	Na 1954.1
17. Iron	Fe 0.8	
18. Barium	Ba 0.0	
19. Strontium	Sr 70.0	
20. Total Hardness (CaCO3)	11000.0	

## PROBABLE MINERAL COMPOSITION


*milli equivalents per Liter	Compound	Equiv wt X meq/L	= mg/
+-----+	+-----+	+-----+	+-----+
162  *Ca <----- *HCO3	5  Ca (HCO3)2	81.0	5.2 421
-----  /----->	-----  CaSO4	68.1	28.1 1913
81  *Mg -----> *SO4	28  CaCl2	55.5	128.4 7123
-----  <-----/	-----  Mg (HCO3)2	73.2	
1954  *Na -----> *Cl	2163  MgSO4	60.2	
+-----+	+-----+	+-----+	+-----+
Saturation Values Dist. Water 20 C	MgCl2	47.6	80.6 3838
CaCO3 13 mg/L	NaHCO3	84.0	
CaSO4 * 2H2O 2090 mg/L	Na2SO4	71.0	
BaSO4 2.4 mg/L	NaCl	58.4	1954.1 114195

Baker Petrolite Chemicals Group

Respectfully submitted,

Tom Willer

*Tom Willer*





(Deg. F)	Carbonate	Sulfate	Sulfate	Sulfate
60.0	-1.97	-92.38	NA	NA
80.0	-1.78	-92.75	NA	NA
100.0	-1.54	-92.80	NA	NA
120.0	-1.25	-91.88	NA	NA
140.0	-0.92	-91.22	NA	NA
160.0	-0.55	-90.13	NA	NA
180.0	-0.13	-89.24	NA	NA
200.0	0.33	NA	NA	NA
220.0	NA	NA	NA	NA
240.0	NA	NA	NA	NA
260.0	NA	NA	NA	NA
280.0	NA	NA	NA	NA
300.0	NA	NA	NA	NA
320.0	NA	NA	NA	NA

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60.0	-2.06	-89.18	NA	NA
80.0	-1.86	-89.54	NA	NA
100.0	-1.62	-89.62	NA	NA
120.0	-1.34	-88.80	NA	NA
140.0	-1.01	-88.08	NA	NA
160.0	-0.64	-86.89	NA	NA
180.0	-0.23	-85.92	NA	NA
200.0	0.23	NA	NA	NA
220.0	NA	NA	NA	NA
240.0	NA	NA	NA	NA
260.0	NA	NA	NA	NA
280.0	NA	NA	NA	NA
300.0	NA	NA	NA	NA
320.0	NA	NA	NA	NA

Positive values indicate scaling tendencies

BUD'S TANK CO.  
TANK SPECIALISTS  
MIDLAND - DOWNEY

# BUD'S TANK COMPANY

QUOTATION 249

683-3612

MIDLAND, TEXAS 79701

BOX 1103

Date NOVEMBER 28, 1969

QUIRY: VERBAL  
MURPHY OIL CORPORATION  
P.O. BOX 547  
ROPLAR, MONTANA

DELIVERY: TWO (2) WEEKS  
TERMS: NET 30 DAYS

ATTENTION: MR. M.T. JAMES

REPLY TO: BUD MC SPADDEN  
MIDLAND, TEXAS  
915-563-1574

We are pleased to quote as follows:

QTY	QUAN	DESCRIPTION	PRICE
1	1	L-500 BEL 20" X 10" USED OPEN TOP REDWOOD TANK COMPLETE WITH THE FOLLOWING COMPONENTS:  A.) COARSE SUNDECK WITH SUPPORTS ( SINGLE COARSE) B.) ALL FLANGES NECESSARY FOR YOUR OPERATIONS C.) 3" THICK STAVES D.) 2" THICK BOTTOM  ALL THE ABOVE EQUIPMENT DELIVERED AND ERECTED ON YOUR PREPARED LOCATION  NET SELLING PRICE.....	\$ 3,500.00

NOTE:  
FOR A DOUBLE HEADED TANK ADD \$ 350.00

Yours very truly

BUD'S TANK COMPANY

*Bud McSpadden*


BUD MC SPADDEN

## GUARANTEE

Bud's Tank Company guarantees its products against defective workmanship and material for one year from date of invoice and when owned by original purchaser. Any article not manufactured by the Bud's Tank Company which is included in any proposal is sold under such warranties only as makers give us and we are able to enforce. Our liability for damages caused by defective workmanship or material shall be limited to repairing or replacing the defective part or parts, and no allowance will be granted for repairs or alterations made by the purchaser without the seller's written consent. Bud's Tank Company shall not be liable for indirect or consequential damages of any nature or due to any cause.









B&amp;S Code:

Job No.

Signature of Customer or Authorized Agent (also required on reverse)

Signature of Customer/Agent: X

**CUSTOMERS COPY**



# FRACTURING SERVICE TREATING REPORT

HALLIBURTON  
COMPANY

Halliburton District Glendive  
Halliburton Division Denver

Attach To Ticket No. FS-143934

Stage No. 1

Page No. 1

Field East Poplar Sec. Twp. Rng. County Roosevelt State Montana

THE FOLLOWING INFORMATION WAS FURNISHED BY THE WELL OWNER OR HIS AGENT:

Date Completed <u>1956</u>	Formation <u>Dakota</u>	Prev. Treat: Date _____ Type _____
Casing: OD <u>5 1/2</u> Wt. <u>15.50</u> Depth <u>3535</u>		Fluid: Gal. _____ Sand: Lb. _____
Liner: OD <u>3 1/8</u> From _____ To _____		Pres. Treat: Interval: From <u>3218</u> To <u>3512</u>
Perf.: From <u>3218</u> To <u>3250</u> Shots/Ft. <u>4</u>		Tubing: Size <u>2 7/8"</u> Depth _____
Perf.: From <u>3284</u> To <u>3410</u> Shots/Ft. <u>4</u>		Packer: Type <u>RTTS</u> Set at _____
Perf.: From <u>3462</u> To <u>3512</u> Shots/Ft. <u>4</u>		Max. Allowable Pres.: PSI: Tubing <u>5000</u> Casing <u>1500</u>
Open Hole: Size _____ From _____ To _____		Treat Thru: Tubing <input checked="" type="checkbox"/> Annulus <input type="checkbox"/> Casing <input type="checkbox"/> Tubing/Annulus <input type="checkbox"/>

## MATERIALS USED

Type Job Pump Water for Disposal Test  
Fluid Water  
Fluid Source Madison formation  
API Gravity \_\_\_\_\_ Viscosity \_\_\_\_\_ CPS @ \_\_\_\_\_ °F  
Sand: Grade \_\_\_\_\_ Lb. \_\_\_\_\_ Sack ☐ Bulk ☐  
Sand: Grade \_\_\_\_\_ Lb. \_\_\_\_\_ Sack ☐ Bulk ☐  
Surfactant: Type \_\_\_\_\_ Gal. \_\_\_\_\_ in Bbl. Gal. \_\_\_\_\_  
Acid: Type \_\_\_\_\_ Gal. \_\_\_\_\_ %  
Fluid Loss Add.: Type \_\_\_\_\_ Gal. Lb. \_\_\_\_\_  
Perfpac Balls: Type 7/8" RCN No. 150  
Blocking Agent: Type \_\_\_\_\_ Gal. Lb. \_\_\_\_\_  
Gelling Agent: Type \_\_\_\_\_ Gal. Lb. \_\_\_\_\_  
Breaker: Type \_\_\_\_\_ Gal. Lb. \_\_\_\_\_

## TREATMENT SUMMARY

Trucks (No. and Type) 1 58-C  
Hyd. HP Available 550 Used 500  
Pumps On Tubing 2 Casing 0  
AVERAGE RATES—BPM  
Treating \_\_\_\_\_ Displ. \_\_\_\_\_ Overall \_\_\_\_\_  
PRESSURES—PSI  
Breakdown \_\_\_\_\_ Maximum 3050  
Minimum 1200 Displacement \_\_\_\_\_  
Instant Shut-In 1000 5 Min. 800  
VOLUMES:  
Load: Bbl. Gal. \_\_\_\_\_ Breakdown: Bbl. Gal. \_\_\_\_\_  
Treatment: Bbl. 778 Displ.: Bbl. Gal. \_\_\_\_\_  
Total: Bbl. 778

## TREATING LOG

TIME	Operation or Anst. and Type Fluid Pumped	RATE	PUMPS	PRESSURE—PSI		REMARKS
				TUBING	CASING	
6:25	Test Lines		2	6000		
6:30	Pressure Annulus		1		1500	
10:00	Pump into perfs @ 3218 - 3250	10	2	2400		10,770 gal.
11:00	Set packer @ 3265, ch. squeeze set packer @ 3275					
3:33	Pump into perfs @ 3284-3415 and inject	8	2	2800		4,200 gal.
	100 RCN Balls	8	2	2900		6,000 gal.
	inject 25 RCN Balls	8	2	2900		8,000 gal.
	inject 25 RCN Balls	8	2	2900		11,400 gal.
	Set packer @ 3437					
4:37	Pump into perfs @ 3462-3512	8	2	3050		2,100 gal.
"	" " " " "	7	2	3000		
"	" " " " "	5	2	2800		
"	" " " " "	3	1	2200		2,950 gal.
5:05	Pump into perfs @ 3218-3512	9 1/2	2	2400	1000	2,100 gal.
"	" " " " "	7	2	1900		4,200 gal.
"	" " " " "	4 1/2	2	1500		6,300 gal.
5:30	" " " " "	3	1	1200		7,550 gal.

Halliburton Operator Bergner - McLean

Company Representative Wm. Brown

Copies Requested... 3

ORIGINAL MUST ACCOMPANY TICKET

FRACTURING  
Company Murphy Corp.

Lease

E P U

Well No.

80-D

Date

12-31-63

LOG 1381 W&O



HALLIBURTON

A Division of Halliburton Company  
DUNCAN, OKLAHOMA 73523WORK ORDER CONTRACT  
AND PRE-TREATMENT DATA

FORM 1908 R-2

ATTACH TO  
INVOICE & TICKET NO. 079164TRICT GlendiveDATE 2-25-77

HALLIBURTON SERVICES

YOU ARE HEREBY REQUESTED TO FURNISH EQUIPMENT AND SERVICEMEN TO DELIVER AND OPERATE

THE SAME AS AN INDEPENDENT CONTRACTOR TO: Murphy Corp. (CUSTOMER)  
AND DELIVER AND SELL PRODUCTS, SUPPLIES, AND MATERIALS FOR THE PURPOSE OF SERVINGLL NO. #50-D LEASE E.P.M. SEC. 3 TWP. 29N RANGE 51EEast Pease Unit COUNTY Rockwell STATE Mont. OWNED BY S.M.D.E.

THE FOLLOWING INFORMATION WAS FURNISHED BY THE CUSTOMER OR HIS AGENT

FORMATION	TYPE	NEW USED	WEIGHT	SIZE	FROM	TO	MAX. ALLOW. P.S.I.
CASING		<u>U</u>	<u>15.50</u>	<u>5 1/2</u>	<u>51</u>	<u>4500</u>	
LINER							
TUBING		<u>U</u>	<u>6.4</u>	<u>2 3/4</u>	<u>31</u>	<u>2300</u>	
OPEN HOLE							SHOTS/FT.
PERFORATIONS					<u>3218</u>	<u>3512</u>	
PERFORATIONS							
PERFORATIONS							

TREATMENT: DATE \_\_\_\_\_ TYPE \_\_\_\_\_ MATERIALS \_\_\_\_\_

TREATMENT INSTRUCTIONS: TREAT THRU TUBING ☒ ANNULUS ☐ CASING ☐ TUBING/ANNULUS ☐ HYDRAULIC HORSEPOWER ORDERED \_\_\_\_\_Size Perfs. with 2000 gal, 52% Reg.

CUSTOMER OR HIS AGENT STATES THE WELL IS IN PROPER CONDITION TO RECEIVE THE PRODUCTS, SUPPLIES, MATERIALS, AND SERVICES

THIS CONTRACT MUST BE SIGNED BEFORE WORK IS COMMENCED

In consideration, the above-named Customer agrees:

to pay Halliburton in accord with the rates and terms stated in Halliburton's current price lists.

Halliburton shall not be responsible for and Customer shall secure Halliburton against any liability for damage to property of Customer and of the well owner (different from Customer), unless caused by the willful misconduct or gross negligence of Halliburton, this provision applying to but not limited to subsurface image and surface damage arising from subsurface damage.

Customer shall be responsible for and secure Halliburton against any liability for reservoir loss or damage, or property damage resulting from subsurface pressure, sing, control of the well and/or a well blowout, unless such loss or damage is caused by the willful misconduct or gross negligence of Halliburton.

Customer shall be responsible for and secure Halliburton against any and all liability of whatever nature for damages as a result of subsurface trespass, or an tion in the nature thereof, arising from a service operation performed by Halliburton hereunder.

Customer shall be responsible for and secure Halliburton against any liability for injury to or death of persons, other than employees of Halliburton, or damage property (including, but not limited to, injury to the well), or any damages whatsoever, irrespective of cause, growing out of or in any way connected with the e of radioactive material in the well hole, unless such damage shall be caused by the willful misconduct or gross negligence of Halliburton.

Halliburton makes no guarantee of the effectiveness of the products, supplies or materials, nor of the results of any treatment or service.

Customer shall, at its risk and expense, attempt to recover any Halliburton equipment, tools or instruments which are lost in the well and if such equipment, s or instruments are not recovered, Customer shall pay Halliburton its replacement cost unless such loss is due to the sole negligence of Halliburton. If lliburton equipment, tools or instruments are damaged in the well, Customer shall pay Halliburton the lesser of its replacement cost or the cost of repairs un- s such damage is caused by the sole negligence of Halliburton. In the case of equipment, tools or instruments for marine operations, Customer shall, in dition to the foregoing, be fully responsible for loss of or damage to any of Halliburton's equipment, tools or instruments which occurs at any time after de- try to Customer at the landing until returned to the landing, unless such loss or damage is caused by the sole negligence of Halliburton.

Because of the uncertainty of variable well conditions and the necessity of relying on facts and supporting services furnished by others, Halliburton is unable to rantee the accuracy of any chart interpretation, research analysis, job recommendation or other data furnished by Halliburton. Halliburton personnel will use ir best efforts in gathering such information and their best judgment in interpreting it, but Customer agrees that Halliburton shall not be responsible for any ages arising from the use of such information except where due to Halliburton's gross negligence or willful misconduct in the preparation or furnishing of it.

Halliburton warrants only title to the products, supplies and materials and that the same are free from defects in workmanship and materials. THERE ARE NOARRANTIES, EXPRESS OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THEEDIATELY PRECEDING SENTENCE. Halliburton's liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, breach warranty, or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, supplies materials on their return to Halliburton or, at Halliburton's option, to the allowance to the Customer of credit for the cost of such items. In no event shall lliburton be liable for special, incidental, indirect, punitive or consequential damages.

On Customer's default in the payment of Customer's account 60 days after date of invoice, such account will thereafter be subject to interest until paid. In event it becomes necessary to employ an attorney to enforce collection of such account, Customer agrees to pay all collection costs and attorney fees in the ount of 20 per cent of the amount of the unpaid account.

Halliburton shall not be bound by any changes or modifications in this contract, except where such change or modification is made in writing by a duly horized executive officer of Halliburton.

I HAVE READ AND UNDERSTAND THIS CONTRACT AND REPRESENT  
THAT I AM AUTHORIZED TO SIGN THE SAME AS CUSTOMER'S AGENT

SIGNED

Ronald Hardline  
CUSTOMERDATE 2-25-77TIME 12:30 A.M. P.M.By that the Fair Labor Standards Act of 1938, as amended, has been complied with  
reduction of goods and/or with respect to services furnished under this contract.

CUSTOMER

# ALLIBURTON SERVICES JOB SUMMARY

HALLIBURTON DIVISION Denver  
HALLIBURTON LOCATION Tingo

DILLED ON 07/11/64  
TICKET NO.

WELL DATA  
East Poplar Unit SEC. 3 TWP. 29N RND. 51E COUNTY Rockwell STATE Mont

ATION NAME \_\_\_\_\_ TYPE \_\_\_\_\_  
ATION THICKNESS \_\_\_\_\_ FROM \_\_\_\_\_ TO \_\_\_\_\_  
L PROD: OIL \_\_\_\_\_ GPD. WATER \_\_\_\_\_ GPD. GAS \_\_\_\_\_ MCFD  
INT PROD: OIL \_\_\_\_\_ GPD. WATER \_\_\_\_\_ GPD. GAS \_\_\_\_\_ MCFD  
LETION DATE \_\_\_\_\_ MUD TYPE \_\_\_\_\_ MUD WT. \_\_\_\_\_  
IR TYPE \_\_\_\_\_ SET AT \_\_\_\_\_  
IN HOLE TEMP. \_\_\_\_\_ PRESSURE \_\_\_\_\_  
DATA \_\_\_\_\_

	NEW USED	SIZE	FROM	TO	WEIGHT	MAXIMUM PSI ALLOWABLE
CASING	11	5 1/2	21	4500	15.00	
LINER						
TUBING	4	2 3/8	21	2200	6.4	
OPEN HOLE						TOTAL DEPTH
PERFORATIONS			2212	2512		SHOTS/FT.
PERFORATIONS						SHOTS/FT.
PERFORATIONS						SHOTS/FT.

TOOLS AND ACCESSORIES		
TYPE AND SIZE	QTY.	MAKE
COLLAR		
SHOE		
SHOE		
ALIZERS		
M PLUG		
UC		
<u>Swedge 4"</u>	<u>1</u>	<u>Holco</u>

## JOB DATA

CALLER OUT	ON LOCATION	JOB STARTED	JOB COMPLETED
DATE <u>2-25</u> TIME <u>1200</u>	DATE <u>2-25</u> TIME <u>1245</u>	DATE <u>2-25</u> TIME <u>1300</u>	DATE <u>2-25</u> TIME <u>1500</u>

## PERSONNEL AND SERVICE UNITS

NAME	UNIT NO. & TYPE	LOCATION
<u>D. Nelson</u>	<u>0086</u>	<u>Tingo</u>
<u>L. Tundo</u>	<u>3404</u>	<u>Tingo</u>
<u>R. Hernandez</u>	<u>4121</u>	<u>Tingo</u>

MATERIALS  
FLUID \_\_\_\_\_ DENSITY \_\_\_\_\_ LB/GAL. API  
FLUID \_\_\_\_\_ DENSITY \_\_\_\_\_ LB/GAL. API  
TYPE \_\_\_\_\_ SIZE \_\_\_\_\_ LB.  
TYPE \_\_\_\_\_ SIZE \_\_\_\_\_ LB.  
TYPE Reg GAL. 3000 28  
TYPE \_\_\_\_\_ GAL. \_\_\_\_\_  
TYPE \_\_\_\_\_ GAL. \_\_\_\_\_  
STANT TYPE \_\_\_\_\_ GAL. \_\_\_\_\_ IN  
NT TYPE 3N GAL. 10 IN 2000  
OSS ADD. TYPE \_\_\_\_\_ GAL.-LB. \_\_\_\_\_ IN  
AGENT TYPE \_\_\_\_\_ GAL.-LB. \_\_\_\_\_ IN  
ED. AGENT TYPE \_\_\_\_\_ GAL.-LB. \_\_\_\_\_ IN  
IR TYPE \_\_\_\_\_ GAL.-LB. \_\_\_\_\_ IN  
NO AGENT TYPE \_\_\_\_\_ GAL.-LB. \_\_\_\_\_  
C BALLS TYPE \_\_\_\_\_ QTY. \_\_\_\_\_  
Enl H-50-20 901 IN  
2000 gal

DEPARTMENT Stimulation  
DESCRIPTION OF JOB Stimulation 12, P. unit  
2000 gal. 28.02. 12.02.  
JOB DONE THRU TUBING ☒ CASING ☐ ANNULUS ☐ TGG/ANN. ☐  
CUSTOMER REPRESENTATIVE X Gerald Hernandez  
HALLIBURTON OPERATOR D. Nelson COPIES REQUESTED \_\_\_\_\_

## CEMENT DATA

NUMBER OF SACKS	TYPE	API CLASS	BRAND	BULK SACKED	ADDITIVES	YIELD CU.FT./SK.	MIXED LBS./GAL.

## PRESSURES IN PSI

## SUMMARY

## VOLUMES

FIND \_\_\_\_\_ DISPLACEMENT \_\_\_\_\_ PREFLUSH GDL-GAL \_\_\_\_\_ TYPE \_\_\_\_\_  
WFF \_\_\_\_\_ MAXIMUM \_\_\_\_\_ LOAD & SHDN GDL-GAL \_\_\_\_\_ FAPI GDL-GAL \_\_\_\_\_  
RACTURE GRADIENT \_\_\_\_\_ TREATMENT GDL-GAL 48 DISPLI GDL-GAL 48  
INSTANT \_\_\_\_\_ 5-MIN. \_\_\_\_\_ 15-MIN. \_\_\_\_\_ CEMENT SLURRY GDL-GAL \_\_\_\_\_  
HYDRAULIC HORSEPOWER \_\_\_\_\_ TOTAL VOLUME GDL-GAL 96 28.12  
AVAILABLE \_\_\_\_\_ USED \_\_\_\_\_ REMARKS \_\_\_\_\_  
AVERAGE RATES IN BPM \_\_\_\_\_  
DISPL. \_\_\_\_\_ OVERALL \_\_\_\_\_  
CEMENT LEFT IN PIPE \_\_\_\_\_  
REASON \_\_\_\_\_

CUSTOMER

CUSTOMER

Murphy Corp.

LEAD FPU

WELL NO.

3-10 JOB TYPE Stimulation DATE 2-25-77

IALLIBURTON SERVICES  
**JOB LOG**

TICKET NO. 074164  
 PAGE NO. 1  
 DATE 2-25-77

CU. MER Murphy Corp.  
 JOB TYPE Acidizing Formation

ORM 2013 R-1

CHART NO.	TIME	RATE (OPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
1	1212	3		1		300		Start Acid
1	1322	3	24	1		550		Start Flush
	1328		<del>24</del>	1		550		Acid on Formation
	1325		36	1		600		Acid on Formation Let Soak
	1401		<del>44</del>	1		200		Start pumping Rest of Acid out
	1409		47	1		375		Start Acid, Acid out
	1416		48	1		375		Start Acid and Back
	1415		72	1		350		Start Flush
	1420		84	1		400		Acid on Formation Let Soak
	1452			1		200		Start pumping Rest of Acid
	1456		95	1		375		Acid out
	1457		96	1		375		Acid Flush 1801
						200		Instant Shut In
								Job Complete
								Thank
								You!
								Dole
								Lytle

CUSTOMER.

SHIP  
TO

Subject: Mrs.  
about: 1974-1975  
Army & Navy  
Popular, Modern: 00200

CUSTOMER'S  
ORDER  
NUMBER

CUSTOMER'S REF.

134. 10. 1. 1932.

DATE OF REQUISITION 1-3-89	DATE REQUIRED AT DESTINATION	INVOICE DATE	SHIP VIA UPS
CHARGE TO 37702-07400		CREDIT #13 80-D 1 1/2" 580 <sup>00</sup> ea	

ITEM NO	ORDERED QTY.	SHIPPED QTY.	HALLIBURTON NUMBER	ARTICLES AND DESCRIPTION	Z A R B
i.	4		291.43078	<p>Reframed Grip Jacket 1-10-69</p> <p>Halliburton Flow Measurement System consisting of:            1-1.5" internal flow meter, stainless steel, with 1.5"            male npt ends, 1" outside connection and quick            change tap section.            Serial # 1.051-34021      S.F. 310.07                                            \$77.21         \$24.95                                            \$77.24         \$25.95                                            \$77.3         \$27.81</p> <p>1-model Boston Electric Magnetic Pickup            1-model RS-11 Flow Analyzer, continuous recording,            with paper recording assembly, complete with one            lithium battery, continuous assembly with automatic            registering device and RS-11 motor &amp; recording unit.            Serial #</p> <div style="text-align: right;">             129641              129642              129643              129644           </div> <div style="text-align: right;">             4 @ 17 -              6.10.67-6.10.69              10.10.67-10.10.69              1.10.69           </div>	

FILED BY	RECEIVED BY	DATE RECEIVED	DATE SHIPPED	ENTERED STORES LEDGER
----------	-------------	---------------	--------------	-----------------------

BOXES \_\_\_\_\_ BAGS \_\_\_\_\_ CRATES \_\_\_\_\_ CARTONS \_\_\_\_\_

SIGNATURE \_\_\_\_\_

FORM HLS 7125







ATTACH: ) TICKET NO. 79208

TYPE OF JOB		LOG UNIT NO.	
Diff Temp Log		6058	
WELL NO.	LEASE	OWNED BY	

**As consideration the above named Customer agrees:**

- (a) To pay Halliburton Logging Services, Inc. ("HLS") in accordance with the rates and terms stated in HLS' current price schedules.
- (b) To defend, indemnify, release and hold harmless HLS, its divisions, subsidiaries, parent and affiliated companies and the officers, directors, employees, agents and servants of all of them from and against any claims, liability, expenses, attorney's fees, and costs of defense to the extent permitted by law, or:
1. Damage to property owned by, in the possession of, or leased by Customer, and/or the well owner (if different from Customer); including, but not limited to, surface and subsurface damage. The term "well owner" shall include working and royalty interest owners.
  2. Reservoir, formation or well loss or damage, subsurface trespass or any action in the nature thereof.
  3. Personal injury or death or property damage (including, but not limited to, damage to the reservoir, formation or well), or any damages whatsoever, growing out of or in any way connected with, or resulting from pollution, subsurface pressure, losing control of the well and/or a well blowout or the use of radioactive material.
- The defense, indemnity, release and hold harmless obligations of Customer provided for in this Section (b) and Section (c) below shall apply to claims or liability even if caused or contributed to by HLS' negligence, strict liability, or the unseaworthiness of any vessel owned, operated, or furnished by HLS or any defect in the data, products, supplies, materials, or equipment of HLS whether in the preparation, design, manufacture, distribution, or marketing thereof, or from a failure to warn any person of such defect. Such defense, indemnity, release and hold harmless obligations of Customer shall not apply where the claim or liability are caused by the gross negligence or willful misconduct of HLS. The term "HLS" as used in said Sections (b) and (c) shall mean HLS, its divisions, subsidiaries, parent and affiliated companies, and the officers, directors, employees, agents and servants of all of them.
- (c) That because of the uncertainty of variable well conditions and the necessity of relying on facts and supporting services furnished by others, HLS is unable to guarantee the effectiveness of the products, supplies or materials, nor the results of any treatment or service, nor the accuracy of any log or chart interpretation, research analysis, job recommendation or other data furnished by HLS. HLS personnel will use their best efforts in gathering such information and their best judgement in interpreting it, but Customer agrees that HLS shall not be liable for and Customer shall indemnify HLS against any damages arising from the use of such information.
- (d) That Customer shall, at its risk and expense, attempt to recover any HLS equipment, tools or instruments which are lost in the well and if such equipment, tools or instruments are not recovered, Customer shall pay HLS its replacement cost unless such loss is due to the sole negligence of HLS. If HLS equipment, tools or instruments are damaged in the well, Customer shall pay HLS the lesser of its replacement cost or the cost of repairs unless such damage is caused by the sole negligence of HLS. In the case of equipment, tools or instruments for marine operations, Customer shall, in addition to the foregoing, be fully responsible for loss of or damage to any HLS' equipment, tools or instruments at any time such equipment, tools or instruments are returned to the landing, unless such loss or damage is caused by the sole negligence of HLS.
- (e) To furnish at its expense any transportation for HLS marine services personnel to and from point of embarkation.
- (f) That HLS warrants only title to the products, supplies and materials and that the same are free from defects in workmanship and materials. THERE ARE NO WARRANTIES, EXPRESSED OR IMPLIED, OF MERCHANTABILITY, FITNESS OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. HLS' liability and Customer's exclusive remedy in any cause of action (whether, in contract, tort, breach of warranty or otherwise) arising out of the sale or use of any products, supplies or materials is expressly limited to the replacement of such products, supplies or materials on their return to HLS or, at HLS' option, to the allowance to the Customer of credit for the cost of such items. In no event shall HLS be liable for special, incidental, indirect, punitive or consequential damages.
- (g) Invoices payable NET by the 20th of the following month after date of invoice. Upon Customer's default in payment of Customer's account by the last day of the month following the month in which the invoice is dated, Customer agrees to pay interest thereon after default at the highest lawful contract rate applicable but never to exceed 18% per annum. In the event it becomes necessary to employ an attorney to enforce collection of said account, Customer shall be responsible for the amount of 20% of the amount of any attorney fees and costs of collection.
- (h) These terms and conditions shall be governed by the law of the state where services are performed or equipment or materials are furnished.
- (i) HLS shall not be bound by any changes or modifications in this contract except where such change or modification is made in writing by a duly authorized executive officer of HLS.
- (j) Customer, or his agent, warrants the well is in proper condition to receive the products, supplies, materials and services.
- (k) To waive the provisions of the Deceptive Trade Practices - Consumer Protection Act, to the extent permitted by law.
- (l) Notwithstanding anything contained herein to the contrary, in the event a logging tool containing a radioactive source or a radioactive source utilized in any other manner by HLS becomes lost or lodged in a well, Customer shall be responsible for meeting all requirements of Section 39.15(a) of the Nuclear Regulatory Commission regulations concerning retrieval and, if necessary, abandonment of lost or lodged sources and to permit HLS to monitor the recovery efforts.

INSTRUMENT PROTECTION ☒ INIT NOT OFFERED ☐ INIT ACCEPTED ☐ INIT DECLINED

I have read and understand this contract and represent that I am authorized to sign the same as Customer's agent.

DATE 5-5-92 TIME SIGNED 11:42 ☐ A.M. ☒ P.M.  
DISTRICT W.H. 11

THIS CONTRACT MUST BE SIGNED BEFORE WORK IS COMMENCED

HLS certifies that the Fair Labor Standards Acts of 1938, as amended, has been complied with in the production of products, supplies and materials and/or with respect to services performed under this contract.



#3 Motor

Electro Dynamic

Frame 584

Model 274577A2

Type T

115 70 SF

Code F des R

3 Phase

Cyc H.P. R.P.M. Volt amp

60 125 1175 220/440 304/152

GWS

#3

184 strokes per min Plunger 3 1/4

Motor 10 1/2 Pump 14.0

Pump

Serial No. P115-54

Type 346-P size 4 1/4 x 6

input H.P.

Pump R.P.M.

Piston R.P.M.

125

250

1110

100

200

888

75

150

666

Plunger

Max Pres

4 1/4

205

4

195

3 1/2

1040

3

1420



# Proposal

Page No. 1  
of \_\_\_\_\_ Pages

## JACOBSEN CONSTRUCTION, INC.

Your Butler Builder

Highway 2 & 85 North  
P.O. Box 1235

Williston, N. Dak.  
GR 3-3791

PROPOSAL SUBMITTED TO:		PHONE:	DATE: 12/13/63
NAME: Murphy Corporation		JOB NAME:	
STREET: Poplar		STREET:	
CITY:		CITY:	STATE:
STATE: Montana		ARCHITECT:	DATE OF PLANS:

We hereby submit specifications and estimates for: One 16' x 23'10" x 8' Butler Paul-Frame building with one 12" ventilator with damper, one 5' wide x 7' high single slide door, Four A22140 commercial project out steel frame windows.

Building completely erected on 6" x 6" beams supplied by buyer.

Insulated walls and roof with 1½" Ultralite insulation with Foil Skrim Craft facing. Walls and roof interior covered with 28 ga. galvanized flat steel sheets.

One end of building flashed to 9'6" diameter tank.

One 6' x 4' area partitioned off. Partition to go to roof and to be 2x4 studs on 24" centers covered with 28 ga flat galvanized steel sheets each side. Partition to contain single slide 5' wide x 7' high door.

Two to three week delivery.

We hereby propose to furnish labor and materials — complete in accordance with the above specifications, for the sum of:

Twenty-five Hundred Six and 00/100 - - dollars (\$ 2506.00) with payment to be made as follows:

All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado and other necessary insurance. Our workers are fully covered by Workmen's Compensation Insurance.

Authorized Signature



NOTE: This proposal may be withdrawn by us if not accepted within \_\_\_\_\_ days.

### Acceptance of Proposal

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

Accepted:

Signature \_\_\_\_\_

Date \_\_\_\_\_

Signature \_\_\_\_\_



**MURPHY**  
CORPORATION

MURPHY BUILDING  
EL DORADO, ARKANSAS

SHOW THIS NUMBER

No 12830

ON YOUR INVOICE, B/L, CASE,  
BUNDLES, PACKING LIST AND  
ALL CORRESPONDENCE.



## PURCHASE ORDER

ORDER DATE	REQ. NO.	DELIVERY DATE REQUIRED
10-23-63	18726	10-30-63

TO

Rice Engineering & Operating, Inc.  
1809 Washington Street  
Great Bend, Kansas

Attn: Mr. Gordon Jones

SHIP TO

Murphy Corporation  
% M. T. James  
P. O. Box 547  
Poplar, Montana 59255

MAIL INVOICES IN TRIPLICATE TO MURPHY CORPORATION, EL DORADO, ARKANSAS

CHARGE TO	A.P.E. NO.	F.O.D. POINT	SHIP PREPAID VIA	
EPU #80-D S.W. Disposal Facilities	3-1519	Poplar, Montana/	Best Way	
QUANTITY	DESCRIPTION			UNIT PRICE
1	6" x 6" Class 100 F/T C.A. Male Ell			
1	6" series 300 C.I. Flange machined out to fit Class 100 F/T C.A.			
4	6" 150 series C.I. Flange machined out to fit Class 100 F/T C.A.			
1	6" x 6" Class 100 F/T C.A. Nipple fully machined			
2	10" C.A. F/T Outside cap Class 100			
2	10" Steel strap for 10" outside C.A. F/T cap Class 100			
2	10" x 36" C.A. F/T nipple with 2" PVC Schedule 80 T.O.E. Nipple 6" from end. Fully machined.			
2	10" Female x 8" male swage nipple C.A. F/T Class 100			
2	8" Full opening gate Valve C.A. F/T Class 100			
1	8" Male x 8" male x 8" Female 45 degree Y C.A. F/T Class 100			
4	8" 150 series C.I. Flange machined out to fit Class 100 F/T C.A.			
1	8" C.A. F/T Class 100 45 degree Male x Female Ell			
1	8" Male Class 100 x 8" female Class 100 x 6" side male Class 150 C.A. F/T tee.			
2	6" 150 series C.I. Flanges machined out for Class 150 F/T C.A.			
1	6" Male x 6" Female side opening x 6" female Class 150 F/T C.A. tee			
2	6" Female x 4" Male side opening x 6" male F/T C.A. Class 150 tee			
1	6" Full opening gate valve Class 150 F/T C.A.			
2	4" 150 series C.I. Flanges machined out for Class 150 F/T C.A.			
2	4" F/T Female x 2" T.O.E. PVC Schedule 80 Nipple x 4" F/T Female Side opening tee			
2	Gas relief Valve with 2" female threaded bottom connection			
4	6" 150 series full face gaskets			
2	4" 150 series full face gaskets			
2	8" 150 series full face gaskets			

MURPHY CORPORATION

REMARKS

BY

B. J. Jones

PURCHASING DEPARTMENT

TO BE FILLED IN BY PERSON RECEIVING MATERIAL

RECEIVED VIA

DATE

BY

PERSON RECEIVING MATERIAL (OFFICE FILE COPY)  
(TO BE RETAINED BY DEPARTMENT RECEIVING MATERIAL)

**MURPHY**  
CORPORATION

MURPHY BUILDING  
EL DORADO, ARKANSAS

SHOW THIS NUMBER

No 12831

ON YOUR INVOICE, B/L, CASE,  
BUNDLES, PACKING LIST AND  
ALL CORRESPONDENCE.



## PURCHASE ORDER

ORDER DATE	REQ. NO.	DELIVERY DATE REQUIRED
10-23-63	18724	As Soon As Possible

TO

Black, Sivalls & Bryson  
Williston,  
North Dakota

SHIP TO

Murphy Corporation  
% M. T. James  
P.O. Box 547  
Poplar, Montana 59255

MAIL INVOICES IN TRIPLICATE TO MURPHY CORPORATION, EL DORADO, ARKANSAS

CHARGE TO	A.P.E. NO.	F.O.D. POINT	SHIP PREPAID VIA
EPU #80-D & S.W. Disposal Facilities	3-1519	Poplar, Montana	Best Way
QUANTITY	DESCRIPTION		UNIT PRICE
1	13" x 15" float		
2	8" std tank flanges complete with bolts		
1	8" Comp. flange to fit 8" trunion		
1	8" trunion and stuffing box assembly and bolts		
1	8" x 6" std. nipple		

REMARKS

MURPHY CORPORATION

BY

*Louis C. Instina*  
Louis C. Instina

PURCHASING DEPARTMENT

TO BE FILLED IN BY PERSON RECEIVING MATERIAL

RECEIVED VIA

DATE

/ /

BY

PERSON RECEIVING MATERIAL (OFFICE FILE COPY)  
(TO BE RETAINED BY DEPARTMENT RECEIVING MATERIAL)



**MURPHY**  
CORPORATION

MURPHY BUILDING  
EL DORADO, ARKANSAS

SHOW THIS NUMBER

No 12829

ON YOUR INVOICE, B/L, CASE,  
BUNDLES, PACKING LIST AND  
ALL CORRESPONDENCE.



## PURCHASE ORDER

ORDER DATE	REQ. NO.	DELIVERY DATE REQUIRED
10-23-63	18726	Oct. 30, 1963

TO

South Chester Tube Company  
Suite 700  
Petroleum Club Building  
Tulsa 19, Oklahoma

Attn: Mr. G. E. Foreman

SHIP TO

Murphy Corporation  
% M. T. James  
P.O. Box 547  
Poplar, Montana

MAIL INVOICES IN TRIPLICATE TO MURPHY CORPORATION, EL DORADO, ARKANSAS

CHARGE TO	A.F.E. NO.	F.O.B. POINT	SHIP PREPAID VIA
EPU #80-D & S.W. Disposal Pac.	3-1519	Poplar, Montana	Best Way
QUANTITY	DESCRIPTION		UNIT PRICE
2400'	of 8" Class 100 Century Asbestos-Cement Pipe with fluid Tite couplings, self sealing rings and lubricant		
1	8" x 13' (Reg. length) full machined Class 100 Century Asbestos Cement Pipe		
1	8" x 10' (reg. length) full machined Class 100 Century Asbestos-Cement Pipe		
1	8" x 6' (reg. length) full machined Class 100 Century Asbestos Cement Pipe		
1	8" x 4' (reg. length) full machined Class 100 Century Asbestos Cement Pipe		
1	8" x 2' (reg. length) full machined Class 100 Century Asbestos Cement Pipe		
2	8" x 1' (reg. length) full machined Class 100 Century Asbestos Cement Pipe		
1	6" x 10' (reg length) full machined Class 100 Century Asbestos Cement Pipe		
12	8" Class 100 Fluid-Tite Couplings with self rubber sealing rings		
6	6" Class 100 Fluid Tite Couplings with self sealing rubber rings		
20	6" Class 100 Fluid Tite self sealing rubber rings		
10	8" Class 100 Fluid Tite Self sealing rubber rings		
Confirming Phone order to Mr. G. E. Foreman 10-23-63			
DO NOT DUPLICATE			

MURPHY CORPORATION

REMARKS

BY

PURCHASING DEPARTMENT

TO BE FILLED IN BY PERSON RECEIVING MATERIAL

RECEIVED VIA

DATE

BY

PERSON RECEIVING MATERIAL (OFFICE FILE COPY)  
(TO BE RETAINED BY DEPARTMENT RECEIVING MATERIAL)

**MURPHY**  
CORPORATION

MURPHY BUILDING  
EL DORADO, ARKANSAS

SHOW THIS NUMBER

No 12900

ON YOUR INVOICE, U/L. CASE,  
BUNDLES, PACKING LIST AND  
ALL CORRESPONDENCE.



## PURCHASE ORDER

ORDER DATE	REQ. NO.	DELIVERY DATE REQUIRED
10-28-63	18725	As Soon As Possible

TO

Continental-Aesco Company  
P. O. Box 531  
El Dorado, Arkansas

SHIP TO

Murphy Corporation  
% M. T. James  
P. O. Box 547  
Poplar, Montana 59255

MAIL INVOICES IN TRIPPLICATE TO MURPHY CORPORATION, EL DORADO, ARKANSAS

IE TO	A.F.E. NO.	F.O.D. POINT	SHIP PREPAID VIA
U #80-S.W. Disposal Facil.	3-1519	Poplar, Montana	Best Way
QUANTITY	DESCRIPTION		UNIT PRICE
1	2000# pressure Gauge with 1/2" shank.		
1	6" (491475) type RBL Norriseal Valves with Epoxy Coated Disc Top shaft boss tapped 1/8" NPT 2 sides, lugs drilled and tapped for std. 150 series ASA Flanges with std. handles complete with cap screws.		
1	4" (491475) type RBL Norriseal Valves with Epoxy Coated Disc Top shaft boss tapped 1/8" NPT 2 sides lugs drilled and tapped for std. ASA Flanges with std. handles complete with cap screws.		
1	6" (491475) type RBL Norriseal valve with Epoxy Coated Disc top shaft boss tapped 1/8"NPT 2 sides, lugs drilled and tapped to fit std. 150 series ASA Flanges with std. handle. Cap screws & gaskets.		
12	2" PVC Schedule 80 Elbs threaded.		
10	2" PVC Schedule 80 Tees threaded.		
10	2" x 4" PVC Schedule 80 Nipples threaded.		
10	2" x 6" PVC Schedule 80 Nipples threaded.		
10	2" x 8" PVC Schedule 80 Nipples threaded.		
00'	2" PVC Schedule 80 Threaded Pipe.		
	2" (491475) type RBL Norriseal Valve with Epoxy Coated Disc, top shaft boss tapped 1/8" NPT 2 sides lugs drilled and tapped with std. handle with threaded Companion Flanges and Cap screws.		
	8" (491475) type RBL Norriseal Valve with Epoxy Coated Disc. top shaft boss tapped 1/8" NPT 2 sides, lugs drilled and tapped to fit std. 150 series ASA Flanges with std. handle. Cap screws & gaskets.		
250'	3" 8 V thread xx 2" reg. thd. heavy awage internally plastic coated. of 3-1/2" OD 9.20# J-55 reg. 10 R thd. R 2 Tbg. Internally coated with Tube Kote TK-2, 100% holiday free and retested on location. Fig. 11 Larkin Wall type tbg. packer, 3-1/2" reg.10rd thd. tbg. connect- ion for 5-1/2" 15-5# casing, internally plastic coated.		
- Continued -			

KG

MURPHY CORPORATION

BY

Lewis G. Justice

PURCHASING DEPARTMENT

TO BE FILLED IN BY PERSON RECEIVING MATERIAL

RECEIVED VIA

DATE

BY

PERSON RECEIVING MATERIAL (OFFICE FILE COPY)  
(TO BE RETAINED BY DEPARTMENT RECEIVING MATERIAL)

**MURPHY**  
CORPORATION

MURPHY BUILDING  
EL DORADO, ARKANSAS

SHOW THIS NUMBER

No 12900 Page 2

ON YOUR INVOICE, B/L, CASE,  
BUNDLES, PACKING LIST AND  
ALL CORRESPONDENCE.



PURCHASE ORDER

ORDER DATE	REQ. NO.	DELIVERY DATE REQUIRED
10-28-63	18725	As Soon As Possible

TO

Continental-Emaco Company  
P. O. Box 531  
El Dorado, Arkansas

SHIP TO

Murphy Corporation  
% M. T. James  
P. O. Box 547  
Poplar, Montana 59255

MAIL INVOICES IN TRIPPLICATE TO MURPHY CORPORATION, EL DORADO, ARKANSAS

IE TO	A.F.E. NO.	F.O.B. POINT	SHIP PREPAID VIA
PU #80-D & S. W. Disposal Facilities	3-1519	Poplar, Mont.	Best Way

QUANTITY	DESCRIPTION	UNIT PRICE
	<p>Page 2</p> <p>3" 1000# W.P. 2000# test 10 rd thd. gate valve. Full opening for corrosive salt water service.</p> <p>3" 1000# W.P. 2000# test steel tees 8 v thd. internally plastic coated.</p> <p>3" x 6" Hvy nipples, internally plastic coated 8 v thd.</p> <p>3" x 8" Hvy nipples, internally plastic coated 8 v thd.</p> <p>3" 1000# W.P. 2000# test steel Elbs 8 v thd. internally plastic coated.</p> <p>3" 8 v thd. hvy bull plug taped 1/2"</p> <p>1/2" straight needle valve</p> <p>3" 10 rd. Reg. x 3" 8 v thd x 8" long Ex Hvy. comb. Nipple, Plastic lined.</p>	

KS

MURPHY CORPORATION

BY

*Lewis G. Justice*  
Lewis G. Justice

PURCHASING DEPARTMENT

TO BE FILLED IN BY PERSON RECEIVING MATERIAL

RECEIVED VIA

DATE

1-1

BY

*W. J. Brown*

PERSON RECEIVING MATERIAL (OFFICE FILE COPY)  
(TO BE RETAINED BY DEPARTMENT RECEIVING MATERIAL)





# ANALYTICAL LABORATORY REPORT

File

>> COUPON REPORT <<

Company: MURPHY OIL  
Address: POPULAR, MONTANA

Print date: 11/ 1/83  
Report No. 83C-1527

Page 1 of 1

COUPON LOCATION	EXPOSURE PERIOD	CHEMICAL IN USE	COUPON NUMBER	CORROSION RATE (mpy)	TYPE OF CORROSION
3-D	08/05/83 to 10/26/83	NONE	01698d	1.1	Gen. Etch
4-D	08/05/83 to 10/26/83	VISCO 3410	01697d	2.3	Pitting
5-D	08/05/83 to 10/26/83	VISCO 3410	01693d	1.2	Pitting
6-D WATER DISPOSAL	08/05/83 to 10/26/83	VISCO 1111 & VISCO 3410	01694d	1.5	Pitting
LILLIAN SWD	10/04/83 to 10/26/83	VISCO 1111 & VISCO 3410	06935	1.7	Gen. Etch

d See Deposit Weight Attachment

NALCO CHEMICAL COMPANY  
ANALYTICAL LABORATORIES

Form PS-108 (10M 12-82)

P. O. Box 220  
Long Beach, CA 90801

1927 Nolto Drive  
Paulsboro, NJ 08066

Box 87  
Sugar Land, TX 77478

1801 Diehl Road  
Naperville, IL 60566



## REPORT OF WATER ANALYSIS

Company      Murphy Oil Corporation  
                 Poplar, Montana

Date      August 20, 1985  
Analysis No.  
Sampling Date      August 20, 1985  
Date Sample Rec'd.      August 20, 1985

Sample Marked      3-D

### DISSOLVED SOLIDS

Cations	mg/l	meq/l
Sodium, Na (Calc.)	56,097	2,439
Calcium, Ca	2,000	100
Magnesium, Mg	243	20
Barium, Ba	0	0
Cations Total	58,340	2,559

### Anions

Chloride, Cl	89,836	2,533
Sulfate, SO <sub>4</sub>	845	18
Carbonate, CO <sub>3</sub>	0	0
Bicarbonate, HCO <sub>3</sub>	464	8
Anions Total	91,145	2,559

Total Dissolved Solids (Calc.)	149,485
Total Iron, Fe	0.4
Acidity to Phenolphthalein, CO <sub>2</sub>	229

### RESULTS AS COMPOUNDS

	mg/l
as NaCl	
as CaCO <sub>3</sub>	5,000
as CaCO <sub>3</sub>	1,000
as BaSO <sub>4</sub>	0
as NaCl	148,000
as Na <sub>2</sub> SO <sub>4</sub>	1,250
as CaCO <sub>3</sub>	0
as CaCO <sub>3</sub>	380

as Fe	0.4
as CaCO <sub>3</sub>	520

### OTHER PROPERTIES

pH	6.0
Specific Gravity	
Turbidity (JTU)	
Sulfide, as H <sub>2</sub> S	(present)

CaCO<sub>3</sub> STABILITY INDEX  
@ 70° F.  
@ 120° F.  
@ 160° F.  
Method of Stiff & Davis

Remarks:      cc:    D. Kasowski  
                              D. Brown

/mg

**NALCO CHEMICAL COMPANY**  
**VISCO CHEMICALS**

P. O. BOX 87 • SUGAR LAND, TEXAS 77478



## REPORT OF WATER ANALYSIS

Company      Murphy Oil Corporation  
                 Poplar, Montana

Date      12/11/86  
Analysis No.  
Sampling Date      12/11/86  
Date Sample Rec'd.      12/11/86

Sample Marked      80-D

### DISSOLVED SOLIDS

Cations	mg/l	meq/l
Sodium, Na (Calc.) .....	65,880.6	2,864.4
Calcium, Ca .....	240	12.0
Magnesium, Mg .....	97.2	8.0
Barium, Ba .....		
Cations Total .....	66,217.8	2,884.4

### RESULTS AS COMPOUNDS

	mg/l
as NaCl .....	
as CaCO <sub>3</sub> .....	600
as CaCO <sub>3</sub> .....	400
as BaSO <sub>4</sub> .....	

Anions		
Chloride, Cl .....	101,369.0	2,858.6
Sulfate, SO <sub>4</sub> .....	709.8	14.8
Carbonate, CO <sub>3</sub> .....	0	0
Bicarbonate, HCO <sub>3</sub> .....	671	11
Anions Total .....	102,749.8	2,884.4

as NaCl .....	167,000
as Na <sub>2</sub> SO <sub>4</sub> .....	1,050
as CaCO <sub>3</sub> .....	0
as CaCO <sub>3</sub> .....	550

Total Dissolved Solids (Calc.) ...	168,967.6
Total Iron, Fe .....	2.2
Acidity to Phenolphthalein, CO <sub>2</sub> ..	220

as Fe .....	2.2
as CaCO <sub>3</sub> .....	500

### OTHER PROPERTIES

pH .....	6.6
Specific Gravity .....	
Turbidity (JTU) .....	
Sulfide, as H <sub>2</sub> S .....	(present)

CaCO<sub>3</sub> STABILITY INDEX  
@ 70° F.  
@ 120° F.  
@ 160° F.  
Method of Stiff & Davis

Remarks:      cc:    D. Kasowski  
                              D. Brown

/mg

**NALCO CHEMICAL COMPANY**  
**VISCO CHEMICALS**

P. O. BOX 87 • SUGAR LAND, TEXAS 77478



# REPORT OF WATER ANALYSIS

Company      Murphy Oil Corporation  
                 Poplar, Montana

Date      April 2, 1987

Analysis No.

Sampling Date      April 2, 1987

Date Sample Rec'd. April 2, 1987

Sample Marked      80=D

(Sample taken from disposal pump)

## DISSOLVED SOLIDS

Cations	mg/l	meq/l
Sodium, Na (Calc.)	53,764.8	2,337.6
Calcium, Ca	1,200	60
Magnesium, Mg	121.5	10
Barium, Ba		

Cations Total      55,086.3      2,407.6

## Anions

Chloride, Cl	84,980	2,396.4
Sulfate, SO <sub>4</sub>	135.2	2.8
Carbonate, CO <sub>3</sub>	0	0
Bicarbonate, HCO <sub>3</sub>	512.4	8.4

Anions Total      85,627.6      2,407.6

Total Dissolved Solids (Calc.)      140,713.9

Total Iron, Fe      123.2

Acidity to Phenolphthalein, CO<sub>2</sub>      123.2

## RESULTS AS COMPOUNDS

	mg/l
as NaCl	
as CaCO <sub>3</sub>	3,000
as CaCO <sub>3</sub>	500
as BaSO <sub>4</sub>	

as NaCl	140,000
as Na <sub>2</sub> SO <sub>4</sub>	200
as CaCO <sub>3</sub>	0
as CaCO <sub>3</sub>	420

as Fe	
as CaCO <sub>3</sub>	280

## OTHER PROPERTIES

pH	6.7
Specific Gravity	
Turbidity (JTU)	
Sulfide, as H <sub>2</sub> S	(present)

CaCO<sub>3</sub> STABILITY INDEX  
@ 70° F.  
@ 120° F.  
@ 160° F.  
Method of Stiff & Davis

Remarks:      cc: D. Kasowski  
                 D. Brown  
                 /mg

*Dale Kasowski*  
Account Manager

NALCO CHEMICAL COMPANY  
VISCO CHEMICALS

P. O. BOX 87 • SUGAR LAND, TEXAS 77478



# REPORT OF WATER ANALYSIS

Company Murphy Oil Corporation  
Poplar, Montana

Date July 28, 1987  
Analysis No.  
Sampling Date July 28, 1987  
Date Sample Rec'd. July 28, 1987

Sample Marked 80-D 9:30 a.m. (MST) Taken from disposal tank

## DISSOLVED SOLIDS

Cations	mg/l	meq/l
Sodium, Na (Calc.)	59,064	2,568
Calcium, Ca	1,800	90
Magnesium, Mg	243	20
Barium, Ba		
Cations Total	61,107	2,678

## RESULTS AS COMPOUNDS

	mg/l
as NaCl	
as CaCO <sub>3</sub>	4,500
as CaCO <sub>3</sub>	1,000
as BaSO <sub>4</sub>	

Anions	mg/l	meq/l
Chloride, Cl	94,085	2,654
Sulfate, SO <sub>4</sub>	676	14
Carbonate, CO <sub>3</sub>	0	0
Bicarbonate, HCO <sub>3</sub>	610	10
Anions Total	95,371	2,678

Total Dissolved Solids (Calc.)	156,478
Total Iron, Fe	
Acidity to Phenolphthalein, CO <sub>2</sub>	176

as NaCl	155,000
as Na <sub>2</sub> SO <sub>4</sub>	1,000
as CaCO <sub>3</sub>	0
as CaCO <sub>3</sub>	500

as Fe	
as CaCO <sub>3</sub>	400

## OTHER PROPERTIES

pH	6.6
Specific Gravity	1.105
Turbidity (JTU)	
Sulfide, as H <sub>2</sub> S	(present)

CaCO<sub>3</sub> STABILITY INDEX  
@ 70° F.  
@ 120° F.  
@ 160° F.  
Method of Stiff & Davis

Remarks: cc: D. Kasowski  
D. Brown  
/mg

\*Sample container 6 oz. clear  
prescription bottle

NALCO CHEMICAL COMPANY  
VISCO CHEMICALS

P. O. BOX 87 • SUGAR LAND, TEXAS 77478



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

27-FEB-89

EPU 80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

Cations		mg/l	meq/l		mg/l
		=====	=====		=====
Sodium	Na+	63,415.8	2,757.2	as NaCl	
Calcium	Ca++	880.0	44.0	as CaCO3	2,200.0
Magnesium	Mg++	145.8	12.0	as CaCO3	600.0
Barium	Ba++			as CaCO3	
Strontium	Sr++			as CaCO3	
Total Cations		64,441.6	2,813.2		

Anions		mg/l	meq/l		mg/l
		=====	=====		=====
Chloride	Cl-	98,941.0	2,790.1	as NaCl	163,000.0
Sulfate	SO4=	743.6	15.5	as Na2SO4	1,100.0
Carbonate	CO3=			as CaCO3	
Bicarb.	HCO3-	463.6	7.6	as CaCO3	380.0
Total Anions		100,148.2	2,813.2		
Total Solids		164,589.8			

### METALS

Total Iron, Fe	1.5	as Fe	1.5
Acid to Phen, CO2	140.8	as CaCO3	320.0

### OTHER PROPERTIES

pH	5.8
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2S ppm	
Temperature F	

*Mont. A. J.*  
*2/28/89*

NALCO CHEMICAL COMPANY

Form 733 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

27-FEB-89

EPU 80-D  
PRODUCED

Page 2

## >>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-1.54	-77.22	NA	NA
80	-1.34	-77.61	NA	NA
100	-1.10	-77.70	NA	NA
120	-0.82	-76.88	NA	NA
140	-0.49	-75.84	NA	NA
160	-0.12	-74.78	NA	NA
180	+0.28	-73.70	NA	NA
200	+0.73	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT


MURPHY OIL CORPORATION  
POPLAR, MONTANA

27-FEB-89

EPU 80-D  
PRODUCED

Page 3

>>> scaling indices <<<



O = CaCO<sub>3</sub>  
\* = CaSO<sub>4</sub>  
# = BaSO<sub>4</sub>  
X = SrSO<sub>4</sub>

NALCO CHEMICAL COMPANY

Form 738 (2-88)

ANALYTICAL LABORATORIES

One Nalco Center  
Naperville, IL 60566-1024

P.O. Box 87  
Sugar Land, Texas 77487





# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

21-JUN-89

EPU #80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

=====

Cations		mg/l	meq/l		mg/l
=====		=====	=====		=====
Sodium	Na+	57,745.0	2,510.7	as NaCl	
Calcium	Ca++	1,000.0	50.0	as CaCO3	2,500.0
Magnesium	Mg++	121.5	10.0	as CaCO3	500.0
Barium	Ba++			as CaCO3	
Strontium	Sr++			as CaCO3	
		-----	-----		
Total Cations		58,866.5	2,570.7		

Anions		mg/l	meq/l		mg/l
=====		=====	=====		=====
Chloride	Cl-	90,443.0	2,550.5	as NaCl	149,000.0
Sulfate	SO4=	608.4	12.7	as Na2SO4	900.0
Carbonate	CO3=			as CaCO3	
Bicarb.	HCO3-	457.5	7.5	as CaCO3	375.0
		-----	-----		
Total Anions		91,508.9	2,570.7		

Total Solids 150,375.4

### METALS

=====

Total Iron, Fe	1.5	as Fe	1.5
Acid to Phen, CO2	110.0	as CaCO3	250.0

### OTHER PROPERTIES

=====

pH 5.9  
Specific Gravity 1.1  
Turbidity  
Oxygen, as O2 ppm  
Sulfide as H2S ppm  
Temperature F

*Max A. Jern*  
6/21/89

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P.O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

21-JUN-89

EPU #80-D  
PRODUCED

Page 2

## >>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-1.39	-72.61	NA	NA
80	-1.19	-72.98	NA	NA
100	-0.95	-73.08	NA	NA
120	-0.67	-72.37	NA	NA
140	-0.35	-71.33	NA	NA
160	+0.01	-70.23	NA	NA
180	+0.42	-69.12	NA	NA
200	+0.87	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT


MURPHY OIL CORPORATION  
POPLAR, MONTANA

21-JUN-89

EPU #80-D  
PRODUCED

Page 3

>>> Scaling Indices <<<



O = CaCO<sub>3</sub>  
\* = CaSO<sub>4</sub>  
# = BaSO<sub>4</sub>  
X = SrSO<sub>4</sub>

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

22-SEP-89

EPU 80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

=====

Cations		mg/l	meq/l		mg/l
=====		=====	=====		=====
Sodium	Na+	56,114.8	2,439.8	as NaCl	
Calcium	Ca++	920.0	46.0	as CaCO3	2,300.0
Magnesium	Mg++	170.1	14.0	as CaCO3	700.0
Barium	Ba++			as CaCO3	
Strontium	Sr++			as CaCO3	
Total Cations		57,204.9	2,499.8		

Anions		mg/l	meq/l		mg/l
=====		=====	=====		=====
Chloride	Cl-	88,015.0	2,482.0	as NaCl	145,000.0
Sulfate	SO4=	507.0	10.5	as Na2SO4	750.0
Carbonate	CO3=			as CaCO3	
Bicarb.	HCO3-	439.2	7.2	as CaCO3	360.0
Total Anions		88,961.2	2,499.8		

Total Solids 146,166.1

### METALS

=====

Total Iron, Fe	2.0	as Fe	2.0
Acid to Phen, CO2	114.4	as CaCO3	260.0

### OTHER PROPERTIES

=====

pH	5.9
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2S ppm	
Temperature F	

*max A. ju*  
9-22-89

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1034

ANALYTICAL LABORATORIES

P.O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

22-SEP-89

EPU 80-D  
PRODUCED

Page 2

## >>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-1.49	-74.76	NA	NA
80	-1.30	-75.12	NA	NA
100	-1.06	-75.22	NA	NA
120	-0.77	-74.55	NA	NA
140	-0.45	-73.50	NA	NA
160	-0.08	-72.39	NA	NA
180	+0.32	-71.27	NA	NA
200	+0.77	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT


MURPHY OIL CORPORATION  
POPLAR, MONTANA

22-SEP-89

EPU 80-D  
PRODUCED

Page 3

>>> Scaling Indices <<<



O =  $\text{CaCO}_3$   
\* =  $\text{CaSO}_4$   
# =  $\text{BaSO}_4$   
X =  $\text{SrSO}_4$

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

11-DEC-89

EPU 80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

Cations		mg/l	meq/l		mg/l
		=====	=====		=====
Sodium	Na+	52,452.4	2,280.5	as NaCl	
Calcium	Ca++	880.0	44.0	as CaCO3	2,200.0
Magnesium	Mg++	315.9	26.0	as CaCO3	1,300.0
Barium	Ba++			as CaCO3	
Strontium	Sr++			as CaCO3	
Total Cations		53,648.3	2,350.5		

Anions		mg/l	meq/l		mg/l
		=====	=====		=====
Chloride	Cl-	82,552.0	2,328.0	as NaCl	136,000.0
Sulfate	SO4=	777.4	16.2	as Na2SO4	1,150.0
Carbonate	CO3=			as CaCO3	
Bicarb.	HCO3-	390.4	6.4	as CaCO3	320.0
Total Anions		83,719.8	2,350.5		

Total Solids 137,368.1

### METALS

Total Iron, Fe	1.0	as Fe	1.0
Acid to Phen, CO2	140.8	as CaCO3	320.0

### OTHER PROPERTIES

pH	5.8
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2S ppm	
Temperature F	

*Max*  
12-10-89

NALCO CHEMICAL COMPANY

Form 738 (2-88)

One Nalco Center  
Naperville, IL 60566-1024

ANALYTICAL LABORATORIES

P. O. Box 87  
Sugar Land, Texas 77487



# ANALYTICAL LABORATORY REPORT

MURPHY CORPORATION  
POPLAR, MONTANA

14-DEC-90

EPU 80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

Cations		mg/l	meq/l		mg/l
		=====	=====		H =====
Sodium	Na+	60,456.7	2,628.6	as NaCl	
Calcium	Ca++	1,060.0	53.0	as CaCO3	2,650.0
Magnesium	Mg++	243.0	20.0	as CaCO3	1,000.0
Barium	Ba++			as CaCO3	
Strontium	Sr++			as CaCO3	
Total Cations		61,759.7	2,701.6		

Anions		mg/l	meq/l		mg/l
		=====	=====		=====
Chloride	Cl-	95,299.0	2,687.4	as NaCl	157,000.0
Sulfate	SO4=	419.1	8.7	as Na2SO4	620.0
Carbonate	CO3=			as CaCO3	
Bicarb.	HCO3-	329.4	5.4	as CaCO3	270.0
Total Anions		96,047.5	2,701.6		
Total Solids		157,807.2			

### METALS

Total Iron, Fe	1.5	as Fe	1.5
Acid to Phen, CO2	70.4	as CaCO3	160.0

### OTHER PROPERTIES

pH	5.9
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2S ppm	
Temperature F	

*Max  
Nalco Chemical  
12-21-90*

Form 738 (8-89)

Analytical Laboratory Locations:

**NALCO CHEMICAL COMPANY**  
NE NALCO CENTER • NAPERVILLE, ILLINOIS 60563-1198  
DST OFFICE BOX 87 • SUGAR LAND, TEXAS 77487-0087







# ANALYTICAL LABORATORY REPORT

MURPHY CORPORATION  
POPLAR, MONTANA

14-DEC-90

EPU 80-D  
PRODUCED

Page 2

## >>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-1.51	-76.28	NA	NA
80	-1.31	-76.65	NA	NA
100	-1.07	-76.74	NA	NA
120	-0.79	-75.98	NA	NA
140	-0.46	-74.95	NA	NA
160	-0.09	-73.89	NA	NA
180	+0.31	-72.82	NA	NA
200	+0.76	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

Form 738 (8-89)

Analytical Laboratory Locations:

**NALCO CHEMICAL COMPANY**  
ONE NALCO CENTER • NAPERVILLE, ILLINOIS 60563-1188  
POST OFFICE BOX 87 • SUGAR LAND, TEXAS 77487-0087





# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORP.  
POPLAR, MONTANA

17-DEC-91

EPU 80-D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

Cations	mg/l	meq/l		mg/l
=====	=====	=====		=====
Sodium Na+	54,641.0	2,375.7	as NaCl	
Calcium Ca++	800.0	40.0	as CaCO3	2,000.0
Magnesium Mg++	182.3	15.0	as CaCO3	750.0
Barium Ba++			as CaCO3	
Strontium Sr++			as CaCO3	
Total Cations	55,623.3	2,430.7		

Anions	mg/l	meq/l		mg/l
=====	=====	=====		=====
Chloride Cl-	85,587.0	2,413.6	as NaCl	141,000.0
Sulfate SO4=	439.4	9.1	as Na2SO4	650.0
Carbonate CO3=			as CaCO3	
Bicarb. HCO3-	488.0	8.0	as CaCO3	400.0
Total Anions	86,514.4	2,430.7		
Total Solids	142,137.7			

### METALS

Total Iron, Fe	7.5	as Fe	7.5
Acid to Phen, CO2	118.8	as CaCO3	270.0

### OTHER PROPERTIES

pH	5.8
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2Sppm	
Temperature F	

Form 738 (8-89)

Analytical Laboratory Locations:

**NALCO CHEMICAL COMPANY**  
NALCO CENTER • NAPERVILLE, ILLINOIS 60563-1198  
T OFFICE BOX 87 • SUGAR LAND, TEXAS 77487-0087





# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORP.  
POPLAR, MONTANA

17-DEC-91

EPU 80-D  
PRODUCED

Page 2

>>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-1.56	-77.25	NA	NA
80	-1.36	-77.60	NA	NA
100	-1.12	-77.71	NA	NA
120	-0.84	-77.08	NA	NA
140	-0.51	-76.01	NA	NA
160	-0.15	-74.89	NA	NA
180	+0.25	-73.75	NA	NA
200	+0.70	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

Form 738 (8-89)

alytical Laboratory Locations:

**ALCO CHEMICAL COMPANY**  
E NALCO CENTER 0 NAPERVILLE, ILLINOIS 60563-1198

ST OFFICE BOX 87 0 SUGAR LAND, TEXAS 77487-0087





# ANALYTICAL LABORATORY REPORT

EPA # MTS2026-0026

MURPHY OIL CORPORATION  
POPLAR, MONTANA

17-DEC-92

EPU 80D  
PRODUCED

Page 1

## >>> Oil Field Water Analysis <<<

### DISSOLVED SOLIDS

Cations	mg/l	meq/l		mg/l
Sodium Na+	65,664.1	2,855.0	as NaCl	
Calcium Ca++	240.0	12.0	as CaCO3	600.0
Magnesium Mg++	121.5	10.0	as CaCO3	500.0
Barium Ba++			as CaCO3	
Strontium Sr++			as CaCO3	
Total Cations	66,025.6	2,877.0		

Anions	mg/l	meq/l		mg/l
Chloride Cl-	101,369.0	2,858.6	as NaCl	167,000.0
Sulfate SO4=	574.6	12.0	as Na2SO4	850.0
Carbonate CO3=			as CaCO3	
Bicarb. HCO3-	390.4	6.4	as CaCO3	320.0
Total Anions	102,334.0	2,877.0		
Total Solids	168,359.6			

### METALS

Total Iron, Fe	2.5	as Fe	2.5
Acid to Phen, CO2	77.0	as CaCO3	175.0

### OTHER PROPERTIES

pH	5.9
Specific Gravity	1.1
Turbidity	
Oxygen, as O2 ppm	
Sulfide as H2S ppm	
Temperature F	

*Mark A. Jones*  
1-7-92

Analytical Laboratory Locations:

NALCO CHEMICAL COMPANY  
NALCO CENTER • NAPERVILLE, ILLINOIS 60563-1188  
OFFICE BOX 87 • SUGAR LAND, TEXAS 77487-0087



Form 738 (8-89)



# ANALYTICAL LABORATORY REPORT

MURPHY OIL CORPORATION  
POPLAR, MONTANA

17-DEC-92

EPU 80D  
PRODUCED

Page 2

## >>> Scaling Indices <<<

Positive values indicate scaling tendencies

Temperature (Deg. F)	Calcium Carbonate	Calcium Sulfate	Barium Sulfate	Strontium Sulfate
60	-2.08	-96.93	NA	NA
80	-1.88	-97.33	NA	NA
100	-1.64	-97.41	NA	NA
120	-1.36	-96.58	NA	NA
140	-1.03	-95.54	NA	NA
160	-0.66	-94.45	NA	NA
180	-0.25	-93.36	NA	NA
200	+0.19	NA	NA	NA
220	NA	NA	NA	NA
240	NA	NA	NA	NA
260	NA	NA	NA	NA
280	NA	NA	NA	NA
300	NA	NA	NA	NA
320	NA	NA	NA	NA

Form 738 (8-89)

tical Laboratory Locations:

**LCO CHEMICAL COMPANY**  
NALCO CENTER • NAPERVILLE, ILLINOIS 60563-1198  
OFFICE BOX 87 • SUGAR LAND, TEXAS 77487-0087



**NATIONAL-OILWELL**  
Production Systems

#43316  
FIELD SERVICE REPORT

PORT No 30105  
STORE: Watford City  
REPRESENTATIVE: Tam Halberstam  
DATE: 9-27-90

TOMER Murphy Oil  
ATION

LEASE East Poplar Unit  
WELL NO. 80-0

IBLE AS  
PORTED

TROUBLE AS  
FOUND

ICE PERFORMED  
REMARKS

Travel to location, took Guard off pump, drained oil on pump, pulled covers, took intermediate rods out, loosened motor & took sheave off, pulled crank out, pulled crossheads out of pump, inspected crosshead pins & bushings, all were in good shape, main bearings were showing wear, changed out main bearings, changed out one Retainer, changed out all intermediate rods due to being scored, change out wipers, put crank back to pump, with 1004 end play, torqued connecting rods onto crank put intermediate rods in pump and tightened, put oil in gear end put covers on put sheave back on, put new belts on, aligned sheaves, put Guard on, started pump travel to shops

**PARTS USED**

PART NO.	DESCRIPTION	UNIT	TOTAL
1710018	Baffles		
1710011	wipers		
2T3621	bearings		
1710011	Retainer		
1710006	inter rods		

ME: FROM 6:30 O'CLOCK TO 5:30 O'CLOCK = 11.0 HOURS @ 3.20 PER HOUR

ILEAGE: FROM 61799 TO 62047 = 248 MILES @ .55 PER MILE

Total Charge

USTOMER BY DATE

BOVE CHARGES WILL BE BILLED BY:

HARGED:

S.O. NO.

D.M. NO.

irm No. 1053

ORIGINAL - ATTACH TO SALES ORDER OR DELIVERY TICKET

NATIONAL-OILWELL  
Production Systems

51061  
FIELD SERVICE REPORT

REPORT No 21526

STORE:

REPRESENTATIVE:

DATE:

Watford City  
Tom Kelbert  
11-7-91

STOMER *Murphy*  
CATION

LEASE  
WELL NO.

DOUBLE AS  
REPORTED

TROUBLE AS  
FOUND

IVICE PERFORMED  
OR REMARKS

*pulled sheave & hub off, pulled bull gear off shaft,  
took shaft rollers off pump, pulled Jackshaft off of pump,  
pulled crank shaft out of pump, tried pulling gear off  
back shaft, could not get gear off after 3 tries, took shaft  
down to machine shop to press off, got gear off brought shaft  
back to shop, steam clean power end & brought to machine shop  
for boring crosshead bores.*

PARTS USED

PART NO.	DESCRIPTION	UNIT	TOTAL

IE: FROM 7:00 O'CLOCK TO 5:00 O'CLOCK = 10 HOURS @ 31.00 PER HOUR

LEAGE: FROM \_\_\_\_\_ TO \_\_\_\_\_ = \_\_\_\_\_ MILES @ \_\_\_\_\_ PER MILE

Total Charge \_\_\_\_\_

ISTOMER \_\_\_\_\_ BY \_\_\_\_\_ DATE \_\_\_\_\_

OVE CHARGES WILL BE BILLED BY:

ARGED:

S.O. NO. \_\_\_\_\_

J.M. NO. \_\_\_\_\_

n No. 1053

CUSTOMER COPY

*National Oilwell Production*  
*Watford City ND*

END QUESTIONS TO  
 NATIONAL-OILWELL  
 TOLWAY 22 EAST  
 BOX 1286 (701) 842-2902  
 WYFORD CITY ND 58054



# NATIONAL-OILWELL

DELIVERY TICKET PAGE 1  
 \*\*\*\*\*  
 PLEASE MAIL CHECKS TO:  
 P. O. BOX 845984  
 DALLAS, TX 75284-5984

DATE DELIVERED: 11/12/91 SHIP VIA: DELV PREPAID  
 AD: Y  
 INITIALS: CEZ

CUSTOMER CODE: 6673700

SOLD TO  
 MURPHY OIL U.S.A. INC.

200 PEACH STREET  
 EL DORADO AR

SHIP TO  
 MURPHY OIL U.S.A. INC.

POPLAR, MT

11/30

DELIVERY TICKET 7404-051061

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* DO NOT PAY \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY REEDE

ORDER NO:

LEASE:

WELL/RIG: EPUSWD#80

BLANKET PO:

TAX LOC: 2700 TAX CODE: 0

*file copy*

QUANTITY SOLD	UM	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
1.000	EA	8817	BORE FRAME AND MACHINE CROS SHEADS, SLEEVE THREE STUFFING BOXES, SLEEVE REAR ING RETAINER	2,132.94	\$2,132.94
1.000	EA	08017024	PI7-26 GASKET	11.00	\$11.00
1.000	EA	7310	INROUND UPS ON ABOVE	7.87	\$7.87
3.000	EA	08447010	ROD-CONNECTING	680.82	\$2,042.46
3.000	EA	08444002	BEARING CRANKPIN 2 -HALVES	50.05	\$152.55
6.000	EA	75102005	CUTTER, STEEL, 1/8X11/2	0.04	\$0.24
1.000	EA	08427003	X4 3/8X26 1/2X1/16 GASKET	11.00	\$11.00
6.000	EA	75670003	Y107-21 RETAINING PLATE	1.90	\$11.40
3.000	EA	08463001	GASKET	3.23	\$9.69
3.000	EA	08411013	RING-LANTERN 2-3/8 BAKELITE	34.70	\$104.10
1.000	EA	08018266	PI7-346 CRANK SHAFT	4,176.43	\$4,176.43



\_\_\_\_\_

QUANTITY SOLD	UN	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
1.000	EA	00017561	GASKET- P17-201	48.10	\$48.10
1.000	EA	00275003	P17-308-GASKET	55.20	\$55.20
1.000	EA	00485033	BROWN&SHARPE NO1 PUMP MODIF ICATION F/ 336P	322.00	\$322.00
3.000	EA	99094007	CLAMP- ROSE, 1 5/8" - 3 1/2 ", IDEAL 6448	1.91	\$5.73
12.000	EA	00406001	GASKET	3.30	\$39.60
1.000	EA	9310	INBOUND MOTOR FREIGHT ON SHAFT, ETC.	321.62	\$321.62
1.000	EA	64182049	VALVE- RELIEF, 1/4 IN, BROWN & SHARPE 713-9001-20	49.72	\$49.72
3.000	EA	342757	PACKING, KVL R 3-3/4 X 4-3/4 X 1-7/8	88.95	\$266.85
1.000	EA	4404216	NIPPLE- PIPE, XH SMLS PRSR TO BLK, 1/4 X CLOSE	1.78	\$1.78
1.000	EA	2230050	SABF, TEMP	69.09	\$69.09
1.000	EA	3219	LOT OF BOLTS, COPPER T86 PARTS AND FITTINGS	12.06	\$12.06
1.000	EA	4417332	CONNECTION- BRASS, 1/4 X 1/4 IN, IMPERIAL 68-1	1.74	\$1.74

END QUESTIONS TO:

NATIONAL-OILWELL

JERWAY 23 EAST

BX 1284 (701) 942-2202

AUFORD CITY

NO 58534



## NATIONAL-OILWELL

DELIVERY TICKET

PAGE 4

\*\*\*\*\*

PLEASE MAIL CHECKS TO:

P. O. BOX 345784

DALLAS, TX

75284-5984

DATE DEL/DHPD 11/12/71 SHIP VIA: DELV

PREPATO

DELIVERY TICKET: 7484-051061

AD: Y

INITIALS: DEZ

CUSTOMER CODE: 6675700

SOLD TO

MURPHY OIL U.S.A. INC.

SHIP TO

MURPHY OIL U.S.A. INC.

200 PEACH STREET

FL DORADO AR

POPLAR, MT

71730

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* DO NOT PAY \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY REEDER

ORDER NO:

LEASE:

WELL/RIG:

BLANKET PO:

TAX LOC: 2700

TAX CODE: 0

QUANTITY SOLD	UN	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
1.000	EA	4537339	SCREW- CAP, BRIGHT FINISH, HEX HEAD NC 5/8X5 IN	0.72	\$0.72
1.000	EA	4436115	ELBOW- 90° STRAIGHT BLACK, 1/2 IN 150# 2000050	0.63	\$0.63
1.000	EA	4404505	PIPE- PIPE, XH SMLS PRSR 1/2 BLK, 1/2 X 1 1/2	1.21	\$1.21
1.000	EA	4119616	DAMPENER- PULSATION, 1/2 IN CON STL, MURPHY PD3164	27.00	\$27.00
1.000	EA	4435749	BUSHING- HEX, FS 1/2 X 1/4 SE	0.72	\$0.72
1.000	EA	4625786	PIPE- PIPE, XH SMLS PRSR 1/4 BLK, 1/4 X 1 1/2	1.82	\$1.82
2.000	EA	4537965	WASHER- LOCK, 3/8 IN MED LN	0.02	\$0.04
2.000	EA	4536200	NUT HEX, HEAVY NC 3/8 I R	0.04	\$0.08
1.000	EA	4532016	SCREW- CAP, BRIGHT FINISH, HEX HEAD NC 1/2X2 IN	0.22	\$0.22
1.000	EA	5121702	SWITCH- SAFETY, W/CPR TUBE VENT, MURPHY L-129	52.65	\$52.65
1.000	EA	4098476	PIPE- PIPE, WELDED STD BL K, 1/4 X 4	0.64	\$0.64
1.000	EA	4435707	BUSHING- HEX, FS 1/4 X 1/8 SE	0.72	\$0.72

END QUESTIONS TO:

NATIONAL OILWELL

100-000 (REV. 9-80)

TELETYPE UNIT

BOX 1286 (701)-842-2902

ATFORD CITY ND 58854

DATE ORDERED: 11/12/91 SHIP VIA: DELV

AD: Y

INITIALS: LKZ

CUSTOMER CODE: 4475200

SOLO TO  
MURPHY OIL U.S.A. INC.

200 PEACH STREET  
EL DORADO AR

71730

SHIP TO  
MURPHY OIL U.S.A. INC.

POPLAR, MT

NATIONAL-OILWELL

DELIVERY TICKET / PAGE 5

\*\*\*\*\*

PLEASE MAIL CHECKS TO:

P. O. BOX 645984

DALLAS, TX

75264-5984

DELIVERY TICKET: 7484-051061

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* P O N O T P A Y \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY REEDE

ORDER NO:

LEASE:

WELL/RIG:

BLANKET PO:

TAX LOC: 2700 TAX CODE: 0

QUANTITY SOLD	UM	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
3.000	EA	08466010	DIAPHRAGM COMP INCL 1 08-46	174.00	\$522.00
6.000	EA	49002925	6-011 2 49-002-925 2 75-509	0.74	\$4.44
3.000	EA	08467006	DIAPHRAGM-GLAND	30.37	\$151.11
6.000	EA	75509994	X1/2-13 THD HEX HUY ESNA NU	17.70	\$106.20
9.000	EA	08466012	WIPER-ROD	7.16	\$64.44
3.000	EA	08412170	PLATE CROSSHEAD BAFFLE	7.83	\$23.49
6.000	EA	75635623	X1/2-13X3/4LG SELF LOCK SDC	1.30	\$7.80
1.000	EA	00017164	HD HT CAPSCREW	98.56	\$98.56
6.000	EA	45143001	P17-65A 70-T O P DRIVE SPRO	0.95	\$7.60
1.000	EA	08200145	CKEY	57.84	\$57.84
33.000	EA	9160	SPROCKET-1/2P KC41 15T TYPE	31.00	\$1,023.00
			8 F7 36-P 36-P A 326-F		
			HOURS LABOR PER FSR'S #		
			21326, 21542, 21762 TO		
			DISASSEMBLE, CLEAN UP,		
			REASSEMBLE 346P OILWELL		

END QUESTIONS TO:

NATIONAL-OILWELL

NO. 1000 (REV. 9-90)

HIGHWAY 29 EAST

BOX 1286 (701)-842-2902

ATFORD CITY ND 58054

DATE DELD/SHPO: 11/12/91 SHIP VIA: DELV

AD: Y

INITIALS: CEZ

CUSTOMER CODE: 6675700

SOLD TO  
MURPHY OIL U.S.A. INC.

200 PEACH STREET  
EL DORADO AR

71/30

# NATIONAL-OILWELL



SHIP TO  
MURPHY OIL U.S.A. INC.

POPLAR, MT

DELIVERY TICKET

PAGE 6

\*\*\*\*\*

PLEASE MAIL CHECKS TO:

P. O. BOX 845934

DALLAS, TX

75284-5934

DELIVERY TICKET: 7484-051061

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* DO NOT PAY \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY REEDE

ORDER NO:

LEASE:

WELL/RIG:

BLANKET PO:

TAX LOC: 2700

TAX CODE: 0

QUANTITY SOLD	UM	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
TRIPLEX					
6.000	EA	08496269	VALVE ASSY SG W/DELTRIN DISC	165.49	\$992.94
			FK-P4-400		
3.000	EA	08804117	CROSSHEAD OVERSIZED	465.32	\$1,395.96
3.000	EA	08412030	PLUNGER- TC 3-3/4	337.60	\$1,012.80
3.000	EA	08441026	ROD-EXTENSION	196.00	\$588.00
3.000	EA	342127	GLAND, SB 3-3/4 X 4-3/4 KVL	185.13	\$555.39
			R		
3.000	EA	342359	FOLLOWER, SPG 3-3/4 X 4-3/4	134.04	\$402.12
			KVLR		
1.000	EA	9310	UPS	6.52	\$6.52
3.000	EA	342269	SPRING, KVLR PKG	109.80	\$329.40
6.000	EA	86486454	PLUG- PIPE, 1/8 STD CI BLACK	0.16	\$0.96
			COUNTERSUNK		
1.000	EA	44229100	BREATHING AIR MAZE	34.00	\$34.00
			GKONS		

SUBTOTAL \$18,799.58

TAX \$0.00

TOTAL \$18,799.58

END QUESTIONS TO:

ATLANTA-OILWELL

IGHWAY 23 EAST

DX 1286 (701)-842-2902

ATLANTA CITY MD 58854

DATE DELD/SHIP: 12/07/91 SHIP VIA: CO. TRK.

AD: Y

INITIALS:

CUSTOMER CODE: 5575700

SOLD TO  
MURPHY OIL U.S.A. INC.

200 PEACH STREET  
EL DORADO AR

71730

SHIP TO  
MURPHY OIL U.S.A. INC.

# NATIONAL-OILWELL

DELIVERY TICKET

PAGE 1

\*\*\*\*\*

PLEASE MAIL CHECKS TO:

P. O. BOX 845934

DALLAS, TX

75284-5984

DELIVERY TICKET: 7484-051480

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* DO NOT PAY \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY REEDE

ORDER NO:

LEASE:

WELL/RIG:

BLANKET PO:

TAX LOC: 2700

TAX CODE: 0

*Out copy  
of tickets*

QUANTITY SOLD	UM	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
1.000	EA	8317	BORE & SLEEVE ONE EXTRA STU FFING BOX TO ACCEPT 3 3/4 KEVLAR FOR 346 P OTLW ELL	381.18	\$381.18

12/7/9

**CUSTOMER COPY**

END QUESTIONS TO:

NATIONAL-OILWELL  
HIGHWAY 23 EAST  
OX 1286 (701)-842-2902  
ATFORD CITY ND 58854

# NATIONAL-OILWELL

DELIVERY TICKET PAGE 1

\*\*\*\*\*

PLEASE MAIL CHECKS TO:

P. O. BOX 845984

DALLAS, TX

75284-5984

DATE DELD/SHPD: 12/16/91 SHIP VIA: DELV

AD: Y

INITIALS: TLC

PREPAID

DELIVERY TICKET: 7484-051624

\*\*\*\*\*

\* DELIVERY TICKET ONLY \*

\* DO NOT PAY \*

\* INVOICE WILL BE MAILED \*

\*\*\*\*\*

ORDERED BY: RAY LEEDE

ORDER NO:

LEASE: EPU

WELL/RIG: 800

BLANKET PO:

TAX LOC: 2700 TAX CODE: 0

CUSTOMER CODE: 6675700

SOLD TO  
MURPHY OIL U.S.A. INC.

SHIP TO  
MURPHY OIL U.S.A. INC.

200 PEACH STREET  
EL DORADO AR

POPLAR, MT

71730

QTY SOLD	UM	ITEM CODE	PART DESCRIPTION	NET RESALE	NET AMOUNT
10.000	EA	9160	HRS. TRAVEL TIME AND LABOR TO INSTALL STUFFING BOXES, PLUNGERS, INTERMEDIATE, & START UP & MONITOR FSR #21566	31.00	\$310.00
234.000	EA	9160	MILES CO. CAR FSR #21566	0.55	\$128.70

SUBTOTAL \$438.70  
TAX \$0.00  
TOTAL \$438.70





#51624

## FIELD SERVICE REPORT

REPORT NO 21566

STORE: 2484

REPRESENTATIVE: T.M.

DATE: 12-16-91

CUSTOMER Murphy Oil

LEASE EPU

LOCATION

WELL NO. 80D

TROUBLE AS REPORTED

Pump

Start up repaired.

TROUBLE AS FOUND

SERVICE PERFORMED OR REMARKS

Travel to loc-on loc 10:00 CDT - Installed  
xest rods - hooked up suction line - Had to loosen & realign  
aid cylinder to get boxes installed - Ready to start pump  
2:00 - Ran for 5 minutes & shut down due to leak at  
check valve - Traveled to 8D lease to inspect other 36A triplex  
turned in 2 hrs. & started unit - Ran for about 40 minutes &  
monitored for any problems - Found none - Traveled to Wc  
Shop

## PARTS USED

N.	PART NO.	DESCRIPTION	UNIT	TOTAL
		2 hrs to inspect pump at 8D		

TIME: FROM 8:00 CDT O'CLOCK TO 8:00 CDT O'CLOCK = 10.0 HOURS @ 31.00 PER HOUR 310.00

LEASE: FROM 20832 TO 20966 = 234 MILES @ .55 PER MILE 128.20

Total Charge 438.20

CUSTOMER Murphy Oil

BY

DATE

OTHER CHARGES WILL BE BILLED BY:

ARGED:

S.O. NO.

J.M. NO.

n No. 1053

CUSTOMER COPY

CUSTOMER COPY

605 REV. 11-69  
D IN U. S. A.

INTERNAL TRANSFER CHARGE

1:50  
2:15



OILWELL

Division of United States Steel Corporation

3209-T-7161

oday  
urphy Oil Corp.

urphy Oil Corp.  
oplar, Montana 57525

CREDIT APPROVED	REQUISITION OR IHO NO.	DATE	
		6-15-72	
COST CODES		BRANCH NO.	ITC NO.
A-Inventory R-Other Operating Cost C-Whse and Shipping Cost			
SHIP CHEAPEST WAY UNLESS OTHERWISE SPECIFIED BELOW:		QUOTATION AND DATE	
FREIGHT <input type="checkbox"/>		P.P. <input checked="" type="checkbox"/>	
CUSTOMER ORDER NUMBER		LEASE OR LOCATION AND WELL NO.	
BD435		EPU SWD	
SHIPPED FROM		DATE SHIPPED	PREPAID <input checked="" type="checkbox"/> COLLECT <input type="checkbox"/>
P.O.U.		SALES OR USE TAX RATE CODE	STATE CODE TO FROM
			83 73

INVOICE NUMBER	UNIT	COMMODITY NO.	STANDARD DESCRIPTION	SOURCE		RATIO	CODE	UNIT COST	EXTENSION	TAX CODE
				QUAN.	LOCATION					
21	ea	08416025	Valve Spring 23-610-06	97			A			22
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			

DEBIT		CREDIT		LOADING NO.	PACKED BY	COST	
BRANCH		BRANCH				A	
NT	BRANCH	SUB.	ACCOUNT	BRANCH	SUB.	AMOUNT	BRANCH INVOICE NO.
				DR. INVOICE DATE	CAR NO. AND INITIALS	PARCEL POST CHG.	
						S	

CKING LIST COPY

CIRCLED ENTRIES INDICATE PARTIAL SHIPMENT. REMAINDER BACK ORDERED.

3

## INTERNAL TRANSFER CHARGE

2605 REV. 9-73



Division of United States Steel Corporation

MURPHY OIL CORP.	CREDIT APPROVED	REQUISITION OR INO NO.	3209-T-8827	
		DATE	6/19/75	
MURPHY OIL CORP. C/O OILWELL DIV. WILLISTON, NORTH DAKOTA	COST CODES		BRANCH NO.	ITC NO.
	A-Inventory B-Other Operating Cost C-Whse and Shipping Cost			
6-20-75	SHIP CHEAPEST WAY UNLESS OTHERWISE SPECIFIED BELOW:		QUOTATION AND DATE	
	FREIGHT <input checked="" type="checkbox"/> P.P. <input type="checkbox"/>			
	CUSTOMER ORDER NUMBER		LEASE OR LOCATION AND WELL NO.	
	B 435		EPUSW # 3	
	SHIPPED FROM		DATE SHIPPED	PREPAID COLLECT
	F.O.B.		SALES OR USE TAX RATE CODE	STATE CODE TO FROM
				83 73

QUANTITY	UNIT	COMMODITY NO.	STANDARD DESCRIPTION	QUAN.	LOCATION	RATIO	CODE	UNIT COST	EXTENSION	TAX CODE
3	EA	08441026	EXTENSION ROD ✓	21-423-18	97		A			22
							B			
							C			
1	EA	08466008	PACKING ✓	21-423-20	97		A			
							B			
							C			
2	EA	08441027	BAFFLE ✓	21-423-19	97		A			
							B			
							C			
3	EA	099094087	CALMP ✓	21-416-20	97		A			
							B			
							C			
2	EA	08406001	GASKET ✓	21-422-03	97		A			
							B			
							C			
2	EA	08416078	VALVE DISC. ✓	21-423-04	97		A			
							B			
							C			
1	EA	08427003	GASKET ✓	21-423-15	97		A			
							B			
							C			
2	EA	20900016	VALVE ASSEMBLY ✓	21-435-065	97		A			
							B			
							C			

DEBIT		CREDIT		LOADING NO.	PACKED BY	COST		
BRANCH		BRANCH				A		
BRANCH	SUB.	ACCOUNT	BRANCH	SUB.	AMOUNT	BRANCH	INVOICE NO.	FILED BY
								CHECKED BY
								BILL OF LADING NO.
								PARCEL POST CHG.
								\$

CIRCLED ENTRIES INDICATE PARTIAL SHIPMENT, REMAINDER BACK ORDERED

1G LIST COPY

③

## INTERNAL TRANSFER CHARGE

IM 2605 REV. 9-73



OILWELL

Division of United States Steel Corporation

MURPHY OIL CORP.	CREDIT APPROVED	REQUISITION OR IHO NO.	3209-T-8827	
		DATE	6/19/75	
MURPHY OIL CORP. C/O OILWELL WILLISTON, NORTH DAKOTA		COST CODES	BRANCH NO.	ITC NO.
		A-Inventory B-Other Operating Cost C-Whse and Shipping Cost		
OR: 6-20-75	SHIP CHEAPEST WAY UNLESS OTHERWISE SPECIFIED BELOW:		QUOTATION AND DATE	
	FREIGHT <input checked="" type="checkbox"/> P.P. <input type="checkbox"/>			
	CUSTOMER ORDER NUMBER	LEASE OR LOCATION AND WELL NO.		
	B435	EPUSW # 3		
	SHIPPED FROM	DATE SHIPPED	PREPAID	COLLECT
	F.O.B.	SALES OR USE TAX RATE CODE	STATE CODE TO FROM	
			83 73	

QUANTITY SHIPPED	UNIT	COMMODITY NO.	STANDARD DESCRIPTION	SOURCE		RATIO	CODE	UNIT COST	EXTENSION	TAX CDD
				QUAN.	LOCATION					
3	EA	08435000	CROSSHEAD 14-222-06		97		A			
							B			
							C			
1	EA	08017024	GASKET 21-420-05		97		A			
							B			
							C			
1	EA	08412103	4 1/2 CERMIC PLUNGERS 21-422-17		97		A			
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			
							A			
							B			
							C			

DEBIT		CREDIT		LOADING NO.	PACKED BY	COST	
CH	BRANCH	ACCOUNT	BRANCH	AMOUNT	BRANCH INVOICE NO.	CHECKED BY	BILL OF LADING NO.
					OR. INVOICE DATE	CAR NO. AND INITIALS	PARCEL POST CHG.
							\$

CIRCLED ENTRIES INDICATE PARTIAL SHIPMENT, REMAINDER BACK ORDERED

PACKING LIST COPY

3




# WATERSAVER COMPANY, INC.

3560 WYNKOOP STREET • DENVER, COLORADO 80216 • (303) 623-4111

Data Sheet SORV - 72

SPECIFICATION  
Physical Properties For  
OIL RESISTANT VINYL (P.V.C.)



	<u>.020 Gauge</u>	<u>.030 Gauge</u>
Tensile	L 2950 T 2600	2800 2450
Elongation %	L 440 T 460	520 520
Modulus 100% PSI	L 1150 T 1050	1050 950
Greaves Tear PSI	L 290 T 300	290 300
Water Extraction	.70% Gain	.36% Gain
Volatility	.97%	.65%
Cold Crack	+ 10° F	
Specific Gravity	1.29	
Color	Grey or Black	

These typical property values are intended as a guide and are not specification limits.

WELL NAME & NO.		FIELD		DISTRICT	
EPU # 80-D		East Poplar		RM	
K. B. ELEVATION	SETTING DATE		DISTANCE K. B. TO CASING HEAD FLANGE		AFE NO.
2069'	August 3, 1984		8.00'		

JOINTS	COND.	SIZE	DESCRIPTION	FEET
98	1	2 7/8', 6.50#, J-rr, 8rd., EUE Tubing		3189.93
1	1	Arrowset Packer		6.93
3	1	2 7/8", 6.50#, J-55, 8rd., EUE Tubing		97.61
			TOTAL	3294.47

6.50

3300.97

Dakota Sand @ 3218'-3250', 3284'-3410', 3462'-3512'

3 joints 2 7/8" coated tubing

P A C K E R	MANUFACTURER		SIZE	WEIGHT	TYPE	MODEL
	I.D.	LENGTH	TOP SET #	BOTTOM SET #	TYPE " J " ASSEMBLY	

CHOKES/SEATING NIPPLES:

SPECIAL EQUIPMENT DESCRIPTION:

# YAPUNCICH, SANDERSON & BROWN LABORATORIES

P. O. BOX 593

BILLINGS, MONTANA

20 N 31st ST

## WATER ANALYSIS REPORT

Lab. No. 1169-W


Field East Poplar County Roosevelt State Montana  
 Well No. 80 Unit Location C 2W NW 3-28N-51E  
 Formation "B-2" Zone Depths 5654.5-5659'  
 Operator Murphy Corporation Date Sampled 7-19-56  
 DST No. 1 Sample Date Analyzed 8-8-56  
 Other Data Tool open 2 hrs. SI 20 min. Recovered 2051' gas, 273' clean  
oil, 182' oily muddy salt water and 1647' salt water. FP 112-1745 lbs.,  
SIP 2988 lbs., HP 3260 lbs. Sample clear colorless water with H<sub>2</sub>S  
present.

Constituents	PPM	MEQ.	MEQ. %	Total Solids in Parts per Million
Sodium	62,953	2738.27	48.72	By evaporation <u>175,000</u>
Calcium	1148	57.29	1.02	After ignition <u>171,800</u>
Magnesium	180	14.80	0.26	Calculated <u>171,862</u>
Sulfate	5983	124.45	2.21	pH <u>7.0</u>
Chloride	101,430	2680.33	47.69	Specific Gravity @ 60°F <u>1.114</u>
Carbonate	0	0	0	Resistivity @ 68°F
Bicarbonate	340	5.58	0.10	ohms/meter <u>0.057</u>
Chloride as NaCl	<u>167,258</u>	PPM.	Total Solids From Resistivity as NaCl	<u>168,918</u> PPM.

NOTE: Sodium and potassium reported as sodium. MEQ. milliequivalents per liter. PPM. parts per million (milligrams per liter). 1 PPM equivalent to 0.0001%.

### WATER ANALYSIS PATTERN

Scale MEQ. Per Unit





# YAPUNCICH, SANDERSON & BROWN LABORATORIES

P. O. BOX 593

BILLINGS, MONTANA

20 N. 31st St.

## WATER ANALYSIS REPORT

Lab. No. 1170-W


Field East Poplar County Roosevelt State Montana  
 Well No. 80 Unit Location C SW NW 3-28N-51E  
 Formation "B-1" Zone Depths 5634-46'  
 Operator Murphy Corporation Date Sampled 7-20-56  
 DST No. 2 Sample Top of Tool Date Analyzed 8-8-56  
 Other Data Tool open 2 hrs. SI 20 min. Recovered 546' gas, 30' clean  
oil, 60' oil and gas-cut mud and 800' salt water. FP 30-440 lbs.,  
SIP 2555 lbs., HP 3260 lbs. Sample clear colorless water.

Constituents	PPM	MEQ.	MEQ. %	Total Solids in Parts per Million
Sodium	96,273	4187.59	49.17	By evaporation <u>251,300</u>
Calcium	1168	58.28	0.68	After ignition <u>248,200</u>
Magnesium	156	12.82	0.15	Calculated <u>249,294</u>
Sulfate	2728	56.74	0.67	pH <u>7.2</u>
Chloride	148,764	4195.14	49.25	Specific Gravity @ 60°F <u>1.160</u>
Carbonate	0	0	0	Resistivity @ 68°F
Bicarbonate	415	6.81	0.08	ohms/meter <sup>2</sup> <u>0.049</u>
Chloride as NaCl <u>245,312</u> PPM.				Total Solids From Resistivity as NaCl <u>247,935</u> PPM.

NOTE: Sodium and potassium reported as sodium. MEQ., milliequivalents per liter. PPM, parts per million (milligrams per liter). 1 PPM equivalent to 0.0001%.

### WATER ANALYSIS PATTERN

Scale MEQ. Per Unit



SPECIALIZING IN CORE, WATER, GAS AND CRUDE OIL ANALYSES

# YAPUNCICH, SANDERSON & BROWN LABORATORIES

P. O. BOX 593

BILLINGS, MONTANA

20 N. 31st St.

## WATER ANALYSIS REPORT

Lab. No. 1171-W


Field East Poplar County Roosevelt State Montana  
 Well No. 80 Unit Location C SW NW 3-28N-51E  
 Formation "B-3" Zone Depths 5669-5686'  
 Operator Murphy Corporation Date Sampled 7-21-56  
 DST No. 3 Sample Top of Tool Date Analyzed 8-8-56  
 Other Data Tool open 2 hrs. SI 20 min. Recovered 795' salt water. No  
show of oil. FP 30-385 lbs., SIP 2935 lbs. Sample clear light amber  
colored water.

Constituents	PPM	MEQ.	MEQ. %	Total Solids in Parts per Million
Sodium	62,432	2715.63	48.65	By evaporation <u>164,000</u>
Calcium	1208	60.28	1.08	After ignition <u>161,700</u>
Magnesium	180	14.80	0.27	Calculated <u>163,499</u>
Sulfate	2874	59.78	1.07	pH <u>7.3</u>
Chloride	96,600	2724.12	48.81	Specific Gravity @ 60°F <u>1.111</u>
Carbonate	0	0	0	Resistivity @ 68°F
Bicarbonate	415	6.81	0.12	ohms/meter <u>0.60</u>
Chloride as NaCl	<u>159,293</u>	PPM.	Total Solids From Resistivity as NaCl	<u>162,089</u> PPM.

NOTE: Sodium and potassium reported as sodium. MEQ. = milliequivalents per liter. PPM = parts per million (milligrams per liter). 1 PPM equivalent to 0.0001%.

### WATER ANALYSIS PATTERN

Scale MEQ. Per Unit



SPECIALIZING IN CORE, WATER, GAS AND CRUDE OIL ANALYSES

# YAPUNCICH, SANDERSON & BROWN LABORATORIES

P. O. BOX 593

BILLINGS, MONTANA

20 N. 31st St

Lab. No. 1172-W

## WATER ANALYSIS REPORT


Field East Poplar County Roosevelt State Montana  
 Well No. 80 Unit Location C SW NW 3-28N-51E  
 Formation Madison "O" Zone Depths 5791.5-5808'  
 Operator Murphy Corporation Date Sampled 8-23-56  
 DST No. 4 Sample Top of Tool Date Analyzed 8-8-56  
 Other Data Tool open 2 hrs. SI 20 min. Recovered 3367' salt water (muddy).  
FP 58-1582 lbs., SIP 3070 lbs., HP 3315 lbs. Sample muddy water.  
Filtrate clear and dark reddish colored.

Constituents	PPM	MEQ.	MEQ. %	Total Solids in Parts per Million
Sodium	25,094	1090.53	46.12	By evaporation <u>70,300</u>
Calcium	1643	81.99	3.47	After ignition <u>68,780</u>
Magnesium	120	9.86	0.41	Calculated <u>69,865</u>
Sulfate	4218	87.73	3.71	pH <u>7.7</u>
Chloride	38,640	1089.65	46.08	Specific Gravity @ 60°F <u>1.048</u>
Carbonate	0	0	0	Resistivity @ 68°F
Bicarbonate	305	5.00	0.21	ohms/meter <u>0.12</u>
Chloride as NaCl <u>63,717</u> PPM.	Total Solids From Resistivity as NaCl <u>67,726</u> PPM.			

NOTE: Sodium and potassium reported as sodium. MEQ = milliequivalents per liter. PPM = parts per million (milligrams per liter). 1 PPM equivalent to 0.0001%

### WATER ANALYSIS PATTERN

Scale MEQ. Per Unit



SPECIALIZING IN CORE, WATER, GAS AND CRUDE OIL ANALYSES

# YAPUNCICH, SANDERSON & BROWN LABORATORIES

P. O. BOX 593

BILLINGS, MONTANA

20 N. 31st St.

Lab. No. 1173-W

## WATER ANALYSIS REPORT


Field East Poplar County Roosevelt State Montana  
 Well No. 80 Unit Location C SW NW 3-28N-51E  
 Formation "A" Zone Depths 5485.5-5496'  
 Operator Murphy Corporation Date Sampled 7-25-56  
 DST No. 5 Sample Top of Tool Date Analyzed 8-8-56  
 Other Data Tool open 2 hrs., SI 20 min. Recovered 200' gas, 45' clean oil,  
45' mid-cut oil and 130' salt water. FP 30-112 lbs., SIP 2990 lbs.,  
HP 3152 lbs. Sample muddy water. Filtrate clear and dark reddish  
colored.

Constituents	PPM	MEQ.	MEQ. %	Total Solids in Parts per Million
Sodium	40,737	1771.94	48.54	By evaporation <u>108,920</u>
Calcium	1069	53.34	1.46	After ignition <u>107,400</u>
Magnesium	0	0	0	Calculated <u>108,846</u>
Sulfate	8925	185.64	5.09	pH <u>8.7</u>
Chloride	57,960	1634.47	44.77	Specific Gravity @ 60°F <u>1.075</u>
Carbonate	96	3.20	0.09	Resistivity @ 68°F
Bicarbonate	120	1.97	0.05	ohms/meter <u>0.088</u>
Chloride as NaCl <u>95,576</u>	PPM.	Total Solids From Resistivity as NaCl <u>104,329</u> PPM.		

NOTE: Sodium and potassium reported as sodium. MEQ. = milliequivalents per liter. PPM: parts per million (milligrams per liter). 1 PPM equivalent to 0.0001%

### WATER ANALYSIS PATTERN

Scale MEQ. Per Unit



SPECIALIZING IN CORE, WATER, GAS AND CRUDE OIL ANALYSES

WESTERN LITHO-PRINT, INC., BILLINGS, MONT

Yapuncich, Sanderson & Brown Laboratories  
Billings, Montana

## LARGE CORE ANALYSIS REPORT

OPERATOR	Murphy Corporation	FIELD	East Poplar	WELL NO.	80 Unit
LOCATION	C SW NW 3-28N-51E	COUNTY	Roosevelt	STATE	Montana
FORMATION	B-1, B-2 & B-3 Zones	DEPTHS	5625-5689.0'	DATE	7-25-56
					LAB. NO 2742

Sample No.	Interval Feet	Footage	PERMEABILITY, Md.				Total Porosity Per Cent	SATURATION % PORE SPACE		Matrix Density	DESCRIPTION
			K Max.	K 90°	K Matrix	K Vertical		Residual Oil	Water		
CORE NO. 1 5652-59' Cut 34' Rec. 33'											
	5625-35.5	10.5	-	-			-	-	-		Anhydrite
B-1 Zone											
1	5635.5-35.8	0.3	0.9	0.4		0.4	7.2	Trace	100.0		OVF Similar to No. 1
	5635.8-36.6	0.8	-	-		-	7.2	Trace	100.0		
2	5636.6-37.3	0.7	*	-	4.8	-	12.5	Trace	78.4		OVF
3	5637.3-38.2	0.9	5.9	4.0		2.2	4.2	Trace	81.0		VF Stylolite
	5638.2-38.5	0.3	-	-		-	4.2	Trace	81.0		OVF Similar to No. 3
4	5638.5-39.3	0.8	3.7	2.1		2.4	6.4	Trace	39.1		VF
5	5639.3-40.2	0.9	4.8	1.6		1.5	7.6	14.5	61.8		
6	5640.2-41.5	1.3	3.4	2.5		1.3	10.6	Trace	90.6		Not Received
	5641.5-42.5	1.0	-	-		-	-	-	-		
	5642.5-53.5	11.0	-	-		-	-	-	-		
B-2 Zone											
7	5653.5-54.0	0.5	17	11		4.4	11.4	7.9	51.8		V
8	5654.0-55.2	1.2	7.4	5.6		7.4	17.4	Trace	50.3		
9	5655.2-55.7	0.5	13	11		6.4	16.7	8.4	54.5		Not Recovered
10	5655.7-56.3	0.6	2.6	2.5		1.7	10.6	1.9	66.0		
11	5656.3-58.0	1.7	9.3	6.1		9.3	15.2	11.2	48.0		
	5658.0-59.0	1.0	-	-		-	-	-	-		
CORE NO. 2 5659-86' Cut 27' Rec. 30'											
12	5659.0-59.7	0.7	2.8	<0.1		3.1	16.7	1.2	61.1		
13	5659.7-60.4	0.7	6.3	4.4		2.2	9.5	Trace	100.0		

Yapuncich, Sanderson & Brown Laboratories  
Billings, Montana

LARGE CORE ANALYSIS REPORT

Murphy Corporation  
East Poplar Field, Roosevelt County, Montana  
Well No. 80 Unit


SUMMARY OF REPORT

	<u>B-1 Zone</u>	<u>B-2 Zone</u>	<u>B-3 Zone</u>
Probable Production	Water	Oil & Water	Water
Estimated Recoverable Oil	-	800 bbls./acre	-
Productive Interval	5635½-41½'	5653½-69'	5675-81'
Porosity Thickness	6 feet	14½ feet	6 feet
Average Maximum Permeability	4.1 md.*	24 md.*	1.2 md.*
Average Porosity	7.9%	14.1%	15.4%
Average Oil Saturation	Trace - 14.5%	2.7%	Trace
Average Water Saturation	79.2%	73.6%	79.9%

\*Average permeability does not include permeability of open fractures. B-1 Zone has 1.8' of open fractures; B-2 Zone 1.3' and B-3 Zone 0.4'.

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

## WELL REWORK RECORD

NAME AND ADDRESS OF PERMITTEE  
Murphy Exploration & Prod. Co.  
P.O. Box 547  
Poplar, MT 59255-0547NAME AND ADDRESS OF CONTRACTOR  
Diamond B Trucking, Inc.  
P.O. Box 567  
Plentywood, MTLOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRESSTATE  
MTCOUNTY  
RooseveltPERMIT NUMBER  
MTS2026-0026

## SURFACE LOCATION DESCRIPTION

1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface Location 1982 ft. from (N/S) N Line of quarter section  
and 761 ft. from (E/W) W Line of quarter section

## WELL ACTIVITY

- ☒
- Brine Disposal
- 
- ☐
- Enhanced Recovery
- 
- ☐
- Hydrocarbon Storage

Lease Name

East Poplar Unit

Total Depth Before Rework

Total Depth After Rework

3575

Date Rework Commenced

Date Rework Completed

## TYPE OF PERMIT

- ☒
- Individual
- 
- ☐
- Area

Number of Wells 1

Well Number

80-D

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

DESCRIBE REWORK OPERATIONS IN DETAIL  
USE ADDITIONAL SHEETS IF NECESSARY

Mechanical Integrity Test Attached

## WIRE LINE LOGS, LIST EACH TYPE

Log Types

Logged Intervals

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Raymond Reede  
District Manager

SIGNATURE

Raymond Reede

DATE SIGNED

5-27-98


UNITED STATES ENVIRONMENTAL PROTECTION AGENCY WASHINGTON, DC 20460		WELL REWORK RECORD																				
NAME AND ADDRESS OF PERMITTEE  Murphy EXPRO P.O. Box 547 Poplar, MT 59255-0547		NAME AND ADDRESS OF CONTRACTOR																				
LOCATE WELL AND OUTLINE UNIT ON SECTION PLAT — 640 ACRES		<div style="display: flex; justify-content: space-between;"> <span>STATE <b>MT</b></span> <span>COUNTY <b>Roosevelt</b></span> <span>PERMIT NUMBER <b>MTS2026-0026</b></span> </div>																				
		SURFACE LOCATION DESCRIPTION <div style="display: flex; justify-content: space-around;"> <span><math>\frac{1}{4}</math> OF SW <math>\frac{1}{4}</math> OF NW <math>\frac{1}{4}</math> SECTION 3</span> <span>TOWNSHIP 28N RANGE 51E</span> </div>																				
		LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT Surface 1982 N Location _____ ft. from (N/S) _____ Line of quarter section and 761 ft. from (E/W) W _____ Line of quarter section																				
		<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 50%;">WELL ACTIVITY</th> <th style="width: 25%;">Total Depth Before Rework</th> <th style="width: 25%;">TYPE OF PERMIT</th> </tr> </thead> <tbody> <tr> <td><input checked="" type="checkbox"/> Brine Disposal</td> <td>3575'</td> <td><input checked="" type="checkbox"/> Individual</td> </tr> <tr> <td><input type="checkbox"/> Enhanced Recovery</td> <td>Total Depth After Rework</td> <td><input type="checkbox"/> Area</td> </tr> <tr> <td><input type="checkbox"/> Hydrocarbon Storage</td> <td>3575'</td> <td>Number of Wells <u>1</u></td> </tr> <tr> <td rowspan="2">Lease Name</td> <td>Date Rework Commenced</td> <td rowspan="2">Well Number</td> </tr> <tr> <td>Date Rework Completed</td> </tr> <tr> <td colspan="2"></td> <td style="text-align: center; font-size: 1.2em;">80-D</td> </tr> </tbody> </table>		WELL ACTIVITY	Total Depth Before Rework	TYPE OF PERMIT	<input checked="" type="checkbox"/> Brine Disposal	3575'	<input checked="" type="checkbox"/> Individual	<input type="checkbox"/> Enhanced Recovery	Total Depth After Rework	<input type="checkbox"/> Area	<input type="checkbox"/> Hydrocarbon Storage	3575'	Number of Wells <u>1</u>	Lease Name	Date Rework Commenced	Well Number	Date Rework Completed			80-D
WELL ACTIVITY	Total Depth Before Rework	TYPE OF PERMIT																				
<input checked="" type="checkbox"/> Brine Disposal	3575'	<input checked="" type="checkbox"/> Individual																				
<input type="checkbox"/> Enhanced Recovery	Total Depth After Rework	<input type="checkbox"/> Area																				
<input type="checkbox"/> Hydrocarbon Storage	3575'	Number of Wells <u>1</u>																				
Lease Name	Date Rework Commenced	Well Number																				
	Date Rework Completed																					
		80-D																				

[illegible][illegible]

DESCRIBE REWORK OPERATIONS IN DETAIL USE ADDITIONAL SHEETS IF NECESSARY	WIRE LINE LOGS, LIST EACH TYPE	
	Log Types	Logged Intervals
Found tubing leak. Ran new packer and hydrotested tubing to 7000#		

### CERTIFICATION

*I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment, (Ref. 40 CFR 144.32).*

NAME AND OFFICIAL TITLE (Please type or print)	SIGNATURE	DATE SIGNED
Raymond Reede District Manager		Sept. 15, 1998




UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
WASHINGTON, DC 20460

## WELL REWORK RECORD

## NAME AND ADDRESS OF PERMITTEE

Murphy EXPRO.  
P.O. Box 548  
Poplar, Mt. 59255-0547

## NAME AND ADDRESS OF CONTRACTOR

H & H Well Service  
P.O. Box 1244  
Poplar, Mt. 59255-1244LOCATE WELL AND OUTLINE UNIT ON  
SECTION PLAT — 640 ACRESSTATE  
MT.

COUNTY

Roosevelt

PERMIT NUMBER

MTS 2026-0026

## SURFACE LOCATION DESCRIPTION

1/4 OF SW 1/4 OF NW 1/4 SECTION 3 TOWNSHIP 28N RANGE 51E

## LOCATE WELL IN TWO DIRECTIONS FROM NEAREST LINES OF QUARTER SECTION AND DRILLING UNIT

Surface 1982' N  
Location \_\_\_\_\_ ft. from (N/S) \_\_\_\_\_ Line of quarter section  
and 761' W  
\_\_\_\_\_ ft. from (E/W) \_\_\_\_\_ Line of quarter section

## WELL ACTIVITY

- ☒
- Brine Disposal
- 
- ☐
- Enhanced Recovery
- 
- ☐
- Hydrocarbon Storage

Lease Name

Total Depth Before Rework

3575'

Total Depth After Rework

3575'

Date Rework Commenced

5-4-99

Date Rework Completed

505099

## TYPE OF PERMIT

- ☒
- Individual
- 
- ☐
- Area
- 
- Number of Wells 1

Well Number

80D

## WELL CASING RECORD — BEFORE REWORK

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## WELL CASING RECORD — AFTER REWORK (Indicate Additions and Changes Only)

Casing		Cement		Perforations		Acid or Fracture Treatment Record
Size	Depth	Sacks	Type	From	To	

## DESCRIBE REWORK OPERATIONS IN DETAIL

USE ADDITIONAL SHEETS IF NECESSARY

Hydrotest tubing. Run and set  
packer.

## WIRE LINE LOGS. LIST EACH TYPE

Log Types

Logged Intervals

## CERTIFICATION

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

NAME AND OFFICIAL TITLE (Please type or print)

Raymond Reede  
District Manager

SIGNATURE

DATE SIGNED

May 10, 1999


Casing/Tubing Annulus  
Pressure Test

Name of Company: Murphy Oil Corporation Date: 9/27/85  
Name of Well: #80-D Permit No.:   
Name of Field East Poplar County: Roosevelt  
Location of Well: SW 1/4 NW 1/4 Sec. 3 T-20N R-57E  
Type of Well: SWD X ER  Total Depth: 5831 Ft.  
Type of Packer: Arrow Set 3531 PBTB  
Packer Setting Depth: 3190  
Surface Casing Size: 13 3/8 From: 0 Ft. To 161 Ft.  
Casing Size: 5 1/2 9 5/8 From: 0 Ft. To 980 Ft.  
Tubing Size: 2 7/8 Amount: 3190  
Time of Test: 1:00 PM Pressure Gauge Reading:

0 Min:	<u>650</u>
5	<u>625</u>
10	<u>625</u>
15	<u>610</u>
20	<u>610</u>
25	<u>610</u>
30	<u>600</u>
35	<u>600</u>
40	<u>600</u>
45	<u>600</u>
50	<u></u>
55	<u></u>
60	<u></u>

Passed Test  
WE Engle

Inspected by: James Rowe  
James Rowe



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION VIII  
999 18th STREET - SUITE 500  
DENVER, COLORADO 80202-2405

MECHANICAL INTEGRITY PRESSURE TEST  
CASING/TUBING ANNULUS

Company Name: Murphy Oil Date: 8/1/77  
Well Name: 44-10-10 Permit No. APR 2016-001  
Field Name: 1st St. Field County:   
Well Location:  Sec 17 T 24N R 51E  
Well Type: SWD 1 ER  2H  Other:   
Type of Packer: Ball Valve Total Depth: 3575 PBD  
Packer Set at (depth): 3190 FT  
Surface Casing Size: 7 7/8" From: 0 FT to 1271 FT  
Casing Size: 5 1/2" From: 0 FT to 5825 FT  
Tubing Size: 3 1/2" Tubing Pressure during Test: 40 psig  
Time of Day: 2:00 -am/pm

	Test #1		Test #2	
0 Min:	<u>470</u>	psig	<u>470</u>	psig
5	<u>470</u>	psig	<u>470</u>	psig
10	<u>470</u>	psig	<u>470</u>	psig
15	<u>470</u>	psig	<u>470</u>	psig
20	<u>470</u>	psig	<u>470</u>	psig
25	<u>470</u>	psig	<u>470</u>	psig
30	<u>470</u>	psig	<u>470</u>	psig
35	<u>470</u>	psig	<u>470</u>	psig
40	<u>470</u>	psig	<u>470</u>	psig
45	<u>470</u>	psig	<u>470</u>	psig
50	<u>470</u>	psig	<u>470</u>	psig
55	<u>470</u>	psig	<u>470</u>	psig
60	<u>470</u>	psig	<u>470</u>	psig

Test Conducted by: James H. H. H.  
Inspected by: John B. L.  
Others Present: Bill M. C. H. H. H.

Mechanical Integrity Test  
Casing or Annulus Pressure Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Implementation Section, 8WM-DW  
999 18th Street, Suite 500, Denver, CO 80202-2466

EPA Witness: Debbie Madison Date 5 / 21 / 98 Time 8:30 am  
Test conducted by: Ray Reede  
Others present: Shane Corne Lloyd Ritland

Well: EPU No. 80-D	Well ID: MTS2026-0026
Field: East Poplar Unit	Company: Murphy EXPRO
Well Location: SW NW Section 3, T28N, R51E	P.O. Box 547
	Address: Poplar, MT 59255

Time	Test #1	Test #2	Test #3
0 min	510 psig	psig	psig
5	510		
10	510		
15	510		
20	510		
25	510		
30 min	510		
35			
40			
45			
50			
55			
60 min			
Tubing press	psig	psig	psig

Result (circle) Pass Fail Pass Fail Pass Fail

Signature of EPA Witness: \_\_\_\_\_  
*See back of page for any additional comments & compliance followup*

Debbie Madison did not witness M.I.T. test on casing. She did witness a pump test with casing open

# Mechanical Integrity Test Casing or Annulus Pressure Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Implementation Section, 8WM-DW  
999 18th Street, Suite 500, Denver, CO 80202-2466

EPA Witness: \_\_\_\_\_ Date 9 / 11 / 98 Time 1:35 ~~PM~~  
Test conducted by: Ray Reede  
Others present: Terry Ross

Well: East Poplar Unit No. 80-D	Well ID: MT52026-0026
Field: East Poplar Unit	Company: Murphy EXPRO
Well Location: SW NW Section 3, T28N, 51E Roosevelt County	Address: P.O. Box 547 Poplar, MT 59255-054

Time	Test #1	Test #2	Test #3
0 min	600# psig	_____ psig	_____ psig
5	590#	_____	_____
10	585#	_____	_____
15	580#	_____	_____
20	577#	_____	_____
25	574#	_____	_____
30 min	570#	_____	_____
35	567#	_____	_____
40	563#	_____	_____
45	560#	_____	_____
50	_____	_____	_____
55	_____	_____	_____
60 min	_____	_____	_____
Tubing press	0 psig	_____ psig	_____ psig

Result (circle) Pass Fail      Pass Fail      Pass Fail

Signature of EPA Witness: Jim Boyter w/EPA and Debbie Madison W/Fort Pec  
*See back of page for any additional comments & compliance followup*  
Tribal EPA gave verbal permission to restart w

# Mechanical Integrity Test Casing or Annulus Pressure Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Implementation Section, 8WM-DW  
999 18th Street, Suite 500, Denver, CO 80202-2466

EPA Witness: Debmadsen Date 5/5/99 Time 1:19  
Test conducted by: H. H. Murphy III  
Others present: Ray Reeder


Well: 80-0	Well ID: MT S2026-00026
Field: EPH	Company: Murphy Oil USA
Well Location: SW, NW, SE 3 T28N R31E	Address: Murphy P.O. Box 547 Poplar MT 59255

Time	Test #1	Test #2	Test #3
0 min	482 psig	psig	psig
5	482		
10	482		
15	482		
20	482		
25	482		
30 min	482		
35			
40			
45			
50			
55			
60 min			
Tubing press	psig	psig	psig

Result (circle) Pass Fail Pass Fail Pass Fail

Signature of EPA Witness: Debmadsen Ray Reeder  
See back of page for any additional comments & compliance followup.

This is the front side of two sides



Mechanical Integrity Test.  
Casing or Annulus Pressure Test

U.S. Environmental Protection Agency  
Underground Injection Control Program, UIC Implementation Section, 8WM-DW  
999 18th Street, Suite 500, Denver, CO 80202-2466

EPA Witness: \_\_\_\_\_ Date \_\_\_\_/\_\_\_\_/\_\_\_\_ Time \_\_\_\_\_ a

Test conducted by: \_\_\_\_\_

Others present: \_\_\_\_\_

Well:	Well ID:
Field:	Company:
Well Location:	Address:

Time	Test #1	Test #2	Test #3
0 min	510 psig	psig	psig
5	510		
10	510		
15	510		
20	515		
25	5		
30 min			
35			
40			
45			
50			
55			
60 min			
Tubing press	psig	psig	psig

Result (circle) Pass Fail Pass Fail Pass Fail


Signature of EPA Witness: \_\_\_\_\_  
See back of page for any additional comments & compliance followup





PRODUCTION &  
INJECTION DATA




East Poplar Unit No. 3-D  
Cathodic Protection Installation  
July, 1980







EPU 80-D





Plan View

- 28 Gauge C.G.I. Sheeting on exterior
- 2 1/2" Blanket Insulation Walls + ceiling
- 28 Gauge Flat G.I. Sheeting on interior
- 4 - 24" x 24" Double hung Windows
- 2" x 4" Studing on 18" centers
- 2" x 6" Trussed Roof
- 1 - 12" Leslie Turbine Ventilator
- 1 - 4' Sliding Door
- 1 - Double door for front of building

Building must be air tight around tank







REVISIONS					
NO.	DATE	BY			
1	1-24-72		19'6" DIAM. X 5" THICK 5-SACK CONCRETE FILLING		
2					
3			DRAWN BY	SCALE NO SCALE	MATERIAL
4			CHK'D	DATE	DRAWING NO.
			TRACED	APP'D	

10:




Subject: F.P.U. S.W. DISP station # N #80-D

From:

Date: 8-9-71 30 mil,  
#040



3" Fiber-glass from Bottom lined  
TIT to INSIDE SALT WATER STATION  
CONNECT to PUMP WITH INTO WOOD  
TANK, CONNECT to 3" FLOW-LINE  
to PUMP OIL to F.B. 34, USE 3"  
F.G. LINE FOR OIL FLOW FROM WOOD  
TANK to PIT





PLUGGING &  
ABANDONMENT